



Hyatt Place

Install Date: 1/28/2014

By:
Cintas Fire Protection
443 Fore Street
Portland, ME 04101
603-717-7300

Notes

Fusible Links:

=> To determine actual fusible link ratings, temperature readings must be taken during peak cooking time.

Hyatt Place:

Note 1 => Nozzle: 1F x1: (Range: 2 burners) nozzle position: 40"48", front edge of burner, nozzle flats parallel with burner front-to-rear centerline, aimed at center

Note 2 => Nozzle: 1N x2: (Pizza Oven) nozzle position: Opposite ends (either corner) of the enclosed cooking chamber, 1 to 3 inches above surface of chain, max 4 inches from opening, aimed diagonally across top of chain.