



**EIGHTH FLOOR FINISH PLAN**  
SCALE: 1/8" = 1'-0"

## GENERAL NOTES

- ALL SHADED AREAS INDICATE "NO WORK" OR "NOT IN CONTRACT" UNLESS OTHERWISE NOTED ON PLAN.
- ALL HARDWARE TO MATCH BUILDING STANDARD FINISH, UNLESS OTHERWISE NOTED.
- ALL MILLWORK TO BE SHOP FINISHED. ALL PAINTED MILLWORK TO BE SHOP SPRAYED PAINTED LOW GLOSS LACQUER FINISH.
- FLOOR TRANSITIONS SHALL OCCUR AT THE CENTERLINE OF DOOR, UNLESS OTHERWISE NOTED.
- FLOORING CONTRACTOR TO PROVIDE AND CONTINUE SCHEDULED FLOORING FROM PARTITION TO PARTITION AND UNDER MILLWORK UNLESS OTHERWISE NOTED.
- PROVIDE HIGH GLOSS WAX FINISH ON ALL SCHEDULED VCT FLOORING, WITH THE EXCEPTION OF ALL ANTI-STATIC TILE.
- DO NOT PROVIDE SCHEDULED RUBBER/VINYL BASE ON MILLWORK PLASTIC LAMINATE TOE-KICK TYPICAL. REFER TO MILLWORK SECTIONS/DETAILS SHEET A4.01.
- SEAM SEALER REQUIRED AT ALL CARPET SEAMS IN ACCORDANCE WITH THE CRI INSTALLATION INSTRUCTIONS
- PROVIDE 4" COVE BASE AT ALL CARPETED AREAS AND ALL HARDSURFACE FLOORING AREAS UNLESS OTHERWISE NOTED ON PLANS.
- FINISH SYSTEMS DESCRIBE THE FINISH SPECIFICATION FOR THE VERTICAL SURFACE AT ALL ITEMS PLACED ON A PARTITION. IF DISCREPANCY OCCURS, CONTACT THE ARCHITECT FOR CLARIFICATION PRIOR TO STARTING WORK WITHIN THE SUBJECT AREA.
- ALL SURFACES SHALL BE PROPERLY PREPARED AS REQUIRED TO RECEIVE SPECIFIED FINISH INCLUDING WALLCOVERING, FLOORING, PAINT, STONE, ETC. EACH FINISH SUBCONTRACTOR SHALL INSPECT SURFACES TO RECEIVE FINISHES AND REPORT UNFAVORABLE CONDITIONS AND SUBSTRATES TO THE GENERAL CONTRACTOR BEFORE PROCEEDING WITH THE WORK. GENERAL CONTRACTOR SHALL NOTIFY ARCHITECT IMMEDIATELY. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR REWORK OF ANY SUBSTRATES SEEMED UNACCEPTABLE FOR FINISH APPLICATION.
- ALL GYPSUM BOARD CEILINGS SHALL BE PAINTED SHERWIN WILLIAMS SWT005 PURE WHITE FLAT, UNLESS OTHERWISE NOTED ON PLANS.

## FINISH SYSTEMS

- |   |                                     |  |
|---|-------------------------------------|--|
| 1 | BASE:<br>DOORS:<br>FRAMES:<br>WALLS | B-1<br>STAINED<br>P-3 ENAMEL<br>P-1 EGGSHELL |
| 2 | BASE:<br>DOORS:<br>FRAMES:<br>WALLS | B-1<br>STAINED<br>P-3 ENAMEL<br>P-2 EGGSHELL |
| 3 | BASE:<br>DOORS:<br>FRAMES:<br>WALLS | B-1<br>STAINED<br>P-3 ENAMEL<br>WC-1         |
| 4 | BASE:<br>DOORS:<br>FRAMES:<br>WALLS | B-1<br>STAINED<br>P-3 ENAMEL<br>P-4 EGGSHELL |

## FINISH SPECIFICATIONS

### CARPET

C-1 MFR: SHAW CONTRACT  
STYLE: JAVA 5A035  
COLOR: CHOCOLATE FLOWER 35500  
FOR SPECIAL PRICING AND DELIVERY  
CONTACT: LINDA SULLIVAN  
617.283.0867

### PAINT

P-1 MFR: SHERWIN WILLIAMS  
COLOR: BASKET BEIGE  
NO.: SW6143

P-2 MFR: SHERWIN WILLIAMS  
COLOR: SMOKEHOUSE  
NO.: SWT040

P-3 MFR: SHERWIN WILLIAMS  
COLOR: URBAN BRONZE  
NO.: SWT048

P-4 MFR: SHERWIN WILLIAMS  
COLOR: RETREAT  
NO.: SW6207

### VINYL BASE

B-1 MFR: ROPPE  
COLOR: BLACK BROWN  
NO.: 193

### VINYL COMPOSITION TILE

VCT-1 MFR: ARMSTRONG  
STYLE: EXECELON STONETECH  
COLOR/NO.: 52143 SANDSTONE TAN

VCT-2 MFR: ARMSTRONG  
STYLE: ANTI-STATIC  
COLOR/NO.: 51950 MARBLE BEIGE

### PLASTIC LAMINATE

PL-1 COUNTERTOPS  
MFG: WILSONART  
COLOR: EVENING TIGRIS  
NO.: 4674-60

PL-2 CABINETS  
MFG: WILSONART  
COLOR: SLATE GREY  
NO.: D91-60

### VINYL WALL COVERING

WC-1 MFR: WOLF GORDON WALLCOVERING  
STYLE: VINYL  
COLOR/NO.: VB 41754

### Revisions:

Description:	Date:
01 Clarification 01	12.17.13

Issue date: 05.11.15  
Project number: 14-019

Eighth Floor  
Plan