EIGHTH FLOOR FINISH PLAN

SCALE: 1/8" = 1'-0"

GENERAL NOTES

1. ALL SHADED AREAS INDICATE "NO WORK" OR "NOT IN CONTRACT" UNLESS OTHERWISE NOTED ON PLAN.

2. ALL HARDWARE TO MATCH BUILDING STANDARD FINISH, UNLESS OTHERWISE NOTED.

3. ALL MILLWORK TO BE SHOP FINISHED. ALL PAINTED MILLWORK TO BE SHOP SPRAYED PAINTED LOW GLOSS LACQUER FINISH.

4. FLOOR TRANSITIONS SHALL OCCUR AT THE CENTERLINE OF DOOR, UNLESS OTHERWISE NOTED.

5 FLOORING CONTRACTOR TO PROVIDE AND CONTINUE SCHEDULED FLOORING FROM PARTITION TO PARTITION AND UNDER MILLWORK UNLESS OTHERWISE NOTED.

6. PROVIDE HIGH GLOSS WAX FINISH ON ALL SCHEDULED VCT FLOORING, WITH THE EXCEPTION OF ALL ANTI-STATIC TILE.

7. DO NOT PROVIDE SCHEDULED RUBBER/VINYL BASE ON MILLWORK PLASTIC LAMINATE TOE-KICK TYPICAL. REFER TO MILLWORK SECTIONS/DETAILS SHEET A4.01.

8. SEAM SEALER REQUIRED AT ALL CARPET SEAMS IN ACCORDANCE WITH THE CRI INSTALLATION INSTRUCTIONS

9. PROVIDE 4" COVE BASE AT ALL CARPETED AREAS AND ALL HARDSURFACE FLOORING AREAS UNLESS OTHERWISE NOTED ON PLANS.

9. FINISH SYSTEMS DESCRIBE THE FINISH SPECIFICATION FOR THE VERTICAL SURFACE AT ALL ITEMS PLACED ON A PARTITION. IF DISCREPANCY OCCURS, CONTACT THE ARCHITECT FOR CLARIFICATION PRIOR TO STARTING WORK WITHIN THE SUBJECT AREA.

10. ALL SURFACES SHALL BE PROPERLY PREPARED AS REQUIRED TO RECEIVE SPECIFIED FINISH INCLUDING WALLCOVERING, FLOORING, PAINT, STONE, ETC. EACH FINISH SUBCONTRACTOR SHALL INSPECT SURFACES TO RECEIVE FINISHES AND REPORT UNFAVORABLE CONDITIONS AND SUBSTRATES TO THE GENERAL CONTRACTOR BEFORE PROCEEDING WITH THE WORK. GENERAL CONTRACTOR SHALL NOTIFY ARCHITECT IMMEDIATELY. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR REWORK OF ANY SUBSTRATES SEEMED UNACCEPTABLE FOR FINISH APPLICATION.

11. ALL GYPSUM BOARD CEILINGS SHALL BE PAINTED SHERWIN WILLIAMS SW1005 PURE WHITE FLAT, UNLESS OTHERWISE NOTED ON PLANS.

FINISH SYSTEMS

1	BASE:	B-1
	DOORS:	STAINED
	FRAMES:	P-3 ENAMEL
	WALLS	P-1 EGGSHELL
2	BASE:	B-1
	DOORS:	STAINED
	FRAMES:	P-3 ENAMEL
	WALLS	P-2 EGGSHELL
3	BASE:	B-1
	DOORS:	STAINED
	FRAMES:	P-3 ENAMEL
	WALLS	WC-1
4	BASE:	B-1
	DOORS:	STAINED
	FRAMES:	P-3 ENAMEL
	WALLS	P-4 EGGSHELL

FINISH SPECIFICATIONS

CARPET

C-1 MFR: SHAW CONTRACT
STYLE: JAVA 5A035
COLOR: CHOCOLATE FLOWER 35500
FOR SPECIAL PRICING AND DELIVERY
CONTACT: LINDA SULLIVAN
617.283.0867

PAINT

P-1 MFR: SHERWIN WILLIAMS
COLOR: BASKET BEIGE
NO.: SW6143

P-2 MFR: SHERWIN WILLIAMS
COLOR: SMOKEHOUSE
NO.: SW7040

P-3 MFR: SHERWIN WILLIAMS
COLOR: URBAN BRONZE
NO.: SW7048

P-4 MFR: SHERWIN WILLIAMS
COLOR: RETREAT
NO.: SW6207

VINYL BASE

B-1 MFR: ROPPE
COLOR: BLACK BROWN
NO.: 193

VINYL COMPOSITION TILE

VCT-1 MFR: ARMSTRONG
STYLE: EXECELON STONETECH
COLOR/NO.: 52143 SANDSTONE TAN

VCT-2 MFR: ARMSTRONG
STYLE: ANTI-STATIC
COLOR/NO.: 51950 MARBLE BEIGE

PLASTIC LAMINATE

PL-1 COUNTERTOPS
MFG: WILSONART
COLOR: EVENING TIGRIS
NO.: 4674-60

PL-2 CABINETS
MFG: WILSONART
COLOR: SLATE GREY
NO: D91-60

VINYL WALL COVERING

WC-1 MFR: WOLF GORDON WALLCOVERING
STYLE: VINYL
COLOR/NO.: VB 41754

RESURGAM CITY OF PORTLAND, MAINE

Inspections Division
Date: 06/03/15

636.661.5059
shay@iia-llc.com

Construction Documents For:
The Hanover Insurance Group
Portland Office
2 Monument Square - Eighth Floor
Portland, Maine

Revisions:

	Description:	Date:
01	Clarification 01	12.17.13

Issue date: 05.11.15
Project number: 14-019

Eighth Floor Plan

A2.02