



REVISIONS

CONSTRUCTION DOCUMENTS

BANK OF AMERICA - HOME LOANS

BANK OF AMERICA

1 MONUMENT SQUARE, PORTLAND ME

TITLE
 DRAWING INDEX, LOCATION MAP, AND PROJECT INFORMATION

DATE **JOB NO.**
 06/29/17 17.0239

DRAWING NO.
A00.00

ISSUED FOR CONSTRUCTION

ABBREVIATIONS		POWER TEL-DATA LEGEND		CONSTRUCTION LEGEND		GENERAL NOTES		DRAWING LIST	
& +/-	AND PLUS OR MINUS. DIMENSION SHOWN SHALL VARY AS CONDITIONS REQUIRE WITH A TOLERANCE OF LESS THAN 2" UNLESS NOTED OTHERWISE. ADVISE ARCHITECT IN CASES WHERE ACTUAL DIMENSIONS EXCEED TOLERANCE	LAV	LAVATORY		WALL MOUNTED DUPLEX RECEPTACLE		REFERENCE TO PARTITION TYPE	1.	THE WORK PERFORMED UNDER THIS CONTRACT SHALL BE DONE IN STRICT ACCORDANCE WITH THE RULES AND REGULATIONS OF THE BUILDING MANAGEMENT AND ALL APPLICABLE STATE, LOCAL AND FEDERAL CODES AND REGULATIONS.
AC	AIR CONDITIONING	LB	POUND LENGTH		WALL MOUNTED QUAD RECEPTACLE		SEE A9.01 FOR DOOR TYPES (X=EXISTING DOOR)	2.	THE GC SHALL REVIEW ALL DOCUMENTS, DIMENSIONS AND FIELD CONDITIONS AND CONFIRM THAT WORK IS AS SHOWN. ANY DISCREPANCIES, ERRORS AND OMISSIONS DISCOVERED IN THE CONSTRUCTION DOCUMENT PACKAGE SHALL BE IMMEDIATELY BROUGHT TO THE ATTENTION OF DYER BROWN ARCHITECTS PRIOR TO PROCEEDING WITH RELATED WORK.
AB	ANCHOR BOLT	MAS	MASONRY		WALL MOUNTED DEDICATED DUPLEX RECEPTACLE		INTERIOR ELEVATIONS	3.	THE GC SHALL DIRECT ALL CONSTRUCTION RELATED CORRESPONDENCE REGARDING THIS PROJECT TO DYER BROWN ARCHITECTS. DYER BROWN ARCHITECTS WILL COORDINATE THE DISTRIBUTION OF ALL INFORMATION TO THE APPLICABLE PARTIES, INCLUDING THE OWNER AND PROPERTY MANAGER.
ACT	ACOUSTICAL CEILING TILE	MATL	MATERIAL		WALL MOUNTED GROUND FAULT INTERRUPTER		DETAILS/SECTIONS	4.	UNLESS OTHERWISE NOTED, THE GC SHALL BE RESPONSIBLE FOR THE COMPLETE SCOPE OF MATERIALS AND LABOR AS REQUIRED TO COMPLETE THE CONSTRUCTION AS INDICATED IN THE CONSTRUCTION DOCUMENTS.
AFF	ABOVE FINISHED FLOOR	MECH	MECHANICAL		WALL MOUNTED DUPLEX RECEPTACLE WITH USB PORT		ROOM NAMES	5.	ALL WORK SHALL CONFORM TO THE CONTRACT DOCUMENTS WHICH INCLUDE THE DRAWINGS, SPECIFICATIONS, ALL ADDENDA, BULLETINS AND CHANGE ORDERS.
ALUM.	ALUMINUM	MIN	MINIMUM		WALL MOUNTED VOICE (TELEPHONE) JACK		ELEVATION/GRADE	6.	IN CASE OF CONFLICT BETWEEN THE ARCHITECT'S AND ENGINEER'S DRAWINGS, THE ARCHITECT SHALL BE IMMEDIATELY NOTIFIED FOR CLARIFICATION.
AP	ACCESS PANEL	MISC	MISCELLANEOUS		WALL MOUNTED VOICE/DATA JACK		REVISION	7.	SIMILAR OR "SIM" MEANS COMPATIBLE CHARACTERISTICS FOR CONDITIONS NOTIFIED. VERIFY DIMENSIONS AND ORIENTATION ON PLANS AND ELEVATIONS.
APPROX.	APPROXIMATELY	MOC	MASONRY OPENING		FLOOR MOUNTED DUPLEX OUTLET		ALIGN WITH ESTABLISHED SURFACES	8.	WORK AREAS ARE TO REMAIN SECURE AND LOCKABLE DURING CONSTRUCTION. GC SHALL COORDINATE WITH OWNER TO ENSURE SECURITY.
ARCH	ARCHITECTURAL	MTL	METAL		FLOOR MOUNTED QUAD OUTLET		FIRE EXTINGUISHER WITHOUT CABINET	9.	GC SHALL PROVIDE FINAL CLEANING. FINAL CLEANING INCLUDES, BUT IS NOT LIMITED TO, CLEANING OF ALL WALLS, GLASS, GLOSSY SURFACES, FLOOR, DOORS, FRAMES, WALL BASE & LIGHT FIXTURES, PER MANUFACTURERS RECOMMENDED CLEANING INSTRUCTIONS.
BL	BASE LINE	N	NEW		FLOOR MOUNTED COMBINATION VOICE DATA OUTLET		FIRE EXTINGUISHER CABINET	10.	THE GC SHALL MAINTAIN, FOR THE ENTIRE DURATION OF THE WORK, ALL EXITS, EXIT LIGHTING, FIRE PROTECTIVE DEVICES AND ALARMS IN CONFORMANCE WITH ALL APPLICABLE CODES AND TO THE SATISFACTION OF THE LOCAL FIRE INSPECTOR.
BLDG	BUILDING	NIC	NOT IN CONTRACT		FLOOR MOUNTED TELEPHONE OUTLET		FIRE ALARM PULL	11.	ALL WORK SHALL BE COORDINATED WITH THE BUILDING OWNER INCLUDING SCHEDULING TIME AND LOCATIONS FOR DELIVERIES, BUILDING ACCESS, USE OF BUILDING FACILITIES, USE OF BUILDING PHONE LINES, ETC.
BLKG	BLOCKING	NTS	NOT TO SCALE		FLOOR MOUNTED DATA OUTLET		FIRE ALARM PULL HORN	12.	ALL MANUFACTURED ARTICLES, MATERIALS AND EQUIPMENT SHALL BE APPLIED, INSTALLED, CONNECTED, ERECTED, CLEANED AND CONDITIONED PER MANUFACTURER'S INSTRUCTIONS. IN THE CASE OF DIFFERENCES BETWEEN THE MANUFACTURER'S INSTRUCTIONS AND THE CONTRACT DOCUMENTS, THE GC SHALL NOTIFY THE ARCHITECT BEFORE PROCEEDING.
BPL	BASE PLATE	O/O	OUTSIDE TO OUTSIDE		SECURITY SYSTEM CARD READER		CENTERLINE	13.	GC TO VERIFY THAT CONCRETE FLOORS (IF EXISTING) ARE LEVEL, SMOOTH AND FREE FROM SCALING. GC TO REPORT ANY VARIATIONS IN FLOOR LEVEL GREATER THAN 1/4" IN 10'-0".
BRK	BRICK	O/O	OVERALL		CABLE TV OUTLET		EXISTING CONSTRUCTION	14.	BEFORE PURCHASE OR FABRICATION, AND WITHIN PROJECT SCHEDULE, GC SHALL FIRST REVIEW AND THEN SUBMIT CATALOG CUTS, SHOP DRAWINGS AND SAMPLES FOR ARCHITECT'S REVIEW. THIS INCLUDES ALL DOORS, FRAMES, HARDWARE, GLAZING, MILLWORK, LIGHTING, FIXTURES AND ALL FINISH MATERIALS. THE ARCHITECT WILL REVIEW SUBMITTALS FOR DESIGN INTENT ONLY. CONSTRUCTION AND FABRICATION DETAILS AND INTEGRITY ARE THE RESPONSIBILITY OF THE CONTRACTOR.
BS	BUILDING STANDARD	O/O	ON CENTER		DOOR CONTACT DEVICE		EXISTING TO BE DEMOLISHED	15.	BLOCKING AND OTHER CONCEALED SUPPORT REQUIRED FOR THE INTEGRITY OF CONSTRUCTION SHALL BE PROVIDED AT ALL BUILT-IN CONSTRUCTION.
CH	COUNTER HEIGHT	O/O	OUTSIDE DIAMETER		PUSH BUTTON DOOR RELEASE		NEW CONSTRUCTION	16.	DO NOT SCALE DRAWINGS. USE INDICATED OR CALCULATED DIMENSIONS AND ELEVATIONS ONLY. IMMEDIATELY NOTIFY ARCHITECT OF ANY LAYOUT CONDITION THAT IS IN CONFLICT WITH WRITTEN DIMENSIONS, AND DO NOT PROCEED WITH PORTION OF LAYOUT UNTIL DISCREPANCIES ARE RESOLVED.
CJ	CONTROL JOINT	O/F	OUTSIDE FACE		AV OUTLET		TYPICAL DIMENSION AT DOOR JAMB	17.	GC SHALL, IN THE WORK OF ALL TRADES, PERFORM ANY AND ALL CUTTING, PATCHING, REPAIRING, RESTORING AND THE LIKE NECESSARY TO COMPLETE THE WORK AND TO RESTORE ANY DAMAGED OR AFFECTED SURFACES RESULTING FROM THE WORK OF THIS CONTRACT TO THE ORIGINAL CONDITION.
CL	CENTER LINE	O/FACI	OWNER FURNISHED & CONTRACTOR INSTALLED		SECURITY CAMERA			18.	EACH CONTRACTOR SHALL LEAVE THE SITE IN A NEAT, CLEAN AND ORDERLY CONDITION UPON CONCLUSION OF DAILY WORK. ALL WASTE RUBBISH, RECYCLING AND EXCESS MATERIAL SHALL BE REMOVED FROM THE SITE PROMPTLY AND DISPOSED OF IN APPROPRIATE FASHION.
CL GRID	CENTER GRID AS SHOWN	O/FH	OWNER FURNISHED & INSTALLED		WIRELESS ACCESS POINT			19.	ALL FIRE RATED PARTITIONS, SMOKE BARRIERS, AND OTHER SIMILAR PROTECTED OPENINGS SHALL BE IDENTIFIED, AT NO LESS THAN 30' INTERVALS WITH STENCILED 1/2" LETTERING, WITH THE FOLLOWING OR EQUIVALENT TEXT: "FIRE AND/OR SMOKE BARRIER-PROTECT ALL OPENINGS", IN ACCORDANCE WITH IBC 2009, CHAPTER 7, SEC. 703.6.
CL TILE	CENTER TILE AS SHOWN	O/G	OPENING		JUNCTION BOX				
CLG	CEILING	O/P	OPPOSITE		THERMOSTAT				
CLO	CLOSET	OZ	OUNCE						
CLR	CLEAR DIMENSION	P-LAM	PLASTIC LAMINATE						
CMU	CONCRETE MASONRY UNIT	PIH	PARTIAL HEIGHT						
CO	CLEAN OUT	PARA	PARALLEL						
COL	COLUMN	PERP	PERPENDICULAR						
CONC.	CONCRETE	PLUMB	PLUMBING						
CONSTR	CONSTRUCTION	PNL	PANEL						
CONT	CONTINUOUS	PREF	PREFINISHED						
CORR	CORRIDOR	PSF	POUNDS / SQUARE FOOT						
CPT	CARPET	PSI	POUNDS / SQUARE INCH						
CR	CHAIR RAIL	PT	PAINT						
CT	CERAMIC TILE	PTD	PAINTED						
DEPT	DEPARTMENT	QT	QUARRY TILE						
DIAG	DIAGONAL	R	EXISTING RELOCATED						
DIM	DIMENSION	RB	RUBBER BASE						
DL	DOCK LEVELER	RCP	REFLECTED CEILING PLAN						
DS	DOWNSPOUT	RD	ROAD						
DWG	DRAWING	RD	ROAD DRAIN						
E	EXISTING	REC	RECEPTACLE / ELECTRICAL						
EA	EACH	REF	REFERENCE						
EJ	EXPANSION JOINT	REINF	REINFORCING						
ELE	ELEVATION	REQD	REQUIRED						
ELEC	ELECTRICAL	RESIL	RESILIENT FLOOR						
ELEV	ELEVATOR	REV	REVISION						
EMR	ELEVATOR MACHINE ROOM	RF	RIGID FRAME						
ENCL	ENCLOSURE	RO	ROUGH OPENING						
ENG	ENGINEER	RWL	RAIN WATER LEADER						
EQ	EQUAL	S&P	SHELF & POLE						
EQUIP	EQUIPMENT	SAB	SOUND ATTENUATION BLANKET						
ETR	EXISTING TO REMAIN	SC	SOLID CORE						
EXP	EXPOSED	SECT	SECTION						
EXT	EXTERIOR	SF	SQUARE FEET						
F/H	FULL HEIGHT	SIM	SIMILAR						
FB	FACE OF BRICK	SPEC	SPECIFICATION						
FD	FLOOR DRAIN	SPR	SPRINKLER						
FDN	FOUNDATION	SS	STAINLESS STEEL						
FEC	FIRE EXTINGUISHER CABINET	ST	STONE TILE						
FHC	FIRE HOSE CABINET	STB	STONE TILE BASE						
FIN	FINISH	STC	STONE TILE COUNTERTOP						
FL	FLOOR	STD	STANDARD						
FLRG	FLOORING	STL	STEEL						
FLUOR	FLUORESCENT	STN	STAIN						
FO	FINISHED OPENING INSIDE TO INSIDE	STRUC	STRUCTURAL						
FRT	FIRE RETARDANT TREATED	SUSP	SUSPENDED						
FTG	FOOTING	SW	SHOP WELD						
FW	FIELD WELD	SYMM	SYMMETRICAL						
FWC	FABRIC WALL COVERING	TELE	TELEPHONE						
GA	GAUGE	THRU	THROUGH						
GALV	GALVANIZED	TOIL	TOILET						
GB	GRAB BAR	TYP	TYPICAL						
GC	GENERAL CONTRACTOR	UC	UNDERCUT						
GL	GLASS	UON	UNLESS OTHERWISE NOTED						
GT	GROUT	VB	VINYL BASE						
GWB	GYPSPUM WALL BOARD	VCT	VINYL COMPOSITION TILE						
GWB CJ	GYPSPUM CONTROL JOINT	VERT	VERTICAL						
HB	HOSE BIBB	VIF	VERIFY IN FIELD						
HC	HOLLOW CORE	VIN	VINYL						
HD	HEAVY DUTY	VP	VENT PIPE						
HDCP	HANDICAP	VTR	VENT THRU ROOF						
HDWR	HARDWARE	VWC	VINYL WALL COVERING						
HM	HOLLOW METAL	W	WITH						
HORIZ	HORIZONTAL	W/O	WITHOUT						
HP	HIGH POINT	WC	WATER CLOSET						
HT	HEIGHT	WD	WOOD						
HWH	HOT WATER HEATER	WG	WIRE GLASS						
IN	INCHES	WP	WORKING POINT						
INFO	INFORMATION	WT	WEIGHT						
KD	KNOCK DOWN	WT	WINDOW TREATMENT						
		WWF	WELDED WIRE FABRIC						