EQUIPMENT PLAN 1 / A-1
SCALE: 1/4"=1'-0"

AAV SCOPE OF WORK NOTES:

1. **MEET POINT:** EXISTING TELCO BACKBOARD INSIDE GROUND FLOOR TELCO ROOM.
2. **FIBER RUN:** PROPOSED FAIRPOINT FIBER TO ORIGINATE FROM EXISTING TELCO ROOM AND RUN WITHIN EXISTING 4"ø RGS ABOVE GROUND CONDUIT TO EXISTING PULL BOX ON 14TH FLOOR. (APPROX. 350'±)
3. PROPOSED FIBER TO CONTINUE FROM EXISTING PULL BOX WITHIN PROPOSED 2"ø RGS ABOVE GROUND CONDUIT TO PROPOSED METRONID MOUNTED ON PROPOSED BACKBOARD INSIDE SPRINT LEASE AREA. (APPROX. 80'±)
4. SPRINT TO PROVIDE MULE TAPE AND INNERDUCT FOR THE FIBER. (APPROX. 430'±)
5. PROPOSED METRONID MOUNTED ON PROPOSED 2'x3' BACKBOARD INSIDE SPRINT LEASE AREA BY FAIRPOINT.
6. PROPOSED FIBER TO CONTINUE FROM PROPOSED METRONID AND RUN WITHIN PROPOSED 2"ø RGS ABOVE GROUND CONDUIT TO PROPOSED MM-BTS CABINET (APPROX. 10'±)
7. PROPOSED FIBER FROM EXISTING TELCO ROOM TO PROPOSED MM-BTS CABINET (APPROX. 440'± TOTAL)

A. **POWER RUN:** PROPOSED INSTALL 1¼"ø RGS CONDUIT FROM THE PROPOSED MM-BTS TO PROPOSED METRONID (APPROX. 10'±) (DC POWER CONDUCTORS *TBD BY SPRINT GC*)

CALL
BEFORE YOU DIG
CALL TOLL FREE 888-DIG-SAFE

SPRINT TO PROVIDE MULE TAPE AND INNERDUCT IN EXISTING/PROPOSED CONDUIT PATHS UNLESS OTHERWISE NOTED

SITE PLAN 2 / A-1
SCALE: 1/32"=1'-0"

Sprint VISION
1 INTERNATIONAL BLVD, SUITE 800
MAHWAH, NJ 07495
TEL: (800) 357-7641

Alcatel·Lucent
1 ROBBINS ROAD
WESTFORD, MA 01886
TEL: (978) 952-1600

Hudson Design Group LLC
1600 OSGOOD STREET
BUILDING 20 NORTH, SUITE 3090
N. ANDOVER, MA 01845
TEL: (978) 557-5553
FAX: (978) 336-5586

CHECKED BY: KB

APPROVED BY: DPH

SUBMITTALS

REV.	DATE	DESCRIPTION	BY
0	09/12/12	FOR REVIEW	TH

SITE NUMBER:
NM03XC067

SITE NAME:
ONE CITY CENTER
PORTLAND

SITE ADDRESS:
1 CITY CENTER
PORTLAND, ME 04101

SHEET TITLE
COMPOUND PLAN

SHEET NUMBER
A-1

RESURGAM CITY OF PORTLAND, MAINE

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 07/26/13