# INTERIOR FINISH LEGEND

**100313**

**ABSOLUTE HEALTH CHIROPRACTIC**

| ABBREVIATIONS | | | |
|---|---|---|---|
| C | CARPET | T | TILE |
| G | GROUT | TBS | TO BE SELECTED |
| N/A | NOT APPLICABLE | VCB | VINYL COVE BASE |
| P | PAINT | VCT | VINYL COMPOSITE TILE |
| PL | PLASTIC LAMINATE | VSB | VINYL STRAIGHT BASE |
| R | RESILIENT/ RUBBER/ RUBBER TREAD | WC | WALL COVERING (VINYL/ PAPER) |
| SF | SQUARE FEET | WCB | WALL COVERING BORDER (VINYL/ PAPER) |
| SS | SOLID SURFACE/ NATURAL STONE | WD | WOOD |
| SYD | SQUARE YARD(S) | | |

| CODE | MATERIAL | MANUFACTURER | PRODUCT, STYLE AND COLOR | FINISH | REMARKS/ NOTES |
|---|---|---|---|---|---|
| C1 | CARPET | SHAW CONTRACT GROUP | TO BE DETERMINED | FACTORY | |
| SV1 | SHEET VINYL FLOOR | TO BE DETERMINED | TO BE DETERMINED | FACTORY | |
| VCB1 | VINYL COVE BASE | JOHNSONITE | TO BE DETERMINED | FACTORY | |
| P1 | PAINT | SHERWIN WILLIAMS | TO BE DETERMINED | SEMI-GLOSS | |
| P2 | PAINT | SHERWIN WILLIAMS | TO BE DETERMINED | EGGSHELL | |
| P3 | PAINT | SHERWIN WILLIAMS | TO BE DETERMINED | EGGSHELL | |
| P4 | PAINT | SHERWIN WILLIAMS | TO BE DETERMINED | EGGSHELL | |
| T1 | TILE | DAL TILE | TO BE DETERMINED | FACTORY | |
| TB1 | TILE BASE | DAL TILE | TO BE DETERMINED | FACTORY | |
| GROUT | GROUT | PROMA | TO BE DETERMINED | SEALED | |

# INTERIOR FINISH SCHEDULE

**100313**

**ABSOLUTE HEALTH CHIROPRACTIC**

| ABBREVIATIONS | | | |
|---|---|---|---|
| C | CARPET | SYD | SQUARE YARD(S) |
| G | GROUT | T | TILE |
| N/A | NOT APPLICABLE | TBS | TO BE SELECTED |
| P | PAINT | VCB | VINYL COVE BASE |
| PL | PLASTIC LAMINATE | VCT | VINYL COMPOSITE TILE |
| R | RESILIENT/ RUBBER/ RUBBER TREAD | VSB | VINYL STRAIGHT BASE |
| SC | SEALED CONCRETE | WC | WALL COVERING (VINYL/ PAPER) |
| SF | SQUARE FEET | ETR | EXISTING TO REMAIN |
| SS | SOLID SURFACE/ NATURAL STONE | WD | WOOD |

| Room Information | | Floor (Code order: primary / secondary or accent) | | Walls (Code order: above chairrail / below chairrail) | | | | Trim | | | | Countertop/ Worksurface/ Cabinets | | Remarks |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Room # | Room Name | Floor | Grout | North Wall | East Wall | South Wall | West Wall | Base | Decorative Trim(s) | Door(s) | Door & Window Moulding | Horizontal Plane | Vertical Plane | |
| **First Floor Plan** | | | | | | | | | | | | | | |
| 100 | WAITING | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 101 | OFFICE | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 102 | STORAGE | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 103 | CORRIDOR | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 104 | RECEPTION | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 105 | RESTROOM | T1 | G1 | P | P | P | P | TB1 | P1 | – | – | NA | NA | |
| 106 | MASSAGE | SV1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 107 | MASSAGE | SV1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 108 | DR. OFFICE | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 109 | CLOSET | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 110 | CORRIDOR | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 111 | ACTIVE CARE | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 112 | ACTIVE CARE | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 113 | STORAGE | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 114 | CLOSET | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 115 | THERAPY | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 116 | STORAGE | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 117 | CORRIDOR | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 118 | STORAGE | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 119 | TREATMENT | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 120 | TREATMENT | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 121 | TREATMENT | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 122 | RETAIL | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 123 | CORRIDOR | C1 | NA | P | P | P | P | VCB1 | P1 | – | – | NA | NA | |
| 124 | STRAGE | ETR | NA | P | P | P | P | ETR | P1 | – | – | NA | NA | |

## K1 INTERIOR FINISH SCHEDULE & LEGEND

H1

J1

## F1 HEAD & JAMB DETAILS

1 1/2"=1'-0"

## A1 DOOR TYPE AND FRAME TYPE

1/4"=1'-0"

# DOOR SCHEDULE

| DOOR SCHEDULE ABBREVIATIONS | | | | | | |
|---|---|---|---|---|---|---|
| EHO | ELECTRO. HOLD OPENER | NO | NUMBER | | WD | WOOD (SOLID) |
| HM | HOLLOW METAL | ES | ELECTRIC STRIKE | | WG | WIRE GLASS |
| INS | INSULATED | TEMP | TEMPERED | | S | STAIN |
| MTL | METAL | THK | THICKNESS | | PTD | PAINT |

| DOORS | | | | | | | | FRAMES | | | | | | THRESHOLD | | | NO |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | DETAILS/A800 | | | | | DETAILS/A800 | | |
| NO | TYPE | SIZE | THK. | HDWR SET | FINISH | MAT. | REMARKS | TYPE | MAT. | HEAD | JAMB | REMARKS | RATING | MAT. | SILL | HEIGHT | |
| 100 | ETR | – | – | – | – | – | – | – | – | – | – | - | - | - | - | - | 100 |
| 101 | ETR | – | – | – | – | – | – | – | – | – | – | - | - | - | - | - | 101 |
| 102 | ETR | – | – | – | – | – | – | – | – | – | - | - | - | - | - | - | 102 |
| 103 | | NOT USED | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 103 |
| 104 | | NOT USED | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 104 |
| 105 | ETR | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 105 |
| 106 | A | 3'-0"x6'-8" | 1 3/4" | - | S | WD | LOCK | 1 | HM | H1 | J1 | - | - | - | - | - | 106 |
| 107 | ETR | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 107 |
| 108 | ETR | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 108 |
| 109 | ETR | - | - | - | - | - | - | - | - | - | - | | | | | | 109 |
| 110 | | NOT USED | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 110 |
| 111 | ETR | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 111 |
| 112 | A | 3'-0"x6'-8" | 1 3/4" | - | S | WD | LOCK | 1 | HM | H1 | J1 | - | - | - | - | - | 112 |
| 113 | A | 3'-0"x6'-8" | 1 3/4" | - | S | WD | LOCK | 1 | HM | H1 | J1 | - | - | - | - | - | 113 |
| 114 | ETR | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 114 |
| 115 | A | 3'-0"x6'-8" | 1 3/4" | - | S | WD | LOCK | 1 | HM | H1 | J1 | - | - | - | - | - | 115 |
| 116 | A | 2'-6"x6'-8" | 1 3/4" | - | S | WD | LOCK | 1 | HM | H1 | J1 | - | - | - | - | - | 116 |
| 117 | | NOT USED | | | | | | | | | | | | | | | 117 |
| 118 | A | 2'-6"x6'-8" | 1 3/4" | - | S | WD | LOCK | 1 | HM | H1 | J1 | - | - | - | - | - | 118 |
| 119 | A | 3'-0"x6'-8" | 1 3/4" | - | S | WD | LOCK | 1 | HM | H1 | J1 | | | | | | 119 |
| 120 | A | 3'-0"x6'-8" | 1 3/4" | - | S | WD | LOCK | 1 | HM | H1 | J1 | - | - | - | - | - | 120 |
| 121 | A | 3'-0"x6'-8" | 1 3/4" | - | S | WD | LOCK | 1 | HM | H1 | J1 | - | - | - | - | - | 121 |
| 122 | | NOT USED | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 122 |
| 123 | ETR | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 123 |
| 124 | ETR | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 124 |

1. PROVIDE BLOCKING FOR ALL HARDWARE
2. PAINT ALL INTERIOR HOLLOW METAL FRAMES P1
3. COORDINATE HARDWARE WITH TENANT
4. ALL WOOD DOORS TO HAVE FACTORY FINISH TO MATCH EXISTING DOORS

## A7 DOOR SCHEDULE

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 12/18/13


Gawron Turgeon
ARCHITECTS
29 Black Point Road
Scarborough, Maine 04074
www.gawronturgeon.com
207-883-6307 tel 207-883-0361 fax


ONE CITY CENTER
ABSOLUTE HEALTH CHIROPRACTIC
FIRST FLOOR
PORTLAND, MAINE

REVISIONS

| # | DATE | DESCRIPTION |
|---|---|---|
| | | |

| | |
|---|---|
| DATE: | 11.16.131.13 |
| PROJECT # | 100313 |
| DRAWN BY: | DLP |
| CHECKED BY: | |
| DRAWING SCALE | AS NOTED |

SHEET TITLE

DOOR SHCEDULE
SOOR & FRAME TYPES
HEAD & JAMB DETAILS
INTERIOR FINISH LEGEND & SCHEDULE

A800


© COPYRIGHT 1985-2008
REPRODUCTION OR REUSE OF THIS DOCUMENT WITHOUT WRITTEN PERMISSION OF GAWRON TURGEON ARCHITECTS IS PROHIBITED



1.20131100313 - Absolute Health Chiropractic_ Architecture & Interiors\Working Drawings\100313-first floor.dwg, A800, 11/14/2013 12:11:26 PM, gtm