Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 03/10/14

Gamewell Fire Alarm System Addition
1 City Center - 1st Floor
Portland, Maine

System Narrative

In the event of an alarm from an actuated device, the following shall occur: (Devices reporting an alarm: Manual Station, Smoke or Heat Detector, Waterflow Switch)

1) Notify the Portland Fire Depatment via Masterbox

2) Flash all visual signals until system rest

3) Sound a Code 3 Temporal evacuation signal on all horns until system silence.
Sound a pre-recorded message through fire system speakers followed by a Code 3 Temporal evacuation signal until system silence.

4) Annunciate audibly,visually, and in plain english the active initiating device at the fire command center and the remote annunciators.

5) Flash exterior strobe/beacon until system reset.

6) Release magnetically held doors and unlock designated exitways.

7) Interface w/ HVAC, Sound, and Mechanical Equipment as required

8) An elevator lobby or machine room smoke and/or heat detector, in addition to the above functions, shall initiate the appropriate elevator controller interfaces as required by elevator operation codes.

In the event of a supervisory condition from an actuated device, the following shall occur: (Devices reporting as supervisory: Tamper Switch, Sprinkler Supervisory Switch, & Duct Smoke Detector)

1) Notify 24 Hour Attendant Desk

2) Annunciate audibly,visually, and in plain english the active initiating device at the fire command center and the remote annunciator.

In the event of a system trouble report, the following shall occur:

1) Notify 24 Hour Attendant Desk

2) Annunciate audibly,visually, and in plain english the active initiating device at the fire command center and the remote annunciator.