REFLECTED CEILING LEGEND

SYMBOL	DESCRIPTION
	2'x 2' A C T INSTALLED @ 8'-0" AFF U.N.O. GRID: MFR.: ARMSTRONG – ULTIMA VECTOR 15/16" COLOR: WHITE 3/8" SHADOW MOLDING AROUND EDGES ACOUSTIC CEILING TILE: MFR.: ARMSTRONG – ULTIMA VECTOR FINE TEXTURE SIZE: 24" x 24" x ¾" COLOR: WHITE
	DRYWALL CEILING @ 8'-0" AFF U.N.O.
	CEILING MOUNTED EXIT SIGN TO MATCH BUILDING STANDARD.
	DENOTES CEILING STARTING POINT
S	LIGHT OVERRIDE SWITCH – REFER TO ENGINEERING DOCUMENTS
	OCCUPANCY SENSOR – REFER TO ENGINEERING DOCUMENTS (CENTER IN TILE U.N.O.)
	VIDEO PROJECTOR (COORDINATE WITH AV DRAWINGS)
	PROJECTION SCREEN (COORDINATE WITH AV DRAWINGS)
	SECURITY CAMERA (COORDINATE WITH SECURITY VENDOR DRAWINGS)

LIGHT FIXTURES

SYMBOL	DESCRIPTION
F1	HP90 2x2 RECESSED FLUORESCENT LIGHTOLIER HP90S2GLR224UNVPG W/ DIMMING BALLAST LAMPS (2) 24W T5HO
F1A	HP90 2x2 RECESSED FLUORESCENT (FOR CORRIDORS) LIGHTOLIER HP90S2GLR224UNVPG LAMPS (1) 24W T5HO
F2	HP90 2x4 RECESSED FLUORESCENT (FOR CORRIDORS) LIGHTOLIER HP90S2GLR228UNVPI W/ DIMMING BALLAST LAMPS (2) 28W T5
F3	CALCULITE EVOLUTION ADJUSTABLE ACCENT, 3" APERTURE LIGHTOLIER C3MRA CCDW/C3LV W/ DIMMING BALLAST LAMP (1) 37W IR MR16 NARROW FLOOD CENTER WITHIN CEILING TILE, U.N.O.
F4	NARROW SV T5 STRIP LIGHTOLIER SV T5, SINGLE FIXTURE CONFIGURATION. TO BE MOUNTED IN THE MIDDLE OF THE UNDERSIDE OF MILLWORK CABINET. LENGTHS AS REQUIRED TO SPAN LENGTH OF MILLWORK. GC TO COORDINATE LENGTHS WITH MILLWORKER.
F5	EDGE LIT LED EXIT SIGN WITH BATTERY BACKUP EXIT STORE TES-ELE-R-BB OR APPROVED EQUAL
F6	FLUORESCENT LIGHTING LIGHTOLIER CAT. NO.: 1113TCL / 1102T26U LAMPS: (2) 28W CF
F7	WASHWASHERS LIGHTOLIER CAT. NO.: 1135TWH / 1102T26U LAMPS: (2) 28W CF
F8	CEILING RECESSED LINEAR FIXTURE @ FILES – TBD SEE DETAIL FOR LOCATION. LENGTHS TO BE DETERMINED IN FIELD, G.C. TO SPECIFY. LIGHTOLIER CAT. NO.: PTS5-1-S-S-D1-VARIES LAMPS: T5 FLUORESCENT LAMP
F9	ALKCO LITTLE INCH FIXTURE ALCKO, SINGLE FIXTURE CONFIGURATION. LENGTHS AS REQUIRED TO SPAN LENGTH OF CABINETS. GC TO COORDINATE LENGTHS WITH MILLWORKER. FIXTURES TO BE GANGED TOGETHER AND HARDWIRED TO SWITCH THAT CONTROLS CEILING FIXTURES. FIXTURE TO BE CENTERED ON UNDERSIDE OF MILLWORK.
F10	DECORATIVE PENDANT TECH LIGHTING CAT. NO.: 700-FJ-PPR-B5-12V LAMPS: (1) 12V UP TO 50W HALOGEN BI-PIN W/ PYREX GLASS SHIELD

REFLECTED CEILING KEY NOTES

1. NOT USED
2. REFER TO DETAILS FOR LOCATION OF F4, F7, & F8 FIXTURES. LENGTHS TBD IN FIELD.
3. GYP. BD. CEILING.
4. RECESSED MOTORIZED PROJECTION SCREEN SEE AV DRAWINGS FOR ADDITIONAL INFORMATION. 10th FLOOR ONLY
5. CEILING MOUNTED PROJECTOR. (REFER TO AV DRAWINGS FOR ADDITIONAL INFO INCLUDING POWER/ DATA REQUIREMENTS & EXACT LOCATION) 10TH FLOOR ONLY
6. NOT USED
7. COORDINATE LOCATION OF LIGHT FIXTURES WITH RACK LAYOUT PER ENGINEERING DRAWINGS. 10TH FLOOR ONLY.
8. IF ROOM AND DOOR ARE EXISTING TO REMAIN REUSE EXISTING LIGHT SWITCH LOCATION.
9. COORDINATE LOCATION OF CAMERA WITH EXISTING CEILING LAYOUT. NO OTHER CEILING WORK TO BE DONE IN THIS ROOM. 7th FLOOR ONLY
10. PROJECTION SCREEN RAISE/ LOWER SWITCH. 10th FLOOR ONLY

REFLECTED CEILING NOTES

LIGHTING

1. COORDINATE ALL LIGHT SWITCHES AND CIRCUITS OF ALL LIGHTING FIXTURES WITH ARCHITECT, ENGINEER AND TENANT PRIOR TO INSTALLATION.
2. NIGHT LIGHTS, EXIT LIGHTS AND ALARMS SHALL BE PROVIDED BY G.C. AS REQUIRED BY APPLICABLE CODE.
3. ENGINEER TO CHECK AND/OR RECOMMEND BULB WATTAGE AND ADJUSTMENT IN FIXTURE SWITCHING PLACEMENT AS NECESSARY.
4. ALL LIGHTING SHALL BE INSTALLED IN CONFORMANCE WITH ELECTRICAL CODES.
5. SOME LIGHTING FIXTURES MAY REQUIRE LONGER LEAD TIME WHICH ELECTRICAL CONTRACTOR IS RESPONSIBLE FOR ALLOWING SUFFICIENT TIME FOR ORDER PLACEMENT, SUBMITTAL REVIEW & ORDER RELEASE.
6. SUBSTITUTIONS FOR SPECIFIED LIGHTING PRODUCTS ARE NOT ACCEPTABLE & WILL NOT BE CONSIDERED. FAILURE TO INCLUDE ONE OF SPECIFIED PRODUCTS AS A PART OF BASE BID MAY, AT DISCRETION OF OWNER, INVALIDATE THE ENTIRE LIGHTING PRODUCT BID & EXCLUDE CONTRACTOR FROM FURTHER CONSIDERATION.
7. DISTRIBUTOR NET PRICING HAS BEEN SECURED FROM MANUFACTURER OR MANUFACTURER'S REPRESENTATIVE & HAS BEEN USED IN PREPARATION OF PRELIMINARY OPINIONS OF PROBABLE COSTS. A RECORD OF SPECIFIC UNIT COSTS HAS BEEN SHARED W/ OWNER TO ASSIST IN ANALYSIS OF BID SUBMITTALS.
8. UNIT PRICING SHOULD BE MADE AVAILABLE ON ALL SPECIFIED LIGHTING FIXTURES
9. U.N.O. LIGHT SWITCH COVERPLATE FINISH SHALL BE METAL AND PAINTED TO MATCH WALL COLOR IN A SEMIGLOSS FINISH.
10. LIGHTS WILL BE CONTROLLED VIA CEILING MOUNTED MOTION SENSORS AND SWITCH OVER-RIDES. REFER TO ENGINEERING DRAWINGS.

LIFE SAFETY

11. NEW SMOKE DETECTORS &/OR FIRE ALARM STROBES & SPEAKERS, ETC. SHALL BE FURNISHED AND INSTALLED AS REQUIRED. LOCATION TO BE DETERMINED IN THE FIELD. COORDINATE WITH BUILDING MANAGEMENT AND ARCHITECT. REFER TO ENGINEERING DRAWINGS.
12. GENERAL CONTRACTOR SHALL INSTALL NEW EXIT SIGNS AS REQUIRED BY LOCAL BUILDING CODE. SEE MEP DRAWINGS FOR LOCATIONS.
13. REFER TO ENGINEERING DRAWINGS FOR EMERGENCY LIGHT SPECIFICATIONS AND LOCAL LAW REQUIREMENTS.

HVAC

14. HVAC CONTRACTOR TO PROVIDE BALANCING REPORT & SUBMIT TO BUILDING MANAGEMENT. HVAC CONTRACTOR TO NOTIFY BUILDING CHIEF ENGINEER OF DATE & TIME OF BALANCING FOR WITNESS.
15. LOCATION OF THERMOSTATS TO BE ACCEPTED BY ARCHITECT PRIOR TO INSTALLATION. DO NOT INSTALL ON PANELED, FEATURE WALLS OR BEHIND FURNITURE PANELS. COORDINATE WITH FURNITURE INSTALLER.

FINISHES

16. UNO GYPSUM BOARD CEILING TO BE PAINTED CEILING WHITE.
17. GENERAL CONTRACTOR TO CLEAN/ WIPE DUST FROM TOPS OF EXPOSED MECHANICAL DUCTS AND LIGHT FIXTURES PRIOR TO FURNITURE INSTALLATION.

COORDINATION

18. GENERAL CONTRACTOR SHALL COORDINATE ALL TRADES AFFECTED BY HUNG CEILING CONSTRUCTION (HVAC, SPRINKLER, LIGHTING, POWER, ETC).
19. ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING COMPATIBILITY BETWEEN FIXTURE TRIMS & CEILING GRID.
20. ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR SUPPLYING SHOP DRAWINGS FOR SPECIFIED EQUIPMENT FOR APPROVAL TO ARCHITECT ON TIMELY BASIS.
21. COORDINATE INTERCOM SPEAKER LOCATIONS WITH AV DRAWINGS.

UBS

REVISIONS

NO.	DATE	DESCRIPTION
2	07.13.07	ISSUE FOR BID
1	07.13.07	ISSUE FOR PERMIT
	06.26.07	ISSUE FOR CLIENT REVIEW
	06.13.07	ISSUE FOR ENGINEER

NO.	DATE	COPIES	TO WHOM

ISSUE

KEY PLAN

Ted Moudis Associates
ARCHITECTURE
INTERIOR DESIGN
NEW YORK | CHICAGO

79 Madison Avenue
New York, NY 10017
212.308.4000
Fax/212.561 3020

One Financial Place
440 South LaSalle Street
Chicago, IL 60605
312.663.0130
Fax/312.663.0138

www.tedmoudis.com

PROJECT NUMBER	107126.01
SCALE	1/8"=1'-0"
DATE	07.13.07
PROJECT MANAGER	
PROJECT ARCHITECT	
DRAWN BY	AE
CHECKED BY	
CADD FILE	R:\2007\107126.01\CD

10th FL. REFLECTED CEILING PLAN

UBS
ONE CITY CENTER
PORTLAND, ME 04101

A-103.10