

HARRIMAN

AUBURN PORTLAND MANCHESTER

GOULD RESAURANT

414 FORE STREET  
PORTLAND, ME 04101

Harriman Project No. 12752

Key Plan Proj North



GENERAL NOTES

- COORDINATE WORK WITH THE WORK OF ALL OTHER TRADES.
- ALL SANITARY WASTE PIPING SHALL BE INSTALLED WITH A PITCH OF 1/4" PER 1'-0".
- ALL VENT AND WATER SUPPLY SHALL PITCH TO DRAIN.
- REFER TO PLUMBING FIXTURE INSTALLATION SCHEDULE FOR THE SIZE OF PIPING CONNECTIONS AND MOUNTING HEIGHTS OF EACH FIXTURE.
- THE TERM "PROVIDE" SHALL MEAN TO "FURNISH, INSTALL AND CONNECT COMPLETELY".
- OSHA RULES, REGULATIONS AND REQUIREMENTS AND ANY STATE AND LOCAL REQUIREMENTS FOR SAFETY SHALL BE FOLLOWED BY THE CONTRACTOR.
- PROVIDE FIXTURE STOPS ON WATER SUPPLY IMMEDIATELY ADJACENT TO PLUMBING FIXTURES.
- ENTIRE PLUMBING INSTALLATION SHALL BE IN COMPLIANCE WITH ALL CURRENT LOCAL, STATE, AND FEDERAL CODES AND STANDARDS


LEGEND

- EXISTING PIPING ABOVE FINISHED FLOOR TO BE REMOVED
- EXC-W-X --- EXISTING COLD WATER PIPING ABOVE FINISHED FLOOR
- CW-X --- COLD WATER PIPING ABOVE FINISHED FLOOR
- EXF-X --- EXISTING SPRINKLER PIPING ABOVE FINISHED FLOOR
- F-X --- SPRINKLER PIPING ABOVE FINISHED FLOOR
- EXG-X --- EXISTING GAS PIPING ABOVE FINISHED FLOOR
- G-X --- GAS PIPING ABOVE FINISHED FLOOR
- EXHW-X --- EXISTING HOT WATER PIPING ABOVE FINISHED FLOOR
- HW-X --- HOT WATER PIPING ABOVE FINISHED FLOOR
- EXHWR-X --- EXISTING HOT WATER RETURN PIPING ABOVE FINISHED FLOOR
- HWR-X --- HOT WATER RETURN PIPING ABOVE FINISHED FLOOR
- EXGW-X --- EXISTING INDIRECT WASTE PIPING ABOVE FINISHED FLOOR
- GW-X --- INDIRECT WASTE PIPING ABOVE FINISHED FLOOR
- ES-X --- SANITARY PIPING ABOVE FINISHED FLOOR
- S-X --- SANITARY PIPING ABOVE FINISHED FLOOR
- EXSD-X --- EXISTING STORM DRAIN PIPING ABOVE FINISHED FLOOR
- SD-X --- STORM DRAIN PIPING ABOVE FINISHED FLOOR
- EXV-X --- EXISTING VENT PIPING ABOVE FINISHED FLOOR
- V-X --- VENT PIPING ABOVE FINISHED FLOOR
- BV --- BALL VALVE
- SOV --- SHUT-OFF VALVE
- CV --- CHECK VALVE
- BFPV --- BACKFLOW PREVENTER WITH ISOLATION VALVES
- PRV --- PRESSURE REDUCING VALVE
- BV --- BALANCING VALVE
- GR --- GAS REGULATOR
- FD --- FLOOR DRAIN
- FCO --- FLOOR CLEANOUTS
- WCO --- WALL CLEANOUT
- WC-X --- WATER CLOSET
- L-X --- LAVATORY
- SK-X --- COUNTER SINK
- MR --- MOP RECEPTOR
- EWC --- ELECTRIC WATER COOLER
- WH --- WALL HYDRANT
- WM --- WATER METER
- CAP --- CAP
- SA --- SHOCK ARRESTOR OF P.D.I RATING
- V --- VENT PIPING
- VTR --- VENT THROUGH ROOF
- W --- WASTE PIPING
- S --- SOIL PIPING
- RD --- ROOF DRAIN
- RL --- ROOF LEADER
- DN --- DOWN
- AFF --- ABOVE FINISHED FLOOR
- BFF --- BELOW FINISHED FLOOR
- TYP. --- TYPICAL
- CNTE --- CONNECT NEW TO EXISTING
- C --- CONNECT NEW TO EXISTING

PLUMBING FIXTURE INSTALLATION SCHEDULE

MARK	FIXTURE DESCRIPTION	GAS	BRANCH SIZE				BTU	SPECIFICATION	MTG. HT TO RIM
			VENT	WASTE	CW	HW			
WC-1	WATER CLOSET ADA COMPLIANT	---	2"	4"	1"	---	FLOOR MOUNTED TANK TYPE	16-1/2"	
L-1	LAVATORY ADA COMPLIANT	---	1-1/2"	2"	1/2"	1/2"	WALL MOUNTED	34"	
FD	FLOOR DRAIN	---	1-1/2"	2"	---	---			
1	PLANCHA TOP RANGE	3/4"	---	---	---	122,000			
6	FRYER	3/4"	---	---	---	140,000			
2	RANGE W / CONVECTION OVEN	3/4"	---	---	---	210,000			
4	6 BURNER RANGE W / OVEN	3/4"	---	---	---	240,000			
12	ICE MAKER	---	---	3/4"	1/2"	---			
13	DISHWASHER	---	1-1/2"	2"	---	3/4"			
14	UNDERCOUNTER DISHWASHER	---	1-1/2"	2"	---	3/4"			
15	HAND SINK	---	1-1/2"	1-1/2"	1/2"	1/2"			
17A	PRE-RINSE UNIT	---	1-1/2"	2"	1/2"	---			
18	THREE COMPARTMENT SINK	---	1-1/2"	2"	1/2"	---			
18A	PRE-RINSE UNIT	---	1-1/2"	2"	1/2"	---			
18B	SPLASH MOUNT FAUCET	---	---	2"	1/2"	---			
21	TWO COMPARTMENT SINK	---	1-1/2"	2"	1/2"	---			
21A	SPLASH MOUNT FAUCET	---	---	2"	1/2"	---			
26	ICE BIN	---	---	3/4"	---	---			
27	HAND SINK	---	1-1/2"	1-1/2"	1/2"	1/2"			
28	THREE COMPARTMENT SINK	---	1-1/2"	2"	1/2"	---			
30	WALK-IN COOLER	---	---	3/4"	---	---			
31	MOP SINK	---	1-1/2"	2"	1/2"	---			
31A	SERVICE SINK FAUCET	---	1-1/2"	2"	1/2"	---			
-	INSTANTANEOUS WATER HEATER	---	---	---	1/2"	---	MOUNT HEATER BELOW COUNTER	FAUCET MOUNT IN COUNTER	
WH-1	GAS FIRED WATER HEATER	1-1/2"	---	---	1-1/2"	1"	FLOOR MOUNTED, PROVIDE FACTORY CONCENTRIC TERMINATION KIT		
MUA-1	GAS FIRED MAKE-UP AIR UNIT	1-1/2"	---	---	---	240,000			

Mark	Date	Description
05-21-13	75% REVIEW	
05-31-13	ISSUED FOR CONSTRUCTION	
07-26-13	RE-ISSUED FOR CONSTRUCTION	
09-23-13	RE-ISSUED FOR CONSTRUCTION	



Drawing Scales	
NO SCALE	---
	---
	---
	---
PA / PE: CG	© 2013 Harriman Associates
Drawn By: ROM	

LEGEND, NOTES AND SCHEDULE

P00.1