LEGEND

— — — — — —	EXISTING PIPING ABOVE FINISHED FLOOR TO BE REMOVED
EXCW- X	EXISTING COLD WATER PIPING ABOVE FINISHED FLOOR
CW- X	COLD WATER PIPING ABOVE FINISHED FLOOR
EXF- X	EXISTING SPRINKLER PIPING ABOVE FINISHED FLOOR
F- X	SPRINKLER PIPING ABOVE FINISHED FLOOR
EXG- X	EXISTING GAS PIPING ABOVE FINISHED FLOOR
G- X	GAS PIPING ABOVE FINISHED FLOOR
EXHW- X	EXISTING HOT WATER PIPING ABOVE FINISHED FLOOR
HW- X	HOT WATER PIPING ABOVE FINISHED FLOOR
EXHWR- X	EXISTING HOT WATER RETURN PIPING ABOVE FINISHED FLOOR
HWR- X	HOT WATER RETURN PIPING ABOVE FINISHED FLOOR
EXGW- X	EXISTING INDIRECT WASTE PIPING ABOVE FINISHED FLOOR
GW- X	INDIRECT WASTE PIPING ABOVE FINISHED FLOOROR
ES- X	SANITARY PIPING ABOVE FINISHED FLOOR
S- X	SANITARY PIPING ABOVE FINISHED FLOOR
EXSD- X	EXISTING STORM DRAIN PIPING ABOVE FINISHED FLOOR
SD- X	STORM DRAIN PIPING ABOVE FINISHED FLOOR
EXV- X	EXISTING VENT PIPING ABOVE FINISHED FLOOR
V- X	VENT PIPING ABOVE FINISHED FLOOR

	BALL VALVE
	SHUT-OFF VALVE
	CHECK VALVE
	BACKFLOW PREVENTER WITH ISOLATION VALVES
	PRESSURE REDUCING VALVE
	BALANCING VALVE
	GAS REGULATOR
FD	FLOOR DRAIN
FCO	FLOOR CLEANOUTS
WCO	WALL CLEANOUT
WC-X	WATER CLOSET
L-X	LAVATORY
SK-X	COUNTER SINK
MR	MOP RECEPTOR
EWC	ELECTRIC WATER COOLER
WH	WALL HYDRANT
	WATER METER
	CAP
SA " "	SHOCK ARRESTOR OF P.D.I RATING
V	VENT PIPING
VTR	VENT THROUGH ROOF
W	WASTE PIPING
S	SOIL PIPING
RD	ROOF DRAIN
RL	ROOF LEADER
DN	DOWN
AFF	ABOVE FINISHED FLOOR
BFF	BELOW FINISHED FLOOR
TYP.	TYPICAL
CNTE	CONNECT NEW TO EXISTING
	CONNECT NEW TO EXISTING

GENERAL NOTES

1. COORDINATE WORK WITH THE WORK OF ALL OTHER TRADES.

2. ALL SANITARY WASTE PIPING SHALL BE INSTALLED WITH A PITCH OF 1/4" PER 1'-0".

3. ALL VENT AND WATER SUPPLY SHALL PITCH TO DRAIN.

4. REFER TO PLUMBING FIXTURE INSTALLATION SCHEDULE FOR THE SIZE OF PIPING CONNECTIONS AND MOUNTING HEIGHTS OF EACH FIXTURE.

5.THE TERM "PROVIDE" SHALL MEAN TO "FURNISH, INSTALL AND CONNECT COMPLETELY".

6. OSHA RULES, REGULATIONS AND REQUIREMENTS,AND ANY STATE AND LOCAL REQUIREMENTS FOR SAFETY SHALL BE FOLLOWED BY THE CONTRACTOR.

7. PROVIDE FIXTURE STOPS ON WATER SUPPLY IMMEDIATELY ADJACENT TO PLUMBING FIXTURES.

8 .ENTIRE PLUMBING INSTALLATION SHALL BE IN COMPLIANCE WITH ALL CURRENT LOCAL, STATE, AND FEDERAL CODES AND STANDARDS

PLUMBING FIXTURE INSTALLATION SCHEDULE

FIXTURE		BRANCH SIZE							MTG. HT TO RIM
MARK	DESCRIPTION	GAS	VENT	WASTE	CW	HW	BTU	SPECIFACTION	
WC-1	WATER CLOSET ADA COMPLIANT	---	2"	4"	1"	---	---	FLOOR MOUNTED TANK TYPE	16-1/2"
L-1	LAVATORY ADA COMPLIANT	---	1-1/2"	2"	1/2"	1/2"	---	WALL MOUNTED	34"
FD	FLOOR DRAIN	---	1-1/2"	2"	---	---	---		
1	PLANCHA TOP RANGE	3/4"	---	---	---	---	122,000		
6	FRYER	3/4"	---	---	---	---	140,000		
2	RANGE W / CONVECTION OVEN	3/4"	---	---	---	---	210,000		
4	6 BURNER RANGE W / OVEN	3/4"	--	---	---	---	240,000		
12	ICE MAKER	---	---	3/4"	1/2"	---	---		
13	DISHWASHER	---	1-1/2"	2"	---	3/4"	---		
14	UNDERCOUNTER DISHWASHER	---	1-1/2"	2"	---	3/4"	---		
15	HAND SINK	---	1-1/2"	1-1/2"	1/2"	1/2"	---		
17A	PRE-RINSE UNIT	---	1-1/2"	2"	1/2"	---	---		
18	THREE COMPARTMENT SINK	---	1-1/2"	2"	1/2"	---	---		
18A	PRE-RINSE UNIT	---	1-1/2"	2"	1/2"	---	---		
18B	SPLASH MOUNT FAUCET	---	---	2"	1/2"	---	---		
21	TWO COMPARTMENT SINK	---	1-1/2"	2"	1/2"	---	---		
21A	SPLASH MOUNT FAUCET	---	---	2"	1/2"	---	---		
26	ICE BIN	---		3/4"	---	---	---		
27	HAND SINK	---	1-1/2"	1-1/2"	1/2"	1/2"	---		
28	THREE COMPARTMENT SINK	---	1-1/2"	2"	1/2"	---	---		
30	WALK-IN COOLER	---	---	3/4"	---	---	---		
31	MOP SINK	---	1-1/2"	2"	1/2"	---	---		
31A	SERVICE SINK FAUCET	---	1-1/2"	2"	1/2"	---	---		
-	INSTANTANEOUS WATER HEATER	---	---	---	1/2"	---	---	MOUNT HEATER BELOW COUNTER	FAUCET MOUNT IN COUNTER
WH-1	GAS FIRED WATER HEATER	1-1/2"	---	---	1-1/2"	1"	199,000	FLOOR MOUNTED, PROVIDE FACTORY CONCENTRIC TERMINATION KIT	
MUA-1	GAS FIRED MAKE-UP AIR UNIT	1-1/2"	---	---	---	---	240,000		

Plot Date: 9/23/2013 11:03:50 AM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 10/31/13

HARRIMAN

AUBURN PORTLAND MANCHESTER

GOULD RESAURANT

414 FORE STREET
PORTLAND, ME 04101

Harriman Project No.	12752

Key Plan

Proj North

Issues and Revisions

Mark	Date	Description
	05-21-13	75% REVIEW
	05-31-13	ISSUED FOR CONSTRUCTION
	07-26-13	RE-ISSUED FOR CONSTRUCTION
	09-23-13	RE-ISSUED FOR CONSTRUCTION

STATE OF MAINE
CLIFTON W. GREIM
No. 6405
LICENSED
PROFESSIONAL ENGINEER

Drawing Scales
NO SCALE

PA / PE: CG
Drawn By: ROM

© 2013
Harriman Associates

LEGEND, NOTES AND SCHEDULE

P00.1