GENERAL NOTES

1. COORDINATE WORK WITH THE WORK OF ALL OTHER TRADES.

2. SPRINKLERS & PIPING SHALL BE PROVIDED THROUGHOUT THE BUILDING IN ACCORDANCE WITH NFPA 13.

3. SPRINKLER PIPING AND SPRINKLERS SHOWN ON THE BASEMENT, FIRST AND SECOND FLOOR LEVELS ARE INSTALLED IN THE THE PREFERRED LOCATIONS RELATED TO ASTHETICS. MODIFICATIONS MAY BE MADE TO THE LAYOUT ONLY AFTER REVIEW WITH THE ARCHITECT AND THE OWNER.

4. PROVIDE SPRINKLER PROTECTION BELOW DUCTS OR OTHER OBSTRUCTIONS 48" WIDE OR WIDER PER NFPA 13, OR AT ANY OTHER LOCATION WHERE SPRINKLER DISCHARGE IS OBSTRUCTED.

5. THE FIRE SPRINKLER CONTRACTOR SHALL THOROUGHLY REVIEW ALL CONTRACT DRAWINGS AND SPECIFICATIONS THAT IMPACT THE FIRE SPRINKLER SYSTEMS PRIOR TO BID. ANY QUESTIONS THAT AFFECT THE DESIGN AND INSTALLATION OF THE FIRE SPRINKLER SYSTEM SHALL BE RESOLVED BEFORE CONTRACT IS AWARDED.

6. SPRINKLER CONTRACTOR SHALL PREPARE AND SUBMIT SHOP DRAWINGS AS REQUIRED BY THE SPECIFICATIONS.

7. INSTALLED SPRINKLER PIPE SIZES SHALL BE BASED ON HYDRAULIC CALCULATIONS. SPRINKLER PIPE SIZES SHOWN ON DRAWINGS ARE FOR REFERENCE ONLY.

1 BASEMENT FLOOR PLAN FIRE PROTECTION

SCALE: 1/4" = 1'-0"

2 FIRST FLOOR PLAN FIRE PROTECTION

SCALE: 1/4" = 1'-0"

3 SECOND FLOOR PLAN FIRE PROTECTION

SCALE: 1/4" = 1'-0"

Plot Date: 9/23/2013 11:02:50 AM

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 10/31/13

HARRIMAN

AUBURN PORTLAND MANCHESTER

GOULD RESAURANT

414 FORE STREET
PORTLAND, ME 04101

Harriman Project No.	12752

Key Plan

Proj North

Issues and Revisions

Mark	Date	Description
	05-31-13	ISSUED FOR CONSTRUCTION
	07-26-13	RE-ISSUED FOR CONSTRUCTION
	09-23-13	RE-ISSUED FOR CONSTRUCTION

STATE OF MAINE
CLIFTON W. GREEM
No. 5405
LICENSED
PROFESSIONAL ENGINEER

Drawing Scales
As indicated

0 2' 4' 6'
1/4" = 1'-0"

PA / PE: CG

Drawn By: ROM

© 2013 Harriman Associates

FIRE PROTECTION PLANS

F10.1