



SHEET NOTES

- 01 PATCH AND REPAIR ALL WALL, FLOOR, AND CEILING FINISHES IN THIS AREA DISTURBED BY DEMO AND/OR NEW WORK
- 02 PATCH FLOOR TO MATCH EXIST.
- 03 EXIST. MARKERBOARD LOCATION - COORDINATE W/ FURNITURE VENDOR
- 04 EXISTING FLOORING: GC TO COORDINATE AND MATCH WITH BUILDING ATTIC STOCK AS NEEDED.
- 05 EXISTING FLOORING TO REMAIN



2 CITY CENTER, PORTLAND, ME 04101

Gensler

214 North Tryon Street
 Suite 2320
 Charlotte, NC 28202
 United States
 Tel 704.377.2725
 Fax 704.377.2807

URS CORPORATION
 MEP ENGINEERS
 2777 FRANKLIN ROAD
 SUITE 2000
 SOUTHFIELD, MI 48034
 Tel 248.204.5900
 Fax 248.204.5901

MONAGHAN WOODWORKS
 100 COMMERCIAL STREET
 SUITE 212
 PORTLAND, ME 04101
 Tel 207.775.2683
 Fax 207.772.6726

GENERAL NOTES

△	Date	Description
	08/08/14	ISSUED FOR CONSTRUCTION

- A. ALL WALL FINISHES TO BE P5, UNLESS NOTED OTHERWISE.
- B. ALL EXISTING WOOD BASE TO REMAIN U.N.O.
- C. REFER TO INTERIOR ELEVATIONS FOR ADDITIONAL FINISH INFORMATION.
- D. ALL FLOOR FINISH TRANSITIONS SHALL OCCUR AT CENTERLINE OF DOOR, UNLESS NOTED OTHERWISE.
- E. REFER TO G00.30 FOR FINISH SCHEDULE.
- F. EXISTING PAINTED CORE DOORS & FRAMES TO BE PAINTED TO MATCH ADJACENT WALL.
- G. REFER TO TRANSITION DETAILS ON G00.20.
- H. COORDINATE START POINTS FOR ALL TILE FLOORING WITH ARCHITECT
- I. EXISTING FLOORING FINISHES TO REMAIN U.N.O.

Seal / Signature

Project Name
 URS - PORTLAND

Project Number
 59 6222.900

Scale
 1/4" = 1'-0"

Description
 FINISH PLAN - LEVEL 03

A04.03

