

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

CHASE CUSTOM HOMES & FINANCE INC

Located at

6 CITY CTR (2nd floor - left side)

PERMIT ID: 2013-01315

ISSUE DATE: 07/17/2013

CBL: 032 P004001

has permission to **Change of use from medical lab to hair salon - add 2 offices, replace 680 ft drop ceiling and flooring (2nd floor - left side)**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise cloed-in. 48 HOUR NOTICE IS REQUIRED.	A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.
--	--

/s/ Chris Pirone

/s/ Jon Rioux

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

2nd floor, left side - hair salon

Building Inspections

Fire Department

Classification:

Business

Second Floor

2009 NFPA

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Close-in Plumbing/Framing
Electrical - Commercial
Above Ceiling Inspection
Certificate of Occupancy/Final

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2013-01315	Date Applied For: 06/25/2013	CBL: 032 P004001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Hair Salon	Proposed Project Description: Change of use from medical lab to hair salon - add 2 offices, replace 680 ft drop ceiling and flooring (2nd floor - left side)			
<hr/>				
Dept: Zoning	Status: Approved w/Conditions	Reviewer: Ann Machado	Approval Date: 06/26/2013	Ok to Issue: <input checked="" type="checkbox"/>
Note:				
Conditions:				
1) Separate permits shall be required for any new signage.				
2) ANY exterior work requires a separate review and approval thru Historic Preservation. This property is located within an Historic District.				
<hr/>				
Dept: Building	Status: Approved w/Conditions	Reviewer: Jon Rioux	Approval Date: 07/17/2013	Ok to Issue: <input checked="" type="checkbox"/>
Note: Owner stated ceiling tiles are not part of the existing rated assembly (fire separation).				
Conditions:				
1) Separate permits are required for any electrical: plumbing, sprinkler, fire alarm, HVAC systems, commercial hood exhaust systems and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.				
2) 713.3 Fire-resistance-rated walls. Penetrations into or through fire walls, fire barriers, smoke barrier walls and fire partitions shall comply with Sections 713.3.1 through 713.3.3. Penetrations in smoke barrier walls shall also comply with Section 713.5.				
3) Ventilation of this space is required per ASHRAE 62.2 or 62.1, 2007 edition.				
Duct penetrations shall be protected per IBC Sec. 713.1.1 & 716 and when through fire barriers, approved fire or smoke dampers or combination of, shall be installed in accordance with their listing.				
4) Interior wall and ceiling finish requirements by occupancy shall comply with Table 803.9.				
<hr/>				
Dept: Fire	Status: Approved w/Conditions	Reviewer: Chris Pirone	Approval Date: 07/03/2013	Ok to Issue: <input checked="" type="checkbox"/>
Note:				
Conditions:				
1) A separate Suppression System Permit is required for all new suppression systems, including standpipe systems, and sprinkler work effecting more than 20 heads. This review does not include approval of system design or installation.				
2) Construction or installation shall comply with City Code Chapter 10.				
3) A separate Fire Alarm Permit is required for new systems; or for work effecting more than 5 fire alarm devices; or replacement of a fire alarm panel with a different model. This review does not include approval of fire alarm system design or installation.				
4) **The fire alarm system design shall be evaluated for the renovated areas by an NICET IV certified interior fire alarm designer or a licensed engineer for compliance with the code. A compliance letter is required prior to the final inspection.** **A current inspection sticker from an approved fire alarm inspection company is required prior to the final inspection.**				
5) Fire extinguishers are required per NFPA 1.				
6) All means of egress to remain accessible at all times.				
7) Emergency lights and exit signs are required. Emergency lights and exit signs are required to be labeled in relation to the panel and circuit and on the same circuit as the lighting for the area they serve.				
8) Any cutting and welding done will require a Hot Work Permit from Fire Department.				
9) Fire walls, fire barriers, fire partitions, smoke barriers and smoke partitions or any other wall required to have protected openings or penetrations shall be effectively and permanently identified with signs or stenciling in accessible concealed floor, floor-ceiling or attic spaces at intervals not exceeding 30 feet with lettering not less than 0.5 inches in height.				
10 Notice: The first scheduled final inspection fee is at no charge. Additional inspections shall be billed at \$75 for each inspector.				

PERMIT ID: 2013-01315

Located at: 6 CITY CTR (2nd floor - left side)

CBL: 032 P004001

- 11 Through-penetrations and membrane penetrations in fire walls, fire barrier walls, and fire resistance rated horizontal assemblies shall be protected by firestop systems or devices in conformance with NFPA 101:8.3.5 (ASTM E 814 or ANSI/UL 1479). Providing firestop labels at each firestop system or device and an onsite manual containing the detail for each firestop system or device used for the project will streamline final inspection approvals.
- 12 Street addresses shall be marked on the structure and shall be as approved by the City E-911 Addressing Officer. Contact Michelle Sweeney at 874-8682 for further information.