DOOR SCHEDULE												
	DOOR						FRAME				FIRE	
NO.	TYPE	MAT.	FIN.	WIDTH	HEIGHT	THICK.	TYPE	MAT.	FIN.	HDWR.	RATING	NOTES
201	EXG	WD/GL	PT	3'-0"	6'-8"	1 3/4"	EXG	WD	PT	EXG	--	1
209	EXG	WD/GL	PT	3'-0"	6'-8"	1 3/4"	EXG	WD	PT	EXG	--	4
210	EXG	WD / GL	PT	3'-0"	6'-8"	1 3/4"	EXG	WD	PT	EXG	--	2
211	EXG	WD / GL	PT	3'-0"	6'-8"	1 3/4"	EXG	WD	PT	EXG	--	3
212	1	WD / SC	PT	3'-0"	6'-8"	1 3/4"	A	HM	PT	HW-1	--	
213	2	GL	FF	3'-0"	8'-0"	1/2"	--	--	--	HW-2	--	
214	2	GL	FF	3'-0"	8'-0"	1/2"	--	--	--	HW-2	--	
215	2	GL	FF	3'-0"	8'-0"	1/2"	--	--	--	HW-2	--	
216	2	GL	FF	3'-0"	8'-0"	1/2"	--	--	--	HW-2	--	
218	1	WD / SC	PT	3'-0"	6'-8"	1 3/4"	A	HM	PT	HW-3	--	

MATERIAL/FINISH ABBREVIATIONS

EXG EXISTING
FF FACTORY FINISH
GL GLASS
PT PAINT
SC SOLID CORE
WD WOOD

HARDWARE

HW-1 3 HINGES
1 LOCKSET
1 STOP
HW-2 MFR STANDARD PIVOT HINGES, PUSH-PULL, DEADBOLT LOCK, CONCEALED CLOSER
HW-3 3 HINGES
1 PRIVACY SET
1 STOP

NOTES

1. INSTALL EXISTING DOOR X01, FRAME, AND HARDWARE
2. INSTALL EXISTING DOOR X02, FRAME, AND HARDWARE
3. INSTALL EXISTING DOOR X03, FRAME, AND HARDWARE
4. INSTALL EXISTING DOOR X04, FRAME, AND HARDWARE. REVERSE DOOR SWING.

ROOM FINISH SCHEDULE								
		FLOORS	BASE	WALLS	TRIM	CEILING		
NO.	NAME	MAT.	MAT.	MAT.	MAT.	HEIGHT	MAT.	NOTES
201	CONFERENCE	CPT	WD - EXG	PT	PT	10'-0" EXG	EXG	
202	RECEPTION	CER	EXG	PT	PT	9'-0" EXG	EXG	
203	CONFERENCE	CPT	EXG	PT	PT	9'-0" EXG	EXG	
204	OFFICE	CPT	EXG	PT	PT	9'-0" EXG	EXG	
205	OFFICE	CPT	EXG	PT	PT	9'-0" EXG	EXG	
206	OFFICE	CPT	EXG	PT	PT	9'-0" EXG	EXG	
207	OFFICE	CPT	EXG	PT	PT	9'-0" EXG	EXG	
208	HALL	CPT	WD	PT	PT	9'-0"	ACT	
209	OFFICE	CPT	WD	PT	PT	9'-0"	ACT	1
210	OFFICE	CPT	WD	PT	PT	9'-0"	ACT	1
211	OFFICE	CPT	WD	PT	PT	9'-0"	ACT	1
212	MECHANICAL	VCT	VB	PT	PT	8'-0"	ACT	
213	OFFICE	CPT	WD	PT	PT	11'-0"	ACT	1
214	OFFICE	CPT	WD	PT	PT	11'-0"	ACT	1
215	OFFICE	CPT	WD	PT	PT	11'-0"	ACT	1
216	OFFICE	CPT	WD	PT	PT	11'-0"	ACT	1
217	KITCHEN	VCT	EXG	PT	PT	9'-0" EXG	EXG	
218	WASHROOM	CER	EXG	PT	PT	8'-0" EXG	EXG	
219	TOILET	CER	EXG	PT	PT	8'-0" EXG	EXG	
220	TOILET	CER	EXG	PT	PT	8'-0" EXG	EXG	
221	HALL	CPT	EXG	PT	PT	8'-0" EXG	EXG	
222	CLOSET	CPT	EXG	PT	PT	8'-0" EXG	EXG	
223	OPEN OFFICE	CPT	EXG	PT	PT	VARIES	EXG	2
224	CORRIDOR	CPT	EXG	PT	PT	VARIES	EXG	2

MATERIAL/FINISH ABBREVIATIONS

ACT ACOUSTICAL SUSPENDED CEILING
CPT CARPET
CER CERAMIC TILE
EXG EXISTING
PT PAINT
VB VINYL BASE
VCT VINYL COMPOSITION TILE
WD WOOD

NOTES

1. ADJUST CEILING HEIGHT AS NEEDED TO CLEAR WINDOW HEAD.
2. PAINT EXISTING GYPSUM BOARD CEILING.
3. NEW WALL AND CEILNG FINISHES MUST BE CLASS A OR CLASS B IN EXIT ACCESS CORRI
4. NEW WALL AND CEILNG FINISHES MUST BE CLASS A, CLASS B, OR CLASS C IN ALL OTHER AREAS.
5. ALL CARPET MATERIALS SHALL HAVE A MINIMUM CRITICAL RADIANT FLUX OF 0.1 W / CM SEE FLOORING PLAN FOR FLOORING LAYOUT.

DOOR TYPE 1
SCALE" 1/4" = 1'-0"
FRAMELESS GLASS DOOR

DOOR TYPE 2
SCALE" 1/4" = 1'-0"

FRAME TYPE A
SCALE" 1/4" = 1'-0"

FRAME TYPE A
SCALE" 1/4" = 1'-0"

1 TYPICAL DOOR JAMB CLEARANCES
SCALE: 1/4" = 1'-0"
1' 2' 4' 8'

4 ELEVATION
SCALE: 1/4" = 1'-0"
1' 2' 4' 8'

3 ELEVATION
SCALE: 1/4" = 1'-0"
1' 2' 4' 8'

2 ELEVATION
SCALE: 1/4" = 1'-0"
1' 2' 4' 8'

5 SECTION
SCALE: 3/4" = 1'-0"
4" 8" 1'-4" 2'-8"

© 2016 Michael R. Charek, Architect

CITY OF PORTLAND, MAINE — RESURGAM

Inspections Division
Date: 09/07/16

REGISTERED ARCHITECT — MICHAEL R. CHAREK No. 1174 — STATE OF MAINE

Second Floor Renovations

6 City Center
Portland, ME 04101

Title
SCHEDULES

Scale: 1/8" = 1'-0"

Date: 8/16/16

Revisions
ISSUED FOR PERMIT

Sheet
A2