1 FIRST FLOOR PLAN

SCALE: 1/8" = 1'-0"

2' 4' 8' 16'




2 ENLARGED PLAN

SCALE: 1/4" = 1'-0"

1' 2' 4' 8'

FIXTURE AND ACCESSORY NOTES:

1. PROVIDE SOLID WOOD BLOCKING IN WALL FOR MOUNTING OF ALL WALL-MOUNTED ITEMS.




3 BATHROOM FIXTURE MOUNTING HEIGHTS

SCALE: 1/4" = 1'-0"

3" 6" 1' 2'

**NOTES**

1. THIS PLAN SHOWS WORK ON THE EXTERIOR MASONRY WALLS AND WINDOWS, AND ON INTERIOR VACANT SPACE AS WELL AS THE EXISTING TOM VELLIEUX GALLERY. DASHED LINE SHOWS THE LIMIT OF WORK UNDER THSI PERMIT.
2. PLAN SHOWS LOCATIONS FOR LIFE SAFETY ELEMENTS IN RENOVATED SPACE. EXISTING LIFE SAFETY ELEMENTS IN SPACES NOT BEING RENOVATED ARE TO REMAIN IN SERVICE.
3. ITEMS SHOWN IN GREEN ARE FUTURE WORK, TO BE DONE UNDER A SEPARATE PERMIT.

**PARTITION TYPES**

P1 (STANDARD NEW PARTITION UNLESS NOTED OTHERWISE)
3 5/8" 20 GA. STEEL STUD FRAMING 16" O.C.
5/8" GYPSUM BOARD BOTH SIDES
ACOUSTIC INSULATION FULL HEIGHT
PARTITION HEAD ATTACHED TO CEILING GRID
ACOUSTICAL SEALANT AT FLOOR TRACK

P2 6" 20 GA. STEEL STUD FRAMING 16" O.C.
5/8" GYPSUM BOARD BOTH SIDES
ACOUSTIC INSULATION FULL HEIGHT
PARTITION HEAD UP TO DECK ABOVE, WITH SLIP TRACK, SAFING INSULATION, AND INTUMESCENT SEALANT
ACOUSTICAL SEALANT AT FLOOR TRACK

NOTE: PARTITIONS NOT OTHERWISE NOTED BY PARTITION TYPE ARE EXISTING TO REMAIN. PATCH AS NECESSARY AND PAINT.

PLAN NORTH
TRUE NORTH

© 2016 Michael R. Charek, Architect

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 09/20/16

**Michael Charek Architects**
25 Hartley Street
Portland, Maine 04103
(207) 761-0556

REGISTERED ARCHITECT
MICHAEL R. CHAREK
No. 1174
STATE OF MAINE

**6 City Center Exterior Renovations**
6 City Center
Portland, ME 04101

**Title**

FIRST FLOOR PLAN

REV. 9/19/16: H.C. TOILET ROOM DETAILS

**Scale:** 1/8" = 1'-0"

**Date:** 9/15/16

**Sheet**

# A1.2