1 GROUND FLOOR DEMOLITION PLAN

SCALE: 1/8" = 1'-0"

2' 4' 8' 16'

DEMOLITION KEY

EXISTING TO REMAIN

EXISTING TO BE REMOVED

DEMOLITION KEYNOTES -- DEMOLITION SHEETS ONLY

- D01 REMOVE WINDOW
- D02 REMOVE DOOR AND FRAME
- D03 REMOVE FIRE ESCAPE
- D04 REMOVE MASONRY FROM PREVIOUS EXISTING OPENING
- D05 CUT NEW WINDOW OPENING
- D06 CUT NEW ENTRY OPENING THROUGH MASONRY AND FOUNDATION
- D07 REMOVE PARTITION
- D08 REMOVE PLUMBING FIXTURES AND CAP OFF SUPPLY, WASTE, AND VENT PIPING
- D09 REMOVE CASEWORK
- D10 REMOVE ELECTRICAL PANELS FOR RELOCATING TO EXISTING TENANT SPACE

NOTES

1. THIS PLAN SHOWS WORK ON THE EXTERIOR MASONRY WALLS AND WINDOWS, AND A PORTION OF INTERIOR SPACE OCCUPIED BY THE EXISTING STYXX NIGHTCLUB. DASHED LINE SHOWS THE LIMIT OF WORK UNDER THIS PERMIT.

PLAN NORTH
TRUE NORTH

© 2016 Michael R. Charek, Architect

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 09/20/16

Michael Charek Architects

25 Hartley Street
Portland, Maine 04103
(207) 761-0556

REGISTERED ARCHITECT
MICHAEL R. CHAREK
No. 1174
STATE OF MAINE

6 City Center Exterior Renovations

6 City Center
Portland, ME 04101

Title

GROUND FLOOR DEMOLITION PLAN

Scale: 1/8" = 1'-0"

Date: 9/15/16

Sheet

D1.1