PROJECT NOTES

1. SCOPE OF WORK: SHALL INCLUDE THE REMOVAL/ RELOCATION OF 1 EXISTING COMMERCIAL STREET ENTRY DOOR.
2. HISTORIC PRESERVATION APPROVAL HAS BEEN OBTAINED.
3. ALL NEW WORK SHALL CONFORM TO THE CITY OF PORTLAND INSPECTIONS, FIRE, ZONING & HISTORIC PRESERVATION OFFICES.
4. ANY FIRE ALARM WORK SHALL BE INSTALLED ACCORDINGLY TO MEET NFPA 72, CITY OF PORTLAND & STATE FIRE MARSHAL REQUIREMENTS.
5. ALL FIRE RATED WALL PENETRATIONS SHALL BE UL APPROVED.
6. VERIFY EXISTING SPRINKLER HEAD COVERAGE FOR ADDED ENCLOSED AREA. ADD NEW SPRINKLER HEAD AS REQUIRED PER NFPA 72.
7. HVAC DUCT WORK AS SHOWN ON PLANS W/ UL APPROVED FIRE WALL PENETRATIONS
8. CONTACT THE ARCHITECT PRIOR TO WORK SHOULD DISCREPANCIES BE DISCOVERED DURING THE BUILDING PROCESS.

WALL LEGEND

- EXISTING WALL
- PROPOSED WALL
- FIRE RATED WALL
- WALL TO BE REMOVED

EXISTING PLAN @ COMMERCIAL STREET

SCALE: 1/4"=1'-0"

PROPOSED DOOR @ 165 COMMERCIAL STREET

EXISTING ADJACENT DOOR @ 163 COMMERCIAL STREET

PROPOSED WALL - INTERIOR

1 2x4 STUD WALL - (1HR RATED)
(UL DESIGN: U 301) FIRE CAULK PERIMETER

ALIGN FINISHES @ EXTERIOR WALL FACE & FIRE RATED WALL

* INSTALL ALL MATERIALS PER MANUFACTURE REQUIREMENTS

PROPOSED WALL - EXTERIOR

2 2x4 STUD WALL - (NON-RATED)
CAULK PERIMETER

ALIGN FINISHES @ EXTERIOR WALL FACE & FIRE RATED WALL

* INSTALL ALL MATERIALS PER MANUFACTURE REQUIREMENTS

EXTERIOR ELEVATION

SCALE: 1/2"=1'-0"

PROPOSED RENOVATION @ COMMERCIAL STREET EXIT

SCALE: 1/2"=1'-0"

BUILDING PERMIT SET: JUNE -, 2013

MARK MUELLER ARCHITECTS A.I.A.
100 Commercial Street
Suite 205
Portland, Maine 04101
Phone/Fax 207.774.9057
Email:
rfi@muellerarchitects.com

© COPYRIGHT 2013
MARK MUELLER ARCHITECTS

MOULTON BLOCK

5 MOULTON STREET
PORTLAND, MAINE

ENTRY DOOR:

REVISIONS	
DATE	June 2013
PROJECT	5 Moulton St.
DRAWN BY	MRP
CHECK BY	MLM

A-1.1