NOT IN SCOPE **L__**j

1 THIS AND ANY OTHER DEMOLITION DRAWINGS ARE NOT INTENDED TO BE ALL INCLUSIVE NOT TO DEFINE THE SLOPE OF WORK OF ALL DEMOLITION WORK REQUIRED FOR THIS PROJECT. DEMOLITION DRAWINGS ARE SHOWN ONLY TO AID THE CONTRACTOR IN PREPARING THE BID AND PERFORMING THE WORK. CONTRACTOR SHALL EXAMINE ALL CONSTRUCT DOCUMENTS AND VISIT THE SITE DURING BIDDING AS REQUIRED TO DETERMINE THE TOTAL. EXTENTS AND SCOPE OF THE DEMOLITION IRVING, TX 75038 PORTION OF THIS WORK, ALL ITEM'S ELECTRICAL, HVAC, PLUMBING, STRUCTURAL FINISH, ETC. THAT ARE NOT REQUIRED TO REMAIN. SHALL BE PART OF THE DEMOLITION WORK REQUIRED TO CARRY OUT WORK AS SHOWN IN THE CONSTRUCT DOCUMENTS.

2 EXTERIOR DIMENSIONS SHOWN TO EDGE OF SLAB, ALL OTHER

DIMENSIONS TO FACE OF STUD UNLESS NOTED OTHERWISE.

G.C. TO DISPOSE OF ALL WASTE DURING DEMOLITION IN ACCORDANCE WITH ALL APPLICABLE JURISDICTIONS, CODES, AND ORDINANCES. GC TO FIELD LOCATE AND DEACTIVATE IF REQUIRED -IN ALL WALLS TO 4 BE DEMOLISHED -ALL EXISTING "HOT" ELECTRICAL WIRING PRIOR TO

5 CONTRACTOR TO VERIFY ALL DIMENSIONS ON SITE AND NOTIFY ARCHITECT OF ANY DISCREPANCIES IMMEDIATELY PRIOR TO PROCEEDING.

REFER TO MEP PLANS FOR COORDINATION OF ALL EXISTING MECHANICAL,

6 ELECTRICAL AND PLUMBING. 9 ALL CONCRETE SAW CUTTING SHALL BE PREFORMED AT NIGHT 10 ALL LEFT OVER ELECTRICAL WIRING TO BE REMOVED

ALL PLUMBING ELEMENTS THAT WILL NO LONGER BE IN USE TO BE REMOVED AND CAPPED AS REQUIRED. KEY NOTES:

1 EXISTING DEMISING WALL TO REMAIN.

GENERAL NOTES

2 EXISTING CONCRETE SLAB TO REMAIN. GC TO INSURE EXISTING SLAB IS LEVEL FOR NEW TILE FINISH.

3 EXISTING DOOR AND FRAME TO REMAIN. 4 EXISTING STOREFRONT TO REMAIN. 5 EXISTING COLUMN TO REMAIN.

6 EXISTING STAIRWELL TO BE REMOVED. 7 EXISTING WALK-IN COOLER TO BE REMOVED.

8 EXISTING PLUMBING FIXTURES TO BE REMOVED. CAP AND/OR EXTEND LINES AS REQUIRED.

9 EXISTING ELECTRICAL PANEL BELONGING TO ADJACENT TENANT TO REMAIN.

10 EXISTING ELECTRICAL PANELS TO BE REMOVED. REFER TO ELECTRICAL FOR ADDITIONAL INFO.

11 EXISTING WALL TO BE REMOVED. PATCH AND/OR REPAIR SLAB AS ' REQUIRED.

12 EXISTING DOOR TO BE REMOVED.

13 EXISTING FLOORING TO BE REMOVED. 14 EXISTING WOOD FLOOR TO REMAIN.

15 EXISTING ROOF DRAIN, VERIFY IN FIELD.

16 REMOVE EXISTING LIGHTING 17 EXISTING LIGHTING TO REMAIN.

18 EXISTING WALL TO REMAIN. 19 EXISTING WALL UNIT TO BE REMOVED.

20 PARTIAL EXISTING WALL TO BE REMOVED TO MATCH ADJACENT CUT OUT.

21 REMOVE EXISTING HOOD AND ROOF EXHAUST

22 REMOVE EXISTING CONDENSING UNIT.

23 EXISTING CHAIR RAIL AND WAINSCOT TO BE REMOVED. PATCH AND/OR REPAIR FOR NEW FINISH.

WALL LEGEND

EXISTING WALL TO REMAIN

EXISTING WALL/ITEMS TO BE REMOVED.


ARCHITECT: THOMAS A. EDSON, RA 1431 GREENWAY DRIVE

PHONE 972.870.1288

SUITE 510

ELEVATION FRANCHISE VENTURES 4100 NORTH FAIRFAX DR. STE 730 ARLINGTON, VA 22203 703.243.7894

www.elevationburger.com



11/18/2013



DATE	DESCRIPTION
11/18/13	PERMIT ISSUE
	·

DEMOLITION SECOND FLOOR PLAN

D1.1

EVB130001