

**Tuesday, December 03, 2013****Quote #: 1907013****ELEVATION BURGER PORTLA
,ME BD**

To:
CHRIS DIMILLO
BETTER BURGER INC
1 LONG WHARF
PORTLAND, ME 04101
Phone: (207) 671-6420
MARK@DIMILLOS.COM

From:
Steve Duncan
CaptiveAire Systems
1720 West Park Center Dr
Ste C&D
Fenton, MO 63026
Local: (636) 225-3113
Toll Free: (800) 762-1078
Fax: (919) 227-5939
reg72@captiveaire.com

Ship-To:
ELEVATION BURGER
205 COMMERCIAL ST
PORTLAND, ME 04101

CaptiveAire Systems proposes to furnish the following equipment. Production of listed items will commence upon receipt of an approved proposal, a purchase order, an approved submittal, and approved credit.

EQUIPMENT**Hood #1 - GRILLE**

3347BD-2 - 5ft 6" Long Low Proximity Sloped Backshelf Hood with Quarter End Panels (shipped loose) and a Built-In 3" Back Standoff.	x1
- 430 SS Where Exposed	x1
- FILTER - 16" tall x 16" wide Kleen-Gard Stainless Steel Baffle Filter with Handles and Bottom Hanging Hook, UL Classified	x4
- Incandescent Light Fixture-High Temp Assembly, Includes Clear Thermal and Shock Resistant Globe (L55 Fixture), Bulbs By Others	x2
- EXHAUST RISER - Factory installed 10" X 10"	x1
- 1/2 Pint Grease Cup New Style, Flanged Slotted	x1
- FIELD WRAPPER 14.00" High Front, Left, Right	x1
- BACKSPLASH 80.00" High X 66.00" Long 430 SS (Includes End Caps & Divider Bars)	x1
- RIGHT QUARTER END PANEL 23" Top Width, 0" Bottom Width, 23" High 430 SS	x1
- LEFT QUARTER END PANEL 23" Top Width, 0" Bottom Width, 23" High 430 SS	x1

166MISC-PSP - 66.00" long Perforated stainless steel plenum	x1
- 430 SS Where Exposed	x1
- SUPPLY RISER - 12"x 28" Supply Riser with Volume Dampers	x1

Hood #3 - GRILLE

3347BD-2 - 5ft 6" Long Low Proximity Sloped Backshelf Hood with Quarter End Panels (shipped loose) and a Built-In 3" Back Standoff.	x1
- 430 SS Where Exposed	x1
- Fire Cabinet Wall Mounted (Additional charges may apply for cabinet if not sold with fire system)	x1
- FILTER - 16" tall x 16" wide Kleen-Gard Stainless Steel Baffle Filter with Handles and Bottom Hanging Hook, UL Classified	x4
- Incandescent Light Fixture-High Temp Assembly, Includes Clear Thermal and Shock Resistant Globe (L55 Fixture), Bulbs By Others	x2
- EXHAUST RISER - Factory installed 10" X 10"	x1
- 1/2 Pint Grease Cup New Style, Flanged Slotted	x1
- FIELD WRAPPER 14.00" High Front, Left, Right	x1
- BACKSPLASH 80.00" High X 66.00" Long 430 SS (Includes End Caps & Divider Bars)	x1
- RIGHT QUARTER END PANEL 23" Top Width, 0" Bottom Width, 23" High 430 SS	x1
- LEFT QUARTER END PANEL 23" Top Width, 0" Bottom Width, 23" High 430 SS	x1
- Face Mount 1st Switch	x1
- Face Mount Extra Switch(es)	x1
- Electrical Package Installation in Utility Cabinet by Plant.	x1
166MISC-PSP - 66.00" long Perforated stainless steel plenum	x1
- 430 SS Where Exposed	x1
- SUPPLY RISER - 12"x 28" Supply Riser with Volume Dampers	x1

Hood #5 - FRYER

3347BD-2 - 6ft 6" Long Low Proximity Sloped Backshelf Hood with Quarter End Panels (shipped loose) and a Built-In 3" Back Standoff.	x1
- 430 SS Where Exposed	x1
- FILTER - 16" tall x 16" wide Kleen-Gard Stainless Steel Baffle Filter with Handles and Bottom Hanging Hook, UL Classified	x1
- FILTER - 16" tall x 20" wide Kleen-Gard Stainless Steel Baffle Filter with Handles and Bottom Hanging Hook, UL Classified	x3
- Incandescent Light Fixture-High Temp Assembly, Includes Clear Thermal and Shock Resistant Globe (L55 Fixture), Bulbs By Others	x2
- EXHAUST RISER - Factory installed 10" X 15"	x1
- 1/2 Pint Grease Cup New Style, Flanged Slotted	x1

- FIELD WRAPPER 14.00" High Front, Left, Right	x1
- BACKSPLASH 80.00" High X 78.00" Long 430 SS (Includes End Caps & Divider Bars)	x1
- RIGHT QUARTER END PANEL 23" Top Width, 0" Bottom Width, 23" High 430 SS	x1
- LEFT QUARTER END PANEL 23" Top Width, 0" Bottom Width, 23" High 430 SS	x1
186MISC-PSP - 78.00" long Perforated stainless steel plenum	x1
- 430 SS Where Exposed	x1
- SUPPLY RISER - 12"x 20" Supply Riser with Volume Dampers	x2

Fire System #1

ANSUL-3.0/3.0-WC Ansul 6 gallon Fire System in Wall Mounted Utility Cabinet (includes pre-piped hood(s) with detection, tank(s), release mechanism, microswitches and pull station).Includes piping for hoods:.	x1
- GAS VALVE - 2" Mechanical Shutoff Valve (Ansul)(28-55610); SUPPLIED BY DISTRIBUTOR	x1

Fan #1 NCA10FA - Exhaust Fan (EF-1)GRILL HOOD

NCA10FA Belt Drive Centrifugal Upblast Exhaust Fan with 13.75" wheel Exhaust Fan handles 1100 CFM @ -0.750" wc ESP, Fan runs at 1151 RPM. Exhaust Motor: 0.500 HP, 3 Phase 208 V, 60Hz, 1.8 FLA, ODP (Open Drip Proof)	x1
- Grease Cup for kitchen-duty centrifugal exhaust fans, Box Dimensions 15-3/4 L X 5-1/16 W X 3-3/4 H (18 GA.) (Includes Down Spout)	x1
- EF-1 Curb CRB19.5X20E On Fan # 1 Flat Curb	x1
- Hinged Base for Curb. Standard Hinge attached to curb. Used on Fans with wheels 20 inches or smaller. 12 GA Galvanized.	x1
- Vented Base for Curb	x1

Fan #2 NCA16FA - Exhaust Fan (EF-2) GRILL & FRYER

NCA16FA Belt Drive Centrifugal Upblast Exhaust Fan with 18.75" wheel Exhaust Fan handles 2725 CFM @ -1.200" wc ESP, Fan runs at 1069 RPM. Exhaust Motor: 1.500 HP, 3 Phase 208 V, 60Hz, 4.7 FLA, ODP (Open Drip Proof)	x1
- Grease Cup for kitchen-duty centrifugal exhaust fans, Box Dimensions 15-3/4 L X 5-1/16 W X 3-3/4 H (18 GA.) (Includes Down Spout)	x1
- EF-2 Curb CRB26.5x20E On Fan # 2 Flat Curb	x1
- Hinged Base for Curb. Standard Hinge attached to curb. Used on Fans with wheels 20 inches or smaller. 12 GA Galvanized.	x1
- Vented Base for Curb	x1

Fan #3 A2-D.250-G15 - Heater (MUA-1)

- A2-D.250-G15 Direct Gas Fired Heated Make Up Air Unit with 15" Blower Supply Fan handles 3060 CFM @ 0.750" wc ESP, Fan runs at 879 RPM. Heater supplies 231336 BTUs. 70°F Temperature Rise. [Fuel: Natural Gas] Supply Motor: 2.000 HP, 3 Phase 208 V, 60Hz, 6.2 FLA, ODP (Open Drip Proof) x1
- Down Discharge - Air Flow Right -> Left
- Sloped Filtered Intake for Size #2 Modular Heater. 26.813" Wide X 53.625" Long X 31.313" High. Includes 2" MV EZ Kleen Metal Mesh Filters. x1
- RTC Solutions • 40-90°F Discharge Temp Control x1
- Gas Manifold for DF2 GM - BTU 0 - 825001 - 7 in. w.c. - 14 in. w.c., No Insurance Requirement (ANSI), BV250-88 x1
- Motorized Back Draft Damper 22.75" X 24" for Size 2 Standard & Modular Direct Fired Heaters w/Extended Shaft, Standard Galvanized Construction, 3/4" Rear Flange, LF120S Actuator Included x1
- Cooling Interlock Relay. 24VAC Coil. 120V Contacts. Locks out burner circuit when AC is energized. x1
- Low Fire Start. Allows the burner circuit to energize when the modulation control is in a low fire position. x1
- Gas Pressure Gauge, 0-35", 2.5" Diameter, 1/4" Thread Size x1
- Gas Pressure Gauge, -5 to +15 Inches Wc., 2.5" Diameter, 1/4" Thread Size x1
- MUA-1 Curb CRB31X79X20INS Insulated On Fan # 3 Flat Curb x1

Electrical System #1

- SC-321110FP 3 Phase w/ 2 Exhaust Fans, 1 Supply Fan, Exhaust on in Fire, Lights out in Fire, Fan(s) On/Off Thermostatically Controlled. Room temperature sensor shipped loose for field installation. Includes 3 Duct Thermostat kits. x1
- Digital Prewire Lighting Relay Kit. Includes hood lighting relay & terminal blocks. Allows for up to 1400W of lighting each. x1
- Thermistor CABLE - 18/2 AWG GREEN WHITE, plenum rated. USED for thermistor duct stat. Per Foot Price. x100
- CAT-5E CABLE - 50 Foot. x1

Subtotal:	\$14,933.78
Shipping:	\$961.08
Tax:	\$821.36
Total:	USD \$16,716.22