



7 Thomas Drive  
WESTBROOK, MAINE 04092  
(207) 874-1941  
FAX (207) 874-0933

# PROPOSAL

1276

Page 1 of 2

TO: Chris Dimillo  
1 Long Wharf  
Portland ME 04101

PHONE 671-3292	DATE 11/25/2013
JOB NAME/LOCATION Elevation Burgers Hood, Exhaust Fan , Make-up Air Unit & Gas piping Installation	
JOB NUMBER MSD/ #AFF238	JOB PHONE

We hereby submit specifications and estimates for:

Avery Family Fuels Is pleased to submit a quote to perform the following work:  
 Install three Captive Aire hoods and exhaust fans, equipment provided by others.  
 Install make-up air unit, unit provided by others, crane to set unit included.  
 Provide and install three 18GA welded galvanized duct riser one off each hood.  
 Provide and install a Fire blanket on each riser single wrap on the grille risers and double layer wrap hood riser over grease creating grille to meet Maine state code.  
 Provide and install 24GA galvanized ductwork on the make-up air unit, the duct to each of the three hoods will be wrapped with 1 1/2" insulation with a vapor barrier.  
 Provide and install gas piping kitchen equipment and make-up air unit.

**Installation of Ansul Suppression System: Scope of work:**

New kitchen hood suppression system: CaptiveAire is providing hoods with all hood pipes, heat detectors and nozzles. CaptiveAire will also be providing Automan, Pull Station and tanks with agent.  
 Simplex Grinnell (SG) will install pipe that is marked on the print as dotted lines. SG will not be providing and Ansul or suppression parts.  
 \* There is a gas shut off valve in place used by the old system. This valve may work for the new system providing the pipe does not change and that the valve is in good working condition.  
 \* If the suppression system needs to be shut off the kitchen electricity, a customer provided electrician will need to connect system to electrical panel.

We Propose hereby to furnish material and labor - complete in accordance with the above specifications, for the sum of:  
 Cont'd \_\_\_\_\_ dollars (\$) Cont'd \_\_\_\_\_).

Payment to be made as follows:

**\$8,341.00 upon Acceptance; progress Billing Net 5 days; All Balances upon substantial completion.**

If payment is not made as outlined above, a service charge of 2% per month on the overdue balance plus all reasonable costs of collection, including attorney's fees will be paid.

All material is guaranteed to be as specified. All work to be completed in a professional manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance. Our workers are fully covered by Worker's Compensation insurance.

**Acceptance of Proposal** - The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Authorized Signature   
 NOTE: This proposal may be withdrawn by us if not accepted within 30 days.  
 Signature   
 Signature \_\_\_\_\_

Date of Acceptance: \_\_\_\_\_



7 Thomas Drive  
WESTBROOK, MAINE 04092  
(207) 874-1941  
FAX (207) 874-0933

# PROPOSAL

1276

Page 2 of 2

TO: Chris Dimillo  
1 Long Wharf  
Portland ME 04101

PHONE 671-3292	DATE 11/25/2013
JOB NAME/LOCATION Elevation Burgers Hood, Exhaust Fan , Make-up Air Unit & Gas piping Installation	
JOB NUMBER MSD #AFF 238	JOB PHONE

We hereby submit specifications and estimates for:

**Removal of existing kitchen hood suppression system. Scope of work:**

Simplex Grinnell will remove the existing kitchen hood suppression system. Parts removal will include Automan, Gas Tank pull station and some piping near the Automan. Pipe from the Automan on through the hood will be taken out by those responsible for the interior demo.

**EXCLUSIONS:** Captive Aire hoods, exhaust fans, make-up air supplied other, roofwork and adequacy of existing systems.

*12/3/13  
DP # 8341  
CL # 1016*

We Propose hereby to furnish material and labor - complete in accordance with the above specifications, for the sum of:

**Sixteen Thousand Six Hundred Eighty Two and 00/100 Dollars**

dollars (\$

**16,682.00** )

Payment to be made as follows:

**\$8,341.00 upon Acceptance; progress Billing Net 5 days; All Balances upon substantial completion.**

If payment is not made as outlined above, a service charge of 2% per month on the overdue balance plus all reasonable costs of collection, including attorney's fees will be paid.

All material is guaranteed to be as specified. All work to be completed in a professional manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance. Our workers are fully covered by Worker's Compensation insurance.

**Acceptance of Proposal** - The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Authorized Signature

*[Handwritten Signature]*

NOTE: This proposal may be withdrawn by us if not accepted within

**30** days.

Signature

*[Handwritten Signature]*

Signature

Date of Acceptance: \_\_\_\_\_