217 Commercial Street Suite 205 Door Schedule

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 06/27/13

Floor	Description	Size	Swing	wall thichnes	Style	Door knobs
2nd floor						
1	Office Entrance	30-80	LH	2x4 4-3/4"	LH 60 Minute SCBirch unfinished CECO Prep 3068 DW-5 7/8 LH Steel SINGLE DRYWALL FRAME	Jupiter Entry set
2	Conf. Room	60-68	Mr/Mr	2x4 4-3/4"	DBL PR-1515 15LT 4 7/8* PRIMED DBL RBT JB NO CSG	Jupiter Dummy /bullet catch
3	Office #4	30-68	LH	2x4 4-3/4"	PR-1515 15LT 4 7/8* PRIMED DBL RBT JB NO CSG	Jupiter Passage
4	Office #3	30-68	LH	2x4 4-3/4"	PR-1515 15LT 4 7/8* PRIMED DBL RBT JB NO CSG	Jupiter Passage
5	Office #2	30-68	RH	2x4 4-3/4"	PR-1515 15LT 4 7/8* PRIMED DBL RBT JB NO CSG	Jupiter Passage
6	Executive office	30-68	RH	2x4 4-3/4"	PR-1515 15LT 4 7/8* PRIMED DBL RBT JB NO CSG	Jupiter Entry set
7	HVAC Closet	30-68	LH	2x4 4-3/4"	LH SCBirch unfinished CECO Prep 3068 DW-5 7/8 LH Steel SINGLE DRYWALL FRAME	Dead Bold
8	HVAC Closet	30-68	RH	2x4 4-3/4"	RH SCBirch unfinished CECO Prep 3068 DW-5 7/8 LH Steel SINGLE DRYWALL FRAME	Dead Bolt
1st Floor						
1	Closet door	30-68	LH	2x4 4-3/4"	Reuse existing 3060HCB 4 5/8 jamb	Jupiter Store Room

Notes: All walls are 3 1/2" wood or metal studs with single layer 5/8" fire code drywall

All door hardware is Schlage Jupiter Series ADA