

Dependable Hood & Duct Cleaning Company, LLC

424 Old Candia Road - Unit 1 Candia, NH 03034

603-483-0199

www.nhhoodcleaning.com
Service@dependablehood.com

Account :	Isa Bistro	Date of Service :	06/06/2023
Location :	Isa Bistro	Frequency :	180 days
Loc.Add :	79 Portland Street Portland, ME 04101	Tech Name:	Juan Arguello - EXHOOD-450914 - 12/31/23
Date :	06/07/2023		
Phone :	(207) 808-8533		

Service	Options	Comments
1. Are the filters clean?	Yes	Customer maintains their own filters.
2. Do any filters need replacement?	No	
3. Is the grease load less than 2000 microns: (Horizontal)	No	Horizontal ductwork was found at critical depth, our technicians were able to clean portions of it to 40% much of the horizontal duct is inaccessible due to obstructions in the ceiling.
4. Is the grease load less than 2000 microns: (Vertical)	No	Vertical ductwork was found with old neglected grease, our technicians were able to remove 90% of the buildup.
5. Is the grease load less than 2000 microns: (Hood)	No	Hood was found at critical depth with grease buildup, our technicians were able to remove 95% of the buildup
6. Is the fan grease load less than 3175 microns?	Yes	
7. Last cleaning/inspection date:	6/6/2023	1st cleaning with Dependable Hood and Duct Cleaning Co.
8. Did you clean or inspect the systems?	Cleaned/Inspected	
9. Was a Certificate of Performance placed on the hood?	Yes	
10. If a wash system, is the main valve in the open position?	N/A	
11. Are all filters in place?	Yes	
12. Do the fans operate?	Yes	
13. Have the duct dampers been cleaned/inspected?	N/A	
14. Were the exhaust fans cleaned?	Yes	An access port was installed to properly access and clean fan.
15. Were the hood grease cups cleaned?	Yes	
16. Does the system appear to be liquid tight?	Yes	
17. Have exhaust fan belts been inspected/are they working?	Yes	Customer performs maintenance of fan motors and belts.
18. Have horizontal ducts been cleaned or inspected?	Yes	
19. Have vertical ducts been cleaned or inspected?	Yes	
20. Are sufficient access panels provided?	Yes	May need to install in the future, TBD.
21. Is there proper signage on access panels?	Yes	
22. Are all areas of the systems accessible?	No	Most of the horizontal duct is inaccessible due to obstructions in the ceiling.
23. Are hoods and exhaust systems free of obstructions?	No	
24. Cleaning complies with NFPA '96?	Yes	
25. Type of Cooking systems solid fuel, charbroil or Wok?	Other	Flat Top Grill, Fryers, Stove Top, Oven
26. Are the frequencies adequate?	Yes	
27. Are the precipitators/pollution control clean?	N/A	
28. What condition is the rooftop surface in?	Good	
29. Are there deficiencies in these systems?	Yes	Inaccessible horizontal ductwork.
30. Are grease containment systems sufficient?	Yes	
31. Are there Type II duct systems?	No	

List deficiencies or comments related:

All systems were cleaned/inspected and a C.O.P was placed on the appropriate hoods.

A record of this service is to be maintained on premise and made available for inspection. It is the owner/tenant's responsibility to maintain the equipment in good working order. It is the responsibility of the cleaning/inspection company technician to report all deficiencies to the proper authority having jurisdiction. If deficiencies are found in these systems, please send a completed copy of this form to the local Fire Department within 48 hours.