

WPBB Outdoor Enclosure



Features

- ANSI/UL 464 listed
- Black box with side mount tabs
- Made of clear Lexan® providing maximum visibility and reliability
- Unit Dimensions: 5.75" (14.61 cm) high x 4.75" (12.10 cm) wide x 4.18" (10.62 cm) deep
- 3/4" conduit knockouts
- Reinforcement steel hardware
- Outdoor resistant gasket
- Available in red or off-white

Description

The Potter WPBB Outdoor Enclosure is ANSI/UL 464 listed for use in indoor and outdoor applications when used with the Potter EH Series horn and **Outdoor Series** strobe and horn/strobe.

WPLPBB Outdoor Enclosure



Features

- ANSI/UL 464 listed
- Back box with outdoor resistant seal for mounting to wall
- Made of clear Lexan® providing maximum visibility and reliability
- Unit dimensions: 5.75" (14.61 cm) high x 4.75" (12.10 cm) wide x 3.25" (8.255 cm) deep
- 3/4" conduit knockouts
- Reinforcement steel hardware
- Outdoor resistant gasket
- Available in red or off-white


Description

The Potter WPLPBB Low Profile Outdoor Enclosure that creates a surface mount look, is ANSI/UL 464 listed for use in indoor and outdoor applications when used with the Potter EH Series horn and **Outdoor Series** strobe and horn/strobe.

WPBB AND WPLPBB NOTES:

- Product does not meet ANSI/UL 1971 light distribution requirements
- To allow for drainage, the seal on the bottom edge is not water tight

WPLPBB Outdoor Enclosure




Features

- ANSI/UL 464 listed
- 1/2" conduit knockouts with metal washer reinforcement
- Wiremold knockouts for 500, 700 Series and pendulum mount
- Unit Dimensions: 6.20" (15.75 cm) square x 2.04" (5.18 cm) deep
- Reinforcement steel hardware
- Outdoor resistant gasket
- Available in red or off-white

Description

The Potter SPKRBB Outdoor Back Box is constructed of durable plastic is ANSI/UL 464 listed for use in indoor and outdoor applications when used with the WCSPKSTR Series speaker and speaker/strobe.

AVBB Surface Back Box



Features

- ANSI/UL listed for indoor use
- 1/2" conduit knockouts with metal washer reinforcement
- Wiremold knockouts for 500 and 700 Series
- Unit Dimensions: 5.57" (14.15 cm) high x 4.55" (11.56 cm) wide x 1.47" (3.73 cm) deep
- Screw heads hidden
- Available in red or off-white

Description

The Potter AVBB Surface Back Box is constructed of durable plastic and is fully compatible with the wall mount horns, strobes, and horn/strobes.

Alert & Agent Bezels



Features

- Easy to install
- ALERT or AGENT wording on both sides of bezel
- Available in red or off-white

Description

The Potter ALERT and AGENT bezels are constructed of durable plastic and is fully compatible with the wall mount horns, strobes, and horn/strobes.

CLNGBB Ceiling Surface Back Box



Features

- ANSI/UL listed for indoor use
- 1/2" conduit knockouts with metal washer reinforcement
- Wiremold knockouts for 500, 700 Series and pendulum mount
- Unit Dimensions: 6.2" (15.75 cm) round x 1.67" (4.24 cm) deep
- Screw heads hidden
- Available in red or off-white

Description

The Potter CLNGBB Surface Back Box is constructed of durable plastic and is fully compatible with the ceiling mount strobes and horn/strobes.