

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



# CITY OF PORTLAND BUILDING PERMIT

**This is to certify that**  
DYER'S VARIETY STORE

**Located at**  
45 PORTLAND ST

**PERMIT ID:** 2016-01432    **ISSUE DATE:** 07/08/2016    **CBL:** 033 C022001

has permission to **Awning for Dyer's Variety**  
**57' of signage on awning sf**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise cloed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

N/A

/s/ Jonathan Rioux

**Fire Official**

**Building Official**

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY  
THERE IS A PENALTY FOR REMOVING THIS CARD**

*Approved Property Use - Zoning*

*Building Inspections*

*Fire Department*

BUILDING PERMIT INSPECTION PROCEDURES  
Please call 874-8703 (ONLY)  
or email: [buildinginspections@portlandmaine.gov](mailto:buildinginspections@portlandmaine.gov)

**Check the Status or Schedule an Inspection On-Line at  
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

## **REQUIRED INSPECTIONS:**

Framing Only

Final Inspection

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

<b>City of Portland, Maine - Building or Use Permit</b>		<b>Permit No:</b> 2016-01432	<b>Date Applied For:</b> 05/31/2016	<b>CBL:</b> 033 C022001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
<b>Proposed Use:</b> Retail - Dyers Variety		<b>Proposed Project Description:</b> Awning for Dyer's Variety 57' of signage on awning sf		
<p><b>Dept:</b> Zoning      <b>Status:</b> Approved w/Conditions      <b>Reviewer:</b> Christina Stacey      <b>Approval Date:</b> 07/05/2016</p> <p><b>Note:</b> B-2b zone, multi-tenant 40' frontage = 60 sf max sign allowed Proposing 57 sf plus 15 sf existing projecting sign = 72 sf total. The awning signage of 57 sf is replacing existing awning signage of approx 72 sf - reduction OK.      <b>Ok to Issue:</b> <input checked="" type="checkbox"/></p> <p><b>Conditions:</b></p> <p>1) This permit is being approved on the basis of plans submitted. Any deviations shall require a separate approval before starting that work.</p>				
<p><b>Dept:</b> Building Inspecti      <b>Status:</b> Approved w/Conditions      <b>Reviewer:</b> Jonathan Rioux      <b>Approval Date:</b> 06/20/2016</p> <p><b>Note:</b>      <b>Ok to Issue:</b> <input checked="" type="checkbox"/></p> <p><b>Conditions:</b></p> <p>1) 3202.2.3 Awnings. The vertical clearance from the public right-of-way to the lowest part of any awning, including valances, shall be 7 feet minimum.</p> <p>3105.3 Design and construction. Awnings and canopies shall be designed and constructed to withstand wind or other lateral loads and live loads as required by Chapter 16 with due allowance for shape, open construction and similar features that relieve the pressures or loads. Structural members shall be protected to prevent deterioration. Awnings shall have frames of noncombustible material, fire-retardant-treated wood, wood of Type IV size, or 1-hour construction with combustible or noncombustible covers and shall be either fixed, retractable, folding or collapsible.</p> <p>3105.4 Canopy materials. Canopies shall be constructed of a rigid framework with an approved covering that meets the fire propagation performance criteria of NFPA 701 or has a flame spread index not greater than 25 when tested in accordance with ASTM E 84 or UL 723.</p>				