



EQUIPMENT SCHEDULE

MK.	QTY	DESCRIPTION
1	2	SHELVING UNIT
2	1	WALK-IN COOLER
3	1	EVAPORATOR COIL, COOLER
4	1	COMPRESSOR, COOLER
5	1	WALK-IN FREEZER
6	1	EVAPORATOR COIL, FREEZER
7	1	COMPRESSOR, FREEZER
8	7	SHELVING UNIT
9	1	TRAY/SILVERWARE DISPENSER
10	1	MIXER, 40-QUART
11	1	HOT FOOD COUNTER
12	1	HOT FOOD WELLS
13	1	FOOD PROTECTOR
14	3	HAND SINK
15	1	COLD FOOD COUNTER
16	1	COLD FOOD WELLS
17	1	FOOD PROTECTOR
18	1	SLICER
19	1	REFRIGERATOR, WORK TOP
20	1	WORK TABLE WITH SINKS
21	1	TRAY SLIDE
22	1	TRAY SLIDE
23	1	SHELF, WALL CAP
24	1	WORK TABLE
25	2	WALL SHELF
26	1	FOOD PROCESSOR
27	2	FRYER
28	1	EQUIPMENT STAND, FREEZER BASE
29	1	GRIDDLE, COUNTERTOP
30	1	CHAR-BROILER, COUNTERTOP
31	-	- SPARE NUMBER -
32	1	RANGE, 8-BURNER
33	1	STEAMER, CONNECTIONLESS
34	1	CONVECTION OVEN, DOUBLE
35	1	EXHAUST HOOD (BY OTHERS)
36	1	HEATED/HOLDING CABINET
37	1	SALAD BAR
38	1	SNEEZE GUARD
39	-	- SPARE NUMBER -
40	1	DISHTABLE, SOILED
41	1	DISPOSER
42	1	CONDENSATE HOOD (BY OTHERS)
43	1	DISHWASHER WITH BOOSTER HEATER
44	1	SINK, 3-COMPARTMENT
45	1	DISHTABLE, CLEAN
46	-	- SPARE NUMBER -
47	1	MILK DISPENSER
48	1	COFFEE BREWER, DUAL SH
49	1	ICE/BEVERAGE DISPENSER
50	2	ICE MACHINE
51	1	TOASTER, HORIZONTAL CONVEYOR
52	1	MICROWAVE OVEN

NOTES:

- ELECTRICAL CONTRACTOR TO RUN CONTROL WIRING BETWEEN EVAPORATORS AND REMOTE CONDENSING UNITS FOR WALK-IN COOLER AND FREEZER. CO-ORDINATE WITH KITCHEN EQUIPMENT CONTRACTOR (K.E.C).
- ELECTRICAL CONTRACTOR TO INSTALL SEAL-OFF FITTINGS ON ALL CONDUIT PENETRATING WALK-IN COOLER AND FREEZER.
- ELECTRICAL CONTRACTOR TO PROVIDE 115 VOLT W/P RECEPTACLE IN FREEZER FOR DRAIN LINE HEAT TAPE. HEAT TAPE FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR.
- PLUMBING CONTRACTOR TO INSTALL VACUUM BREAKER, SOLENOID VALVE, AND FLOW CONTROL VALVE (FURNISHED) IN COLD WATER LINE TO DISPOSER.
- KITCHEN EQUIPMENT CONTRACTOR TO PROVIDE GAS REGULATING VALVES FOR ALL GAS OPERATED KITCHEN EQUIPMENT.
- FLOOR DRAIN REQUIRES FLOW RATE OF 5 G.P.M.
- PLUMBING CONTRACTOR TO INSTALL ALL DRAINS AND FAUCETS SUPPLIED BY KITCHEN EQUIPMENT CONTRACTOR.
- PLUMBING CONTRACTOR TO FURNISH AND INSTALL ALL INDIRECT DRAIN INTERPIPING TO FLOOR DRAINS.
- PLUMBING CONTRACTOR TO INSTALL GAS REGULATORS ON ALL GAS EQUIPMENT. REGULATORS BY K.E.C.
- PLUMBING CONTRACTOR TO IGNITE ALL GAS PILOTS AND ASSIST K.E.C. AND FACTORY REP'S IN START-UP AND DEMONSTRATION OF EQUIPMENT.
- ELECTRICAL CONTRACTOR TO INTERWIRE SOLENOID VALVE AND CONTROL PANEL TO DISPOSER.
- GENERAL CONTRACTOR TO PROVIDE ALL REQUIRED WALL BACKING AS DIRECTED BY K.E.C.
- GENERAL CONTRACTOR TO PROVIDE ALL REQUIRED SLEEVES THROUGH BUILDING FOR REMOTE REFRIGERATION LINES. REFRIGERATION LINES BY K.E.C.

Bild Architecture
 PO Box 8235
 Portland, ME 04104
 207.408.0168
 evan@bildarchitecture.com

Foodservice Consultant
TJM CONSULTING INC.
 TJM Consulting, Inc.
 273 Main Street, Suite 5
 Yarmouth, Maine 04096
 (207) 215-4736

PROJECT NO. **15031**
 PROJECT NAME **SALVATION ARMY ARC PORTLAND, ME**

REVISIONS

1	-
2	-
3	-
4	-
5	-

Drawn by Construction Document
TJM
 SHEET TITLE **FOODSERVICE EQUIPMENT FLOOR PLAN AND SCHEDULE**

ISSUE DATE **10/25/16**
 SHEET SCALE **1/4" = 1'-0"**

FS
100