


**LEGEND – ELECTRICAL CONNECTIONS**

- |  |  |  |   |
|--|--|--|---|
|  | DUPLEX RECEPT., 20-AMP, 120-VOLT, GROUND TYPE, HORIZONTAL MOUNT                  |  | ELECTRICAL CONDUIT, STUB AS INDICATED FOR DIRECT CONNECTION |
|  | SIMPLEX RECEPT., 20-AMP, 120-VOLT, GROUND TYPE, HORIZONTAL MOUNT                 |  | FLOOR/CEILING RECEPTACLE AS INDICATED                       |
|  | SPECIAL PURPOSE OUTLET, 120-VOLT, GROUND TYPE, HORIZONTAL MOUNT                  |  | ISOLATED GROUND – FOR POS SYSTEM                            |
|  | SPECIAL PURPOSE OUTLET, 208/240-VOLT AS INDICATED, GROUND TYPE, HORIZONTAL MOUNT |  | WP WATERPROOF COVER AT RECEPTACLE                           |
|  | JUNCTION BOX   |  | FIELD WIRING, EXPOSED RIGID WATERTIGHT CONDUIT              |
|  |  |  | FIELD WIRING, CONCEALED IN WALL, FLOOR, OR CEILING          |

**ELECTRICAL CONNECTION SCHEDULE**

- E-2 15 FL AMPS, 120-V, 1-PH SERVICE, STUB FROM CEILING AND CONNECT AT ITEM 2, WALK-IN COOLER.
- E-3 1.4 FL AMPS, 208-230-V, 1-PH SERVICE, STUB FROM CEILING AND CONNECT AT ITEM 3, EVAPORATOR COIL, COOLER.
- E-4 9.6 FL AMPS, 1HP, 208-230-V, 1-PH SERVICE, STUB UPON ROOF AND CONNECT AT ITEM 4, COMPRESSOR, COOLER; VERIFY LOCATION.
- E-5 15 FL AMPS, 120-V, 1-PH SERVICE, STUB FROM CEILING AND CONNECT AT ITEM 5, WALK-IN FREEZER.
- E-6 4.2 FL AMPS, 0.5-KW, 120-V, 1-PH SERVICE, DUPLEX ELECTRIC OUTLET AT 6'-0"-AFF FOR SERVICE TO ITEM 6, EVAPORATOR COIL, FREEZER.
- E-6b 6.4 FL AMPS, 208-230-V, 1-PH SERVICE, STUB FROM CEILING AND CONNECT AT ITEM 6, EVAPORATOR COIL, FREEZER.
- E-7 14.1 FL AMPS, 1HP, 208-230-V, 1-PH SERVICE, STUB UPON ROOF AND CONNECT AT ITEM 7, COMPRESSOR, FREEZER.
- E-10 7 FL AMPS, 2-HP, 208-V, 3-PH SERVICE, SPECIAL PURPOSE ELECTRIC OUTLET AT 4'-2"-AFF FOR SERVICE TO ITEM 10, MIXER, 40-QUART.
- E-12 20.4 FL AMPS, 4.25-KW, 208-V, 1-PH SERVICE, SPECIAL PURPOSE ELECTRIC OUTLET AT 24"-AFF FOR SERVICE TO ITEM 12, HOT FOOD WELLS.
- E-16 6.0 FL AMPS, 1/4-HP, 120-V, 1-PH SERVICE, DUPLEX ELECTRIC OUTLET AT 24"-AFF FOR SERVICE TO ITEM 16, COLD FOOD WELLS.
- E-18 5.4 FL AMPS, 1/2-HP, 120-V, 1-PH SERVICE, CEILING OUTLET FOR SERVICE TO ITEM 18, SLICER; DROP CORD OUTLET, D.F.A..
- E-19 13.7 FL AMPS, 1/3-HP, 115-V, 1-PH SERVICE, FLOOR PEDESTAL OUTLET, FOR SERVICE TO ITEM 19, REFRIGERATOR, WORK TOP.
- E-26 7 FL AMPS, 1HP, 120-V, 1-PH SERVICE, CEILING OUTLET FOR SERVICE TO ITEM 26, FOOD PROCESSOR; DROP CORD OUTLET, D.F.A..
- E-28 5.7 FL AMPS, 1/4-HP, 115-V, 1-PH SERVICE, DUPLEX ELECTRIC OUTLET AT 24"-AFF FOR SERVICE TO ITEM 28, EQUIPMENT STAND, FREEZER BASE.
- E-33 28 FL AMPS, 10-KW, 208-V, 3-PH SERVICE, SPECIAL PURPOSE ELECTRIC OUTLET AT 4'-2"-AFF FOR SERVICE TO ITEM 33, STEAMER, CONNECTIONLESS.
- E-34 6 FL AMPS, 1/2-HP, 115-V, 1-PH SERVICE, DUPLEX ELECTRIC OUTLET AT 24"-AFF FOR SERVICE TO ITEM 34, CONVECTION OVEN, DOUBLE.
- E-34b 6 FL AMPS, 1/2-HP, 115-V, 1-PH SERVICE, DUPLEX ELECTRIC OUTLET AT 4'-2"-AFF FOR SERVICE TO ITEM 34, CONVECTION OVEN, DOUBLE.
- E-36 13.8 FL AMPS, 1.65-KW, 120-V, 1-PH SERVICE, DUPLEX ELECTRIC OUTLET AT 24"-AFF FOR SERVICE TO ITEM 36, HEATED/HOLDING CABINET.
- E-37 7 FL AMPS, 1/4-HP, 115-V, 1-PH SERVICE, DUPLEX ELECTRIC OUTLET AT 18"-AFF FOR SERVICE TO ITEM 37, SALAD BAR.
- E-41 3.3 FL AMPS, 2-HP, 208-V, 3-PH SERVICE, STUB OUT WALL AT 24"-AFF AND CONNECT AT ITEM 41, DISPOSER.
- E-43 45.5 FL AMPS, 208-V, 3-PH SERVICE, STUB OUT WALL AT 24"-AFF AND CONNECT AT ITEM 43, DISHWASHER WITH BOOSTER HEATER.
- E-47 1.4 FL AMPS, 1/10-HP, 115-V, 1-PH SERVICE, DUPLEX ELECTRIC OUTLET AT 4'-2"-AFF FOR SERVICE TO ITEM 47, MILK DISPENSER.
- E-48 28.3 FL AMPS, 5.9-KW, 120/208-V, 1-PH SERVICE, STUB OUT WALL AT 4'-2"-AFF AND CONNECT AT ITEM 48, COFFEE BREWER, DUAL SH.
- E-49 2.8 FL AMPS, 120-V, 1-PH SERVICE, STUB OUT WALL AT 24"-AFF AND CONNECT AT ITEM 49, ICE/BEVERAGE DISPENSER.
- E-50 14.4 FL AMPS, 115-V, 1-PH SERVICE, STUB OUT WALL AT 7'-0"-AFF AND CONNECT AT ITEM 50, ICE MACHINE.
- E-51 18.5 FL AMPS, 3.8-KW, 208-V, 1-PH SERVICE, SPECIAL PURPOSE ELECTRIC OUTLET AT 4'-2"-AFF FOR SERVICE TO ITEM 51, TOASTER, HORIZONTAL CONVEYOR.
- E-52 16 FL AMPS, 2-KW, 120-V, 1-PH SERVICE, SPECIAL PURPOSE ELECTRIC OUTLET AT 4'-2"-AFF AND CONNECT AT ITEM 52, MICROWAVE OVEN.
- C.O. 15.0 FL AMPS, 115-V, 1-PH SERVICE, DUPLEX ELECTRIC OUTLET AT 4'-2"-AFF FOR SERVICE TO CONVENIENCE OUTLET.



REVISIONS

1	-
2	-
3	-
4	-
5	-