

**LEGEND – PLUMBING CONNECTIONS**

- HW–HOT WATER, OR CW–COLD WATER
- S–STEAM SUPPLY, OR C–CONDENSATE RETURN
- GAS SUPPLY
- WASTE, DIRECT–CONNECTED UNLESS NOTED "OPEN HUB"
- FLOOR SINK WITH HALF GRATE UNLESS NOTED OTHERWISE
- ⊗ FLOOR DRAIN
- ⊗ FLOOR DRAIN W/ATTACHED FUNNEL
- FIELD CONNECTIONS

**PLUMBING CONNECTION SCHEDULE**

- P-3 FUNNEL TYPE FLOOR DRAIN, 3/4" INDIRECT WASTE FROM ITEM 3, EVAPORATOR COIL, COOLER. ALSO SERVES ITEMS 6 AND 50.
- P-12 FLOOR SINK, HALF-GRATE, 3/4" INDIRECT WASTE FROM ITEM 12, HOT FOO WELLS.
- P-14 1/2" HOT WATER, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 14, HAND SINK.
- P-14b 1/2" COLD WATER, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 14, HAND SINK.
- P-14c 1-1/2" DIRECT WASTE HUB, STUB OUT WALL AT 24"-AFF, CONNECT AT ITEM 14, HAND SINK.
- P-16 FLOOR SINK, HALF-GRATE, 3/4" INDIRECT WASTE FROM ITEM 16, COLD FOOD WELLS.
- P-20 FLOOR SINK, HALF-GRATE, 2" INDIRECT WASTE FROM ITEM 20, WORK TABLE WITH SINKS, AT 16"-AFF.
- P-20b 1/2" HOT WATER, 1 STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 20, WORK TABLE WITH SINKS, AT 38"-AFF.
- P-20c 1/2" COLD WATER, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 20, WORK TABLE WITH SINKS, AT 38"-AFF.
- P-27 3/4" GAS SUPPLY, 90-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 27, FRYER, AT 11"-AFF.
- P-29 3/4" GAS SUPPLY, 84.9-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 29, GRIDDLE, COUNTERTOP, AT 30"-AFF.
- P-30 3/4" GAS SUPPLY, 80-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 30, CHAR-BROILER, COUNTERTOP, AT 30"-AFF.
- P-32 1" GAS SUPPLY, 275-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 32, RANGE, 8-BURNER, AT 30"-AFF.
- P-34 3/4" GAS SUPPLY, 110-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 34, CONVECTION OVEN, DOUBLE, AT 30"-AFF.
- P-37 FLOOR DRAIN, 3/4" INDIRECT WASTE FROM ITEM 37, SALAD BAR
- P-40 1/2" COLD WATER, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 40, DISHTABLE, SOILED, AT 38"-AFF; ALSO CONNECT AT ITEMS 41.
- P-40b 1/2" HOT WATER, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 40, DISHTABLE, SOILED, AT 38"-AFF.
- P-41 2" DIRECT WASTE HUB, STUB OUT WALL AT 12"-AFF, CONNECT AT ITEM 41, DISPOSER.
- P-43 3" HUB DRAIN, STUB UP 4"-AFF, 1-1/2" WASTE OUTLET, CONNECT AT ITEM 43, DISHWASHER WITH BOOSTER HEATER.
- P-43b 3/4" HOT WATER, STUB OUT WALL AT 8"-AFF AND CONNECT AT ITEM 43, DISHWASHER WITH BOOSTER HEATER.
- P-43c 1/2" COLD WATER, STUB OUT WALL AT 8"-AFF AND CONNECT AT ITEM 43, DISHWASHER WITH BOOSTER HEATER.
- P-44 2" DIRECT WASTE HUB, STUB OUT WALL AT 8"-AFF, CONNECT AT ITEM 44, SINK, 3-COMPARTMENT.
- P-44b 1/2" HOT WATER, 1 STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 44, SINK, 3-COMPARTMENT.
- P-44c 1/2" COLD WATER, STUB OUT WALL AT 18"-AFF AND CONNECT AT ITEM 44, SINK, 3-COMPARTMENT
- P-48 1/4" COLD WATER, STUB OUT WALL AT 54"-AFF AND CONNECT AT ITEM 48, COFFEE BREWER.
- P-50 3/8" COLD WATER, STUB OUT WALL AT 54"-AFF AND CONNECT AT ITEM 50, ICE MACHINE.
- P-50b FLOOR SINK, HALF-GRATE, 1/2" INDIRECT WASTE FROM ITEM 50, ICE MACHINE.

ISSUE DATE  
**10/25/16**  
SHEET SCALE  
**1/4" = 1'-0"**


DRAWN BY  
**TJM**  
SHEET TITLE  
**FOODSERVICE EQUIPMENT FLOOR PLAN AND SCHEDULE**

REVISIONS

1	-
2	-
3	-
4	-
5	-

PROJECT NO.  
**15031**  
PROJECT NAME  
**SALVATION ARMY ARC PORTLAND, ME**

Foodservice Consultant  
**TJM CONSULTING INC.**  
TJM Consulting, Inc.  
272 Main Street, Suite 5  
Yarmouth, Maine 04096  
(207) 215-4736



**Bild Architecture**  
PO Box 8235  
Portland, ME 04104  
207.408.0168  
evan@bildarchitecture.com