

PLUMBING FIXTURE SCHEDULE

FIXTURE	DESCRIPTION	COLD WATER (IN)	HOT WATER (IN)	WASTE (IN)	CONNECTION TYPE	GAS (IN)	GAS (BTUH)	NOTES
P-30	CHAR BROILER	-	-	-	-	¾	80,000	
P-48	COFFEE BREWER	¼	-	-	-	-	-	
P-34	CONVECTION OVEN	-	-	-	-	¾	110,000	
P-44	DISH TABLE - CLEAN WITH POT SINKS	½	½	2	DIRECT	-	-	DRAINS TO GREASE INTERCEPTOR
P-41	DISH TABLE - SOILED WITH DISPOSER	½	½	2	DIRECT	-	-	DRAINS TO GREASE INTERCEPTOR
P-43	DISHWASHER - COMMERCIAL	½	¾	2	DIRECT	-	-	INCLUDES BOOSTER HEATER
P-100	DISHWASHER - RESIDENTIAL	½	½	1-1/2	DIRECT	-	-	
P-3	FLOOR DRAIN - FUNNEL TYPE	-	-	1-1/2	-	-	-	
P-101	FLOOR DRAIN WITH CLEANOUT	½	-	2	DIRECT	-	-	1/2 COLD WATER TO TRAP PRIMER
P-50B / P-20D	FLOOR SINK - HALF GRATE	-	-	2	-	-	-	
P-27	FRYER	-	-	-	-	¾	90,000	
P-29	GRIDDLE	-	-	-	-	¾	84,900	
P-14	HAND SINK	½	½	1-1/2	DIRECT	-	-	
P-102	HOSE BIBB	-	-	-	-	-	-	
P-32	HOT PLATE	-	-	-	-	¾	100,000	
P-50	ICE MACHINE	3/8	-	-	INDIRECT	-	-	
	ICE MACHINE FLOOR MOUNTED							
P-103	KITCHEN SINK	½	½	2	DIRECT	-	-	
P-104	LAVATORY - COMMERCIAL	½	½	1-1/2	DIRECT	-	-	
P-105	LAVATORY - RESIDENTIAL	½	½	1-1/2	DIRECT	-	-	
P-106	SHOWER	½	½	2	DIRECT	-	-	
P-107	WASHING MACHINE & DRYER	½	½	2	INDIRECT	-	-	
P-108	WATER CLOSET - COMMERCIAL	1	-	4	DIRECT	-	-	
P-109	WATER CLOSET - RESIDENTIAL	½	-	4	DIRECT	-	-	
P-110	WATER HEATER	1	1	-	-	-	-	INDIRECT WATER HEATER SERVED BY EXISTING BOILERS.
P-20	WORK TABLE SINK	½	½	2	INDIRECT	-	-	

INDIRECT WATER HEATER SCHEDULE

TAG	SERVICE	TYPE	FIRST HOUR RATING (140 DEG F)	BOILER FLOW RATE (GPM)	PRESSURE DROP (FT)	MANUFACTURER	MODEL	NOTES
IDWH-1	KITCHEN DOMESTIC HOT WATER	INDIRECT	266	10	7.9	HTP	SUPERSTOR SSU-60	1

NOTES:

1. SERVED BY EXISTING VIESSMANN NATURAL GAS BOILERS. WILL REQUIRE RECONFIGURATION OF THE EXISTING PIPING.

PUMP SCHEDULE

TAG	SERVICE	TYPE	GPM	HEAD (FT)	HP	VPH	AMPS	MANUFACTURE R	MODEL	NOTES
P-2	DOMESTIC HOT WATER RECIRCULATING PUMP	INLINE CIRCULATOR	11.5	9.5	1/40	115/1/60	0.57	TACO	006-PNP (IFC)	1
P-3	INDIRECT WATER HEATER CIRCULATING PUMP	INLINE CIRCULATOR	22	13	1/6	15/1/60	2	TACO	0013-F3	

NOTES:

1. AUTOMATICALLY SET TO CIRCULATE PERIODICALLY.



REVISIONS

1	
2	
3	
4	
5	