



GENERAL NOTES

1. DROP DOWN FROM BRANCH DUCTING TO ALL SUPPLY AIR DIFFUSERS IN THE SEATING AREA SO THAT THEY ARE LEVEL WITH THE LIGHTS. APPROXIMATELY 11 FEET ABOVE FINISHED FLOOR. COORDINATE WITH ARCHITECT.
2. SEE DRAWING M501 FOR ROOF CURB AND EQUIPMENT MOUNTING DETAILS.
3. ROOF OPENINGS SIZES TO BE DETERMINED BASED ON SUBMITTED EQUIPMENT SPECIFICATIONS. ROOF OPENINGS SHOWN ARE BASED ON SCHEDULED EQUIPMENT.

KEY NOTES

- ① GOOSENECK OPENING TO BE MINIMUM 24" ABOVE ROOF. PROVIDE BIRDSCREEN, FLASH AND WATERPROOF AT ROOF PENETRATION.

① **DINING HALL HVAC ROOF PLAN**
1/8" = 1'-0"

REVISIONS

1	
2	
3	
4	
5	