

project name

Schlotterbeck Block

117 Preble Street
Portland, Maine

Schlotterbeck Block LLC


goduti/thomas architects


44 oak st.

portland, maine 04101


ph. 207-775-3184

fax 207-774-0846

 hatch indicates area where masonry needs to be cut and reported
see detail O sheet A5.0

 hatch indicates area where masonry needs to be repaired and reported
see detail O sheet A5.0

 repair spalled cast stone

 spalled cement coating repair

WINDOW STEEL LINTEL SCHEDULE

- type A: original lintel has been replaced
no work necessary
- type B: original lintel in place
repair, replace
- type C: replace existing lintel
with new galvanized lintel
- type B/C: either repair or replace
inspect with lift.


- NOTES:
- wash all brick
product: Eco Chem, Restore One
 - remove all loose cement based waterproof coating on existing cast stone
apply new coating layer over all existing cast stone
 - cut and point all brick to cast stone joints and all cast stone to cast stone joints

revisions

date
october 2015

sheet title

masonry repair elevations



scale
1/8"=1'-0"

drawn by
MS

project number
brewer


sheet number

A2.4



Kennebec St. elevation



 **CITY OF PORTLAND**
APPROVED SITE PLAN
Subject to Conditions of Approval
and Standard Conditions
DATE OF APPROVAL 12.15.2015
PLANNER Shukria Wiar
PROJECT NO. 2015-174

Elm St. elevation