



SECOND FLOOR PLAN

SCALE: 1/8" = 1'-0"

GENERAL NOTES:

1. 6'-0" WIDE SLIDING GLASS DOORS SHALL HAVE A MINIMUM 32" CLEAR OPENING WHEN FULLY OPEN. DOOR HARDWARE AND THRESHOLD SHALL CONFORM TO ADA ACCESSIBILITY GUIDELINES AND ANSI A117.1-1991 STANDARDS.
2. ALL PEDESTRIAN DOORS SHALL BE A MINIMUM OF 3'-0" WIDE. ALL HARDWARE SHALL MEET ADA STANDARDS. OPERATING HARDWARE SHALL HAVE LEVER HANDLES.
3. BRAILED SIGNAGE CONFORMING TO THE ADA ACCESSIBILITY GUIDELINES, AND ANSI A117.1-1991 STANDARDS SHALL BE PROVIDED AT ALL TOILET ROOMS, EXITS, AND STAIRWAY, AND AT ANY OTHER ROOMS OR AREAS THAT WILL BE SIGN DESIGNATED.
4. BUILDING SHALL BE PROVIDED WITH AN EMERGENCY LIGHTING SYSTEM CONFORMING TO THE REQUIREMENTS OF SECTION 5-9 OF THE NFPA 101 LIFE SAFETY CODE.
5. BUILDING SHALL BE PROTECTED THROUGHOUT BY AN APPROVED SUPERVISED AUTOMATIC

1. A FIRE ALARM SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH SECTION 7-4 OF THE NFPA 101 LIFE SAFETY CODE AND SHALL CONFORM TO APPLICABLE REQUIREMENTS OF NFPA TO NATIONAL ELECTRIC CODE, AND NFPA NATIONAL FIRE ALARM CODE.
 8. THE FIRE ALARM SYSTEM SHALL BE INITIATED BY MANUAL MEANS OR AT THE OPTION OF THE OWNER BY MEANS OF THE APPROVED AUTOMATIC SPRINKLER SYSTEM.
- ### NEW (N) TOILET ROOM NOTES
9. INSTALL 1 1/2" DIA. X 34" LONG GRAB BARS AT REAR OF WATER CLOSETS AND 1 1/2" DIA. X 42" LONG GRAB BARS ALONG SIDE OF WATER CLOSETS. MOUNT GRAB BARS 9 3/4" ABOVE FINISH FLOOR TO CENTERLINE OF GRAB BARS.
 10. PROVIDE WATER CLOSETS WITH TOP OF SEAT BETWEEN 17'-0" ABOVE FINISH FLOOR.
 11. WALL HUNG URINAL SHALL HAVE AN ELONGATED RIM AND SHALL BE MOUNTED AT A RIM HEIGHT OF 17" ABOVE FINISH FLOOR.

RELOCATE WOMENS TOILET ROOM DOOR TO PROVIDE A MINIMUM 12" LATCHSIDE CLEARANCE FROM WALL TO DOOR EDGE ON PUSH SIDE