

Protection Professionals

325 U.S. Route 1
 Falmouth, ME 04105
 Ph 207-775-5755
 Fax 207-781-2064

Device List

No. **6527**

List Date
4/23/2014

Bill To Name / Address
Efficiency Electric Inc. Attn: Accounts Payable 356 Center Road Windham, Maine 04062

Job Site
353 Cumberland Avenue Central Office/FIRE 353 Cumberland Avenue Portland, ME 04101

CHANGING THIS DEVICE LIST DOES NOT ALTER THE ORIGINAL ESTIMATE
Attach copy to Purchase Order for accounting

Estimate No.

Item	Description	Qty To Order	Qty Ordered
	This quote is based upon the floor plans only, EP100 dated 3-12-14. The current fire alarm system is a conventional Silent Knight 5208. This is not an addressable fire alarm panel as specified. However all of the devices in the building would have to be replaced which is contrary to the floor plans. No devices would be existing and the scope of work would have to include the entire building instead of one floor.		
BK-2WB	Conventional devices only: Smoke Detector 2-wire	6	
AX-AL802ULADA	NAC power supply, 8 amps, two Class A or four Class B circuits at 2.5 amps each, 1 amp Aux power	1	
Bat 12-7	12V 7AH Batteries SEC-1075	2	
BK-P2R	Horn/strobe, wall mount, red, 15cd, 15/75cd, 30cd, 75cd, 95cd, 110cd, or 115cd	16	
BK-SR	Strobe, red, 15cd, 15/75cd, 30cd, 75cd, 95cd, 110cd, or 115cd	15	
500-699669FA	MR-201/C R71-22 RELAY - DPDT, 24VAC/DC, 120/230VAC (damper relay)	16	
RJ-RMS1TKLLP CA...	RMS1TKLP CAT 30 keyed pull station (as per city of Portland specifications)	3	
SSU03505	Speaker/strobe wire guard, 9.5"H X 11.75" W X 5.25" D	10	
ELOCK-FA	Lockout kit with tag	1	

Ordered By: _____

Date: _____

Received By: _____

Date: _____