

36" Double Oven Electric Range




FEATURES

36" Double Oven Electric Range

- 304 Stainless steel
- Chrome knobs and handles
- Stainless steel bezels
- 5 sealed elements
- 2 European convection ovens with elements
- EZ Clean porcelain oven surface
- 2 Heavy duty racks in each oven
- Multi Function electronic programmable oven
- Digital clock and timer
- Full width storage compartment
- Adjustable Stainless steel legs

Accessories:

- EZ Glide rolling rack - optional
- 3" Island trim - optional
- Rounded handles - optional



Specifications		
General Features	Model Number	VEFSEE365DSS
	Size	36"
	Type	Electric
	Clock and Timer	Yes
	Control Knobs	Chrome
	Bezel	SS
	Colors	Stainless Steel
	Storage	Compartment
	3" Island Trim Available	Optional
	Power Requirements	120/240 Volt 60Hz. 50 Amp
Cook Top Features	Elements	5 Sealed
	Left Front	6 7/8" - 1,700W
	Right Front	5 1/2" - 1,200W
	Center – Dual Elements	9" - 2,100W / 700W
	Left Rear	5 1/2" - 1,200W
	Right Rear	6 7/8" - 1,700W
Main Oven Features	Multi Function	Yes
	Oven Capacity (Cu Ft.)	2.4
	Convection Fan	European
	Closed Door Broil	Yes
	Broiler	Yes
	Broiler Power	2,000 W
	Oven Power	2,400 W
	Convection Element	2,450 W
	Racks	2
Broiler Pan	Yes	
Second Oven Features	Multi Function	Yes
	Second Oven Cap. (Cu Ft.)	1.5
	Convection Fan	European
	Closed Door Broil	Yes
	Broiler	Yes
	Broiler Power	1,450 W
	Oven Power	1,500 W
	Convection Heater	2,450 W
	Racks	2
Broiler Pan & Grill Pan	Yes	
Dimensions	Width (in)	35 7/8
	Height (in) w/o Backguard	35 3/8 - 37 1/4
	Height (in) of Backguard	2 or 8
	Depth (in)	24
	Depth (in) with Backguard	25 3/8"
	Weight (lbs.)	310

VEFSEE365NDSS - Stainless Steel

All ranges will ship with 2" Stainless Steel
Extended backguard. An 8" Backguard is available
as a no charge option



Stainless Steel



Requires range cord and plug rated
at 50 amps with ring terminals.

