

- 1, Remove and relocate existing Doorway
- 2, Remove and relocate existing sink to the vicinity of the existing Door
- 3, Existing Doorway opening will be studded, fiberglass insulated, Sheetrock on both sides, and Finished
- 4, Install new door Facing the Dining area, Sheetrock, Finish and install (Marlite) on entire wall where new door is being located.