1 ELECTRICAL DEMOLITION PLAN

SCALE: 1/4"=1'

NOTES:

1. SEE E0.0 FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES.

HATCH INDICATES APPROXIMATE AREA OF TRENCHING REQUIRED TO INSTALL NEW WORK.

DEMOLITION KEYED NOTES:

1. REMOVE FROM EXISTING DRYWALL ALL ELECTRICAL DEVICES INCLUDING BUT NOT LIMITED TO ELECTRICAL RECEPTACLES, VOICE/DATA RECEPTACLES, LIGHT SWITCHES, EMERGENCY LIGHTING, FIRE ALARM DEVICES. SET ASIDE LIFE SAFETY DEVICES FOR RE-USE ON THIS PROJECT.

MorrisSwitzer ENVIRONMENTS FOR HEALTH ARCHITECTURE
e4h
183 Middle Street, Portland
888.781.8441 207.773.8841
BOSTON | DALLAS | NEW YORK | BURLINGTON | PO
e4harchitec

© 2017 Environments For Health

Date: 11/03/17

STATE OF MAINE ROBERT J. CURRAN 11160 LICENSED PROFESSIONAL ENGINEER

SWIFTCURRENT Engineering Services
10 Forest Falls Dr. Unit 4B
Yarmouth, ME 04096
Tel: (207) 847-9280

Greater Portland Health
63 Preble Street Renovation

Portland, Maine

REV	DESCRIPTION	DATE
	ISSUED FOR CONSTRUCTION	7-26-17

SEAL:

PROJECT NUMBER: 201708

DATE: 07/26/2017

ELECTRICAL DEMOLITION PLAN

ED1.0

Unnamed