ABBREVIATIONS

A	AMPERE
AC	ALTERNATING CURRENT
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AIC	AMPERES INTERRUPTING CAPACITY
AL	ALUMINUM
ASYM	ASYMMETRICAL
ATS	AUTOMATIC TRANSFER SWITCH
AUX	AUXILIARY
AWG	AMERICAN WIRE GAUGE
BKR	BREAKER
C	CONDUIT
CAB	CABINET
CB	CIRCUIT BREAKER
CKT	CIRCUIT
CT	CURRENT TRANSFORMER
CU	COPPER
DC	DIRECT CURRENT
DISC	DISCONNECT
EG	EQUIPMENT GROUND
EH	ELECTRICALLY HELD
EM	EMERGENCY
EMT	ELECTRICAL METALLIC TUBING
EO	ELECTRICALLY OPERATED
EPR	ETHYLENE PROPYLENE RUBBER
EQUIP	EQUIPMENT
EX	EXTERIOR
FA	FIRE ALARM
FC	FOOT–CANDLE
FDR	FEEDER
FLUOR	FLUORESCENT
FS	FLOW SWITCH (FA SYSTEM)
FVNR	FULL VOLTAGE NON REVERSING
FVR	FULL VOLTAGE REVERSING
GEN	GENERATOR
GF	GROUND FAULT
GFI	GROUND FAULT CIRCUIT INTERRUPTER
GND	GROUND
H	HAND HOLE
HOA	HAND–OFF–AUTOMATIC
HP	HORSE POWER
HPS	HIGH PRESSURE SODIUM
HV	HIGH VOLTAGE
HZ	HERTZ
IG	ISOLATED GROUND
IMC	INTERMEDIATE METAL CONDUIT
INCAND	INCANDESCENT
JB	JUNCTION BOX
KCMIL	THOUSAND CIRCULAR MILS
KV	KILOVOLT
KVA	KILO VOLT–AMPERE
KW	KILOWATT
KWH	KILOWATT HOUR
LPS	LOW PRESSURE SODIUM
LTG	LIGHTING
LSW	LIGHT SWITCH
LV	LOW VOLTAGE
MCB	MAIN CIRCUIT BREAKER
MCC	MOTOR CONTROL CENTER
MCP	MOTOR CIRCUIT PROTECTION
MH	METAL HALIDE
EMH	ELECTRICAL MANHOLE
MLO	MAIN LUGS ONLY
MO	MECHANICALLY OPERATED
MOD	MOTOR OPERATED DAMPER
MTS	MANUAL TRANSFER SWITCH
MV	MERCURY VAPOR
MVA	MEGAVOLT–AMPERE
NC	NORMALLY CLOSED
NO	NORMALLY OPENED
OH	OVERHEAD
OL	OVER LOAD
OOA	ON–OFF–AUTOMATIC
OSY	OUTSIDE STEM & YOKE VALVE (FA SYSTEM)
P	POLE
PB	PUSH BUTTON
PF	POWER FACTOR
PH	PHASE
PNL	PANEL
PRI	PRIMARY
PT	POTENTIAL TRANSFORMER
PVC	POLYVINYL CHLORIDE
RGSC	RIGID GALVANIZED STEEL CONDUIT
RVSS	REDUCED VOLTAGE SOLID STATE
RSC	RIGID STEEL CONDUIT
RVAT	REDUCED VOLTAGE AUTO TRANSFORMER
S	SIGNAL
SEC	SECONDARY
SHLD	SHIELDED CABLE
SW	SWITCH
SWBD	SWITCHBOARD
SYM	SYMMETRICAL
T	TELEPHONE
TR	TRANSFORMER
TBD	TO BE DETERMINED
TD	TELEDIALER
TDR	TIME DELAY RELAY
TEL	TELEPHONE
TM	TELEMETRY
UG	UNDERGROUND
UT	UTILITY
V	VOLT
VA	VOLT–AMPERE
VFD	VARIABLE FREQUENCY DRIVE
W	WATT
WH	WATT HOUR
WP	WEATHERPROOF
XFMR	TRANSFORMER
XLP	CROSS LINKED POLYETHYLENE
XP	EXPLOSION PROOF

POWER SYMBOLS

	CIRCUIT BREAKER
	GROUND CONNECTION
LP1–2	HOME RUN TO PANEL (CKT. NO. AS SHOWN)
	TRANSFORMER
CT	CURRENT TRANSFORMER
PT	POTENTIAL TRANSFORMER
	20 AMPERE, 120 VOLT DUPLEX RECEPTACLE, +18" AFF
	20 AMPERE, 120 VOLT DOUBLE DUPLEX RECEPTACLE, +18" AFF
	20 AMPERE, 120 VOLT SINGLE RECEPTACLE
	20 AMPERE, 120 VOLT DUPLEX GFCI RECEPTACLE, +18" AFF
H	20 AMPERE, 120 VOLT DUPLEX HOSPITAL GRADE RECEPTACLE, +18" AFF
H	20 AMPERE, 120 VOLT DOUBLE DUPLEX HOSPITAL GRADE RECEPTACLE, +18" AFF
H	20 AMPERE, 120 VOLT DUPLEX HOSPITAL GRADE GFCI RECEPTACLE
H	20 AMPERE, 120 VOLT DOUBLE DUPLEX HOSPITAL GRADE GFCI RECEPTACLE
XX	OTHER POWER RECEPTACLE NEMA DESIGNATION AS NOTED
HP	MOTOR
J	JUNCTION BOX
P	POWER POLE CONNECTION TO MODULAR FURNITURE WHIP
T	TRANSFORMER
CB XX	CIRCUIT BREAKER SIZED AS NOTED
	ELECTRICAL PANEL
BD	BUS DUCT AMPERE RATING AS NOTED
	FLOOR RECEPTACLE CONDUIT INSTALLED IN SLAB
200/3	UNFUSED SAFETY SWITCH, RATING AS NOTED POLES AMPERES
3R F XXAF XXAT	FUSED SAFETY SWITCH, RATING AS NOTED FRAMESIZE FUSE/TRIP NEMA RATING
	MAGNETIC MOTOR STARTER, RATING AS NOTED
M	MANUAL TOGGLE OPERATED MOTOR STARTER
M	SMOKE DAMPER TOGGLE
	ELECTRIC ACTUATED VALVE
M	MOTOR CONTACTOR
	CONTACT NORMALLY OPEN
	CONTACT NORMALLY CLOSED
	SELECTOR SWITCH
	TEMPERATURE SWITCH
R	PILOT LIGHT

FIRE ALARM SYMBOLS

F	PULL STATION
XX H	FIRE ALARM AUDIBLE/VISIBLE NOTIFICATION APPLIANCE (GENERAL EVACUATION)
XX	STROBE UNIT XX= CANDELA
XX 120V	NON–SYSTEM STROBE UNIT
H	MINI HORN UNIT
S	SMOKE DETECTOR
H	FIXED TEMP HEAT DETECTOR (135F OR 200F)
FACP	FIRE ALARM CONTROL PANEL
ANN	ANNUNCIATOR
MB	MASTER BOX
DD	DIGITAL COMMUNICATOR
SD	DUCT SMOKE DETECTOR
T	REMOTE TEST STATION
TS	SPRINKLER TAMPER SWITCH
FS	SPRINKLER FLOW SWITCH
PS	SPRINKLER PRESSURE SWITCH
MM	MONITOR MODULE
CM	CONTROL MODULE
120V S	NON–SYSTEM SMOKE DETECTOR STR = DENOTES INTEGRAL STROBE FOR H/C UNITS
L	RED MASTER BOX LIGHT
KB	KNOX BOX, FBO
EXT	HOOD EXT SYSTEM
DH	DOOR HOLDER
FCPS	SIGNAL POWER EXTENDER

SYSTEMS SYMBOLS

	TELEPHONE SYSTEM WALL JACK
	COMBINATION VOICE/DATA SYSTEM OUTLET
	COMBINATION VOICE/DATA SYSTEM OUTLET IN FLOOR BOX. FURNISH 1" CONDUIT IN SLAB
WAP	CEILING MOUNTED JACK FOR WIRELESS ACCESS POINT.
TV	CATV JACK
DS	SECURITY SYSTEM DOOR SWITCH
EL	ELECTRIC DOOR LOCK SET
KP	SECURITY SYSTEM CARD ACCESS PAD
SP	INTERCOM SYSTEM SPEAKER
INT	INTERCOM MASTER STATION
	CABLE TRAY
	PUSH BUTTON
DB	DOOR BELL
CR	CARD READER
C X	CAMERA 4D = 4 CAMERA DOME

LIGHTING SYMBOLS

X	LIGHT FIXTURE
X	LIGHT FIXTURE W/ EMERGENCY BATTERY BALLAST
X	WALL MOUNTED LIGHT FIXTURE
X	PENDANT MOUNTED LIGHT FIXTURE
X	STRIP/WRAP LIGHT FIXTURE
X	EXTERIOR WALL–PACK
X	ROUND RECESSED CEILING MOUNTED FIXTURE
X	SURFACE MOUNTED FIXTURE
X	WALL MOUNTED LIGHTING FIXTURE
X	WALL SCONCE
X	TRACK LIGHTING FIXTURE (TRACK MOUNTED FIXTURE TYPE MAY VARY)
	EMERGENCY LED EXIT SIGN
	COMBINATION EMERGENCY EXIT SIGN & LIGHTING FIXTURE WITH DUAL LAMPS HEADS BATTERY AND CHARGER
	EMERGENCY LIGHTING FIXTURE WITH DUAL LAMPS HEADS BATTERY AND CHARGER
	REMOTE EMERGENCY LIGHTING LAMP HEAD
Sp a	LIGHT SWITCH DENOTES FIXTURE SWITCHED P = PILOT LIGHT (WHERE NOTED) 3 = 3–WAY (WHERE NOTED) 4 = 4–WAY (WHERE NOTED)
X	ULTRASONIC/INFRARED OCCUPANCY SENSOR C = CEILING MOUNTED W = WALL MOUNTED 48" AFF (TO TOP)
TC	TIME CLOCK
LC	LIGHTING CONTACTOR
PC	PHOTOCELL

GENERAL NOTES

1. ALL WORK SHALL BE IN COMPLIANCE WITH NFPA–70, NATIONAL ELECTRICAL CODE.
2. ALL MOTOR SAFETY SWITCHES, DISCONNECTS AND MOTOR STARTERS ARE FURNISHED BY DIVISION 16000 UNLESS NOTED AS FURNISHED WITH EQUIPMENT (FWE).
3. UNLESS OTHERWISE NOTED, CONVENIENCE RECEPTACLES SHALL BE MOUNTED 18 INCHES AFF AND LIGHTING TOGGLE SWITCHES 48 INCHES AFF.
4. ALL PENETRATIONS THROUGH FLOORS, RATED WALLS AND PARTITIONS SHALL BE SEALED WITH A UL APPROVED FIRE SEALANT METERIAL TO MAINTAIN THE RATING OF THE SEPARATION.
5. LIGHTING TOGGLE SWITCHES SHALL BE COMMERCIAL SPECIFICATION GRADE, 120 VOLT, SIDE WIRED AS MANUFACTURED BY LEVITON, PASS & SEYMOUR, OR APPROVED EQUAL.
6. CONVENIENCE RECEPTACLES SHALL BE COMMERCIAL SPECIFICATION GRADE UNLESS SHOWN OTHERWISE, GROUNDING TYPE, NEMA 5–20R, SIDE WIRED, AS MANUFACTURED BY LEVITON, PASS & SEYMOUR, OR APPROVED EQUAL.
7. HOSPITAL GRADE RECEPTACLES SHALL BE FURNISHED AS SHOWN AS MANUFACTURED BY LEVITON, PASS & SEYMOUR OR APPROVED EQUAL.
8. DEVICE COVERPLATES SHALL BE THERMOPLASTIC NYLON TYPE WITH IVORY FINISH IN ALL FINISHED SPACES. MECHANICAL ROOMS, ELECTRICAL ROOM, AND UTILITY ROOMS SHALL BE FURNISHED WITH BRUSHED STAINLESS STEEL COVERPLATES.
9. UNLESS OTHERWISE NOTED ALL HOMERUNS FOR 15 OR 20A CIRCUITS SHALL BE 2#12AWG & #12 GND. HOMERUNS FED FROM 20A, 1P CIRCUITS IN EXCESS OF 100 FEET (FOR 120V CIRCUITS) OR 200 FEET (FOR 277V CIRCUITS) SHALL BE #10AWG. ALL WIRING SHALL BE COPPER.
10. CONDUIT SYSTEMS: EXPOSED INTERIOR CONDUITS SHALL BE EMT, 3/4" MINIMUM. PROPERLY SUPPORTED MC CABLE ASSEMBLIES MAY BE USED ABOVE CEILINGS AND IN WALLS. HOSPITAL GRADE WIRING FOR NEW EXAM ROOMS SHALL BE IN HCF TYPE MC CABLE ASSEMBLIES AS MANUFACTURED BY SOUTHWIRE OR APPROVED EQUAL, AND INSTALLED IN ACCORDANCE WITH NATIONAL ELECTRICAL CODE 517.13 (A) AND 517.13 (B). FLEXIBLE LIQUIDTIGHT CONDUIT WHIPS SHALL BE USED FOR CONNECTION TO VIBRATING EQUIPMENT.

MorrisSwitzer ENVIRONMENTS FOR HEALTH ARCHITECTURE
e4h
183 Middle Street, Portland
888.781.8441 207.773.8841
BOSTON | DALLAS | NEW YORK | BURLINGTON | PO
e4harchitec

© 2017 Environments For Health

Reviewed for Code Compliance
Inspection Services
Portland, Maine
Date: 11/03/17

STATE OF MAINE
ROBERT J. CURRAN
11160
LICENSED
PROFESSIONAL ENGINEER

SWIFTCURRENT
Engineering Services
10 Forest Falls Dr. Unit 4B
Yarmouth, ME 04096
Tel: (207) 847–9280

Greater Portland Health
63 Preble Street Renovation
Portland, Maine

REV	DESCRIPTION	DATE
	ISSUED FOR CONSTRUCTION	7-26-17

SEAL:

PROJECT NUMBER: 201708

DATE: 07/26/2017

ELECTRICAL GENERAL NOTES & LEGEND

E0.0
Unnamed