

All framing and joists are PT 2x8.

Free standing structure to lay on pavement.

Joist Hangers used at all connection points.

4x4 posts at every corner or 8' on center. Posts will be used for guardrail as seen in diagram 3.

Although everything is 2x8, the grade of the property goes very slightly uphill towards the deck exit. For that reason, we will take a little bit off of the 2x8's near that end to accommodate a 7" step at that exit onto the pavement.

MATERIALS

PREBLE ST.

16" on center

Existing Building.

EXIT

EXIT

16" on center

ALDER ST.

KENNEBEC ST.

