

TABLE 502.2(1)
BUILDING ENVELOPE REQUIREMENTS - OPAQUE ASSEMBLIES

CLIMATE ZONE	1		2		3		4 EXCEPT MARINE		5 AND MARINE 4		6		7		8	
	All other	Group R	All other	Group R	All other	Group R	All other	Group R	All other	Group R	All other	Group R	All other	Group R	All other	Group R
Roofs																
Insulation entirely above deck	R-15ci	R-20ci	R-20ci	R-20ci	R-20ci	R-20ci	R-20ci	R-20ci	R-20ci	R-20ci	R-20ci	R-20ci	R-25ci	R-25ci	R-25ci	R-25ci
Metal buildings (with R-5 thermal blocks ^{a, b})	R-19	R-19	R-13 + R-13	R-13 + R-13	R-13 + R-13	R-19	R-13 + R-13	R-19	R-13 + R-13	R-19	R-13 + R-19	R-19	R-13 + R-19	R-19 + R-10	R-11 + R-19	R-19 + R-10
Attic and other	R-30	R-38	R-38	R-38	R-38	R-38	R-38	R-38	R-38	R-38	R-38	R-38	R-38	R-38	R-49	R-49
Walls, Above Grade																
Mass	NR	R-5.7ci	R-5.7ci	R-7.6ci	R-7.6ci	R-9.5ci	R-9.5ci ^c	R-11.4ci	R-11.4ci	R-13.3ci	R-13.3ci	R-15.2ci	R-15.2ci	R-15.2ci	R-25ci	R-25ci
Metal building ^b	R-16	R-16	R-16	R-16	R-19	R-19	R-19	R-19	R-13 + R-5.6ci	R-13 + R-5.6ci	R-13 + R-5.6ci	R-13 + R-5.6ci	R-19 + R-5.6ci	R-19 + R-5.6ci	R-19 + R-5.6ci	R-19 + R-5.6ci
Metal framed	R-13	R-13	R-13	R-13 + 7.5ci	R-13 + R-3.8ci	R-13 + R-7.5ci	R-13 + 7.5	R-13 + R-7.5ci	R-13 + R-7.5ci	R-13 + R-7.5ci	R-13 + R-7.5ci	R-13 + R-7.5ci	R-13 + R-7.5ci	R-13 + R-15.6ci	R-13 + R-7.5ci	R-13 + R-18.8ci
Wood framed and other	R-13	R-13	R-13	R-13	R-13	R-13	R-13	R-13 + R-3.8ci	R-13 + R-3.8ci	R-13 + 3.8	R-13 + 7.5	R-13 + R-7.5	R-13 + R-7.5ci	R-13 + 7.5ci	R-13 + R-15.6ci	R-13 + 15.6ci
Walls, Below Grade																
Below grade wall ^d	NR	NR	NR	NR	NR	NR	NR	R-7.5ci	R-7.5ci	R-7.5ci	NR R-7.5ci	R-7.5ci	R-7.5ci	R-10ci	R-7.5ci	R-12.5ci
Floors																
Mass	NR	NR	R-6.3ci	R-8.3ci	R-6.3ci	R-8.3ci	R-10ci	R-10.4ci	R-10ci	R-12.5ci	R-12.5ci	R-14.6ci	R-15ci	R-16.7ci	R-15ci	R-16.7ci
Joist/framing Steel/(wood)	NR	NR	R-19	R-30	R-19	R-30	R-30	R-30	R-30	R-30	R-30	R-30 ^e	R-30	R-30 ^e	R-30 ^e	R-30 ^e
Slab-on-Grade Floors																
Unheated slabs	NR	NR	NR	NR	NR	NR	NR	R-10 for 24 in. below	NR	R-10 for 24 in. below	R-10 for 24 in. below	R-15 for 24 in. below	R-15 for 24 in. below	R-15 for 24 in. below	R-15 for 24 in. below	R-20 for 24 in. below
Heated slabs	R-7.5 for 12 in. below	R-7.5 for 12 in. below	R-7.5 for 12 in. below	R-7.5 for 12 in. below	R-10 for 24 in. below	R-10 for 24 in. below	R-15 for 24 in. below	R-15 for 24 in. below	R-15 for 24 in. below	R-15 for 24 in. below	R-15 for 24 in. below	R-20 for 48 in. below	R-20 for 24 in. below	R-20 for 48 in. below	R-20 for 48 in. below	R-20 for 48 in. below
Opaque doors																
Swinging	U - 0.70	U - 0.70	U - 0.70	U - 0.70	U - 0.70	U - 0.70	U - 0.70	U - 0.70	U - 0.70	U - 0.70	U - 0.70	U - 0.50	U - 0.50	U - 0.50	U - 0.50	U - 0.50
Roll-up or sliding	U - 1.45	U - 1.45	U - 1.45	U - 1.45	U - 1.45	U - 1.45	U - 0.50	U - 0.50	U - 0.50	U - 0.50	U - 0.50	U - 0.50	U - 0.50	U - 0.50	U - 0.50	U - 0.50

For SI: 1 inch = 25.4 mm.

ci = Continuous insulation. NR = No requirement.

a. When using R-value compliance method, a thermal spacer block is required, otherwise use the U-factor compliance method. [see Tables 502.1.2 and 502.2(2)].

b. Assembly descriptions can be found in Table 502.2(2).

c. R-5.7 ci is allowed to be substituted with concrete block walls complying with ASTM C 90, ungrouted or partially grouted at 32 inches or less on center vertically and 48 inches or less on center horizontally, with ungrouted cores filled with material having a maximum thermal conductivity of 0.44 Btu-in./h-ft² F.

d. When heated slabs are placed below grade, below-grade walls must meet the exterior insulation requirements for perimeter insulation according to the heated slab-on-grade construction.

e. Steel floor joist systems shall to be R-38.