1 WAREHOUSE NORTH ELEVATION
1/8" = 1'-0"

2 WAREHOUSE EAST ELEVATION
1/8" = 1'-0"

- KEY PLAN Copy 2
1" = 40'-0"

3 WAREHOUSE SOUTH ELEVATION
1/8" = 1'-0"

4 WAREHOUSE WEST ELEVATION
1/8" = 1'-0"

LABEL 2 HR

(1 HR REQ'D)

2 HR BEARING FIRE BARRIER
DESIGN NUMBER - UL - U905
STC SOUND - N/A

1. **CONCRETE BLOCKS -** CLASSIFICATION D-2 (2HR) 8" NOM. THICKNESS. BLOCKS EXTEND 30" BEYOND TOP OF ROOF.
2. **MORTAR -** BLOCKS LAID IN A FULL BED OF MORTAR, NOM. 3/8 IN THICK, OF NOT LESS THAN 2 1/4 AND NOT MORE THAN 3 1/2 PARTS CLEAN SHARP SAND TO 1 PART PORTLAND CEMENT (PROPORTIONED BY VOLUME) AND NOT MORE THAN 50 PERCENT HYDRATED LIME (BY CEMENT VOLUME). VERTICAL JOINTS STAGGERED.
3. **REINFORCING -** SEE STRUCTURAL
4. UNDERSIDE OF STRUCTURE
5. TOP OF STRUCTURE

5 WEST EXTERIOR CMU WALL
1 1/2" = 1'-0"

Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 07/30/15

Prepared For:

Consultant:

Architect:
ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 ARCHETYPE@ARCHETYPEPA.COM

Project:
Century Tire

Revisions:
1 Date 1 Revision 1

Scale: As indicated

Date: 03-16-2015

WAREHOUSE ELEVATIONS

A2.03