PACKAGED ROOFTOP UNIT PERFORMANCE SCHEDULE

* - (NET) AT 95°F AMBIENT
** - SEER

TAG	NOMINAL COOLING (TONS)	TOTAL COOLING (MBH)	SENSIBLE COOLING (MBH)	EDB/ EWB (°F)	TOTAL AIRFLOW (CFM)	E.S.P. (IN.WG)	SUPPLY FAN RPM	MINIMUM O.A. (CFM)	EER (BTUH/ WATT)	HEAT FUEL	HEATING INPUT (MBH)	WEIGHT W/ CURB (LBS)	TYPE OF REFRIG-ERANT	ELECTRICAL REQUIREMENTS				BASIS OF DESIGN - TRANE	
														FLA	MCA	MOCP	V/PH/HZ	SERVICE	MODEL
HVAC-W	7.5	83.0	54.4	80.1/67.9	2400	0.75	994	925	11.2	GAS	200.0	1350	R-410a	-	49.6	60.0	208/3/60	WAREHOUSE	YSC090

PROVIDE UNITS WITH ENTHALPY ECONOMIZER WITH BAROMETRIC RELIEF, MODULATING GAS HEAT WITH STAINLESS STEEL HEAT EXCHANGER.

CONDENSATE TRAP DETAIL

NTS

NOTE - CAP UNUSED DRAIN PAN CONNECTIONS.

RECT. ELBOW W/TURNING VANES

NTS NOTE INSTALL VANE EDGES TO PROJECT TANGENTS PARALLEL TO DUCT SIDES.

OFFSET TYPE 1 (ANGLED)

NTS

CONCENTRIC TRANSITION

NTS

RADIUS ELBOW

NTS

RECTANGULAR TAP 45 DEGREE ENTRY

NTS

OFFSET TYPE 2 (MITERED)

NTS

ECCENTRIC TRANSITION

NTS

LOW PRESSURE DUCT CONSTRUCTION DETAILS - TYPICAL

NTS

UPFEED GAS PIPING CONNECTION DETAIL

NTS

NOTE APPLIANCES WITH REGULATORS LOCATE PIPING SHOWN HEREIN UPSTREAM OF THE APPLIANCE REGULATOR. PROVIDE A TEST PLUG DOWNSTREAM OF THE APPLIANCE REGULATOR.

DOWNFEED GAS PIPING CONNECTION DETAIL

NTS

NOTE APPLIANCES WITH REGULATORS LOCATE PIPING SHOWN HEREIN UPSTREAM OF THE APPLIANCE REGULATOR. PROVIDE A TEST PLUG DOWNSTREAM OF THE APPLIANCE REGULATOR.

WATER ENTRANCE DETAIL

MECHANICAL AND PLUMBING SYMBOLS AND ABBREVIATIONS LEGEND

NOTE - USE SYMBOLS AND ABBREVIATIONS AS APPLICABLE FOR THIS MECHANICAL DRAWING SET.
SOME SYMBOLS AND ABBREVIATIONS IN THIS LEGEND MAY NOT APPLY.

SYMBOL	DESCRIPTION
G	GAS PIPING (G)
	PIPE CAP
	DIRECTION OF FLUID FLOW
	ELBOW UP
	ELBOW DOWN
	PIPE TEE UP
	PIPE TEE DOWN
	PIPE REDUCER
	PIPE WITH GUIDE
	PIPE WITH ANCHOR
	BUTTERFLY VALVE
	OS & Y GATE VALVE
	CHECK VALVE
	BALANCING VALVE (ADJUSTABLE)
	AUTOMATIC FLOW CONTROL VALVE
	RELIEF VALVE (RV)
	BALL VALVE
	BALL VALVE
	3/4" BALL VALVE WITH 3/4" HOSE END
	GATE VALVE
	PRESSURE REDUCING VALVE
	FUSIBLE VALVE
	STRAINER W/BLOWDOWN BALL VALVE
	UNION
	PIPE FLANGE
FC	FLEXIBLE PIPE CONNECTION (FC)
	PITCH DOWN
	PETCOCK

SYMBOL	DESCRIPTION
PG	PRESSURE GAGE WITH GAGE COCK
T	THERMOMETER IN WELL
F	WATER FLOW SWITCH
P	PRESSURE SWITCH OR SENSOR
T	EMURSION TEMPERATURE SENSOR
RH	DUCT MOUNTED SMOKE DETECTOR
R	ROOM TEMPERATURE SENSOR
T S	THERMOSTAT OR SENSOR ON WALL
T G	TSTAT OR SENSOR W/ TAMPERPROOF GUARD
V	MANUAL AIR VENT
3	NOTE TAG (NUMBER)
A 125	AIR DEVICE TAG (LETTER) WITH CFM
101	ROOM NUMBER
	TURNING VANES
	DUCT W/MANUAL DAMPER
	DUCT W/FLEXIBLE CONNECTION (FC)
	LAGGED DUCT
	DUCT W/ACOUSTIC LINING
	DUCT W/SQUARE-TO-ROUND TRANSITION
	FLEXIBLE DUCT
MOD	MOTOR OPERATED DAMPER
	AIRFLOW OUT
	AIRFLOW IN
ϕ	DIAMETER OR FLAT OVAL
	FIRE DAMPER
	ROUND OR FLAT OVAL DUCT DOWN
	ROUND OR FLAT OVAL DUCT UP
CD	SUPPLY DIFFUSER
	RETURN GRILLE
	STEAM TRAP
	WATER HAMMER ARRESTOR

ABBREVIATION	DESCRIPTION
AAV	AUTOMATIC AIR VENT
AD	ACCESS DOOR
AFF	ABOVE FINISHED FLOOR
AHU-*	AIR HANDLING UNIT TAG
AMS	AIRFLOW MONITORING STATION
AMPS	AMPERES
AP	ACCESS PANEL
APD	AIR PRESSURE DROP
AR	ACID RESISTANT PIPING
AS-*	AIR SEPARATOR TAG
ATC	AUTOMATIC TEMPERATURE CONTROL
BFP-*	BACKFLOW PREVENTER TAG
BHP	BRAKE HORSEPOWER
BTUH	BRITISH THERMAL UNITS PER HOUR
CC-*	COOLING COIL TAG
CFM	CUBIC FEET PER MINUTE
CO	CLEANOUT
CP-*	CIRCULATING PUMP TAG
Cv	VALVE COEFFICIENT
CW	COLD WATER
DB	DRY BULB
dB RE	DECIBELS RELATIVE TO
DC	DOUBLE CHECK
DCA	DOUBLE CHECK ATMOSPHERIC
DEG F	DEGREES FAHRENHEIT
DIA	DIAMETER
DIW	DOWN IN WALL
DN	DOWN
EA	EXHAUST AIR
EAT	ENTERING AIR TEMPERATURE

ABBREVIATION	DESCRIPTION
EDB	ENTERING DRY BULB
EDC-*	ELECTRIC DUCT COIL TAG
EER	ENERGY EFFICIENCY RATIO
EF-*	EXHAUST FAN TAG
EFF	EFFICIENCY
ESP	EXTERNAL STATIC PRESSURE
ET-*	EXPANSION TANK TAG
EWB	ENTERING WET BULB
EWH-*	ELECTRIC WATER HEATER TAG
EWT	ENTERING WATER TEMPERATURE
EXG	EXISTING
EXH	EXHAUST
FC	FLEXIBLE CONNECTION
FCO	FLOOR CLEANOUT
FD	FIRE DAMPER
FD-*	FLOOR DRAIN TAG
FLA	FULL LOAD AMPS
FPHB	FROST PROOF HOSE BIBB
FPM	FEET PER MINUTE
FSD	COMBINATION FIRE & SMOKE DAMPER
FT	FEET
GA.	GAGE
GAL	GALLONS
GPH	GALLONS PER HOUR
GPM	GALLONS PER MINUTE
HC-*	HEATING COIL TAG
HP	HORSEPOWER
HRV-*	HEAT RECOVERY VENTILATOR TAG
HW	HOT WATER
HWS/R	HOT WATER SUPPLY AND RETURN

ABBREVIATION	DESCRIPTION
I=B=R	INSTITUTE OF BOILER AND RADIATOR MANUFACTURERS
IN.	INCHES
L-*	LOUVER TAG
LAT	LEAVING AIR TEMPERATURE
LB	POUNDS
LWS/R	LOOP WATER SUPPLY/RETURN
LRA	LOCKED ROTOR AMPS
LWCO	LOW WATER CUTOUT
LWT	LEAVING WATER TEMPERATURE
MAX	MAXIMUM
MBH	THOUSANDS OF BTU PER HOUR
MCA	MINIMUM CIRCUIT AMPACITY
MIN	MINIMUM
NC	NOISE CRITERION
NIC	NOT IN CONTRACT
NTS	NOT TO SCALE
OA	OUTSIDE AIR
OBD	OPPOSED BLADE DAMPER
O.D.	OUTSIDE DIAMETER
OED	OPEN ENDED DUCT
OPD	OVERCURRENT PROTECTIVE DEVICE
P-*	PLUMBING FIXTURE TAG
PENET'N	PENETRATION
PF-*	PADDLE FAN TAG
PSIA	POUNDS PER SQUARE INCH ABSOLUTE
PSIG	POUNDS PER SQUARE INCH GAGE
PVC	POLYVINYL CHLORIDE (PIPE)
RA	RETURN AIR
RD	ROOF DRAIN
RDE	RECOMMENDED DUAL ELEMENT FUSE AMPS
RHW	RECIRCULATED HOT WATER

ABBREVIATION	DESCRIPTION
RLA	RUNNING LOAD AMPS
RPM	REVOLUTIONS PER MINUTE
RPS	REVOLUTIONS PER SECOND
RPZ	REDUCED PRESSURE ZONE
RTU	ROOM TEMPERATURE SENSOR
RV	RELIEF VALVE
RWL	RAINWATER LEADER
SA	SUPPLY AIR
SAN	SANITARY (DRAIN & WASTE)
SD	SMOKE DAMPER
SEER	SEASONAL ENERGY EFFICIENCY RATIO
SF	SUPPLY FAN
SP	STATIC PRESSURE
SQFT	SQUARE FEET
ΔT	TEMPERATURE DIFFERENTIAL
TEMP.	TEMPERATURE
TCP	TEMPERATURE CONTROL PANEL
TMV-*	THERMOSTATIC MIXING VALVE TAG
TSP	TOTAL STATIC PRESSURE
TYP	TYPICAL
UH-*	UNIT HEATER TAG
VB	VACUUM BREAKER
VFD	VARIABLE FREQUENCY INVERTER DRIVE
VTR	VENT THRU ROOF
V/PH/HZ	VOLTS/PHASES/HERTZ
WB	WET BULB
WCO	WALL CLEANOUT
WG	WATER GAGE
WPD	WATER PRESSURE DROP
WSA	WIRE SIZING AMPS
WTD	WATER TEMPERATURE DROP
W/	WITH

STATE OF MAINE — STEPHEN C. LOVEJOY — LICENSED PROFESSIONAL ENGINEER

Prepared For:

Consulting Engineer:
BENNETT ENGINEERING
MECHANICAL • ELECTRICAL
(207) 797-5945

Architect:
ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 Fax (207) 772-4056

Project:
CENTURY TIRE
PORTLAND, MAINE

Revisions:
No. Date:

Date: 03/16/2015
Scale: As Noted

MECHANICAL SCHEDULES, DETAILS AND LEGEND

Date: 03/30/15
Recommended for Approval
Inspection Division
Approved with Conditions: