

SECTION 07900

JOINT SEALERS

1 PART 1 GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of contract including General and Supplementary Conditions and Division 1 specification sections apply to Work of this section.

1.2 SECTION INCLUDES

- A. Sealants and joint backing.

1.3 SUBMITTALS

- A. Product Data: Provide data indicating sealant chemical characteristics, performance criteria, substrate preparation, limitations, color availability .

1.4 ENVIRONMENTAL REQUIREMENTS

- A. Maintain temperature and humidity recommended by the sealant manufacturer during and after installation.

2 PART 2 PRODUCTS

2.1 SEALANTS

- A. Type A - General Purpose Exterior Sealant: Polyurethane ; ASTM C920, Grade NS, Class 25, Uses M, G, and A; single or multi- component.

- 1. Color as selected.
- 2. Applications: Use for:

- a. Joints between concrete and other materials.
- b. Joints between metal frames and other materials.
- c. Joints between siding and other materials.
- d. Other exterior joints for which no other sealant is indicated.

- B. Type B - Exterior Metal Lap Joint Sealant: Butyl or polyisobutylene, nondrying, non-skinning, non-curing.

- 1. Applications: Use for:

- a. Concealed sealant bead in sheet metal work.
- b. Bedding for door thresholds.

- C. Type C - General Purpose Interior Sealant: Acrylic emulsion latex; ASTM C834, single component, paintable.

1. Colors as selected.
 2. Applications: Use for:
 - a. Interior wall and ceiling control joints.
 - b. Joints between door and window frames and wall surfaces.
 - c. Other interior joints for which no other type of sealant is indicated.
- D. Type D - Bathtub/Tile Sealant: White silicone; ASTM C920, Uses M and A; single component, mildew resistant.
1. Applications: Use for:
 - a. Joints between plumbing fixtures and floor and wall surfaces.
 - b. Joints between kitchen and bath countertops and wall surfaces.
- E. Type E - Acoustical Sealant: Butyl or acrylic sealant; ASTM C920, Grade NS, Class 12-1/2, Uses M and A; single component, solvent release curing, non-skinning.
1. Applications: Use for concealed locations only:
 - a. Sealant bead between top stud plate and structure and between bottom stud plate and floor.
- F. Type F - Interior Floor Joint Sealant: Polyurethane, self-leveling; ASTM C920, Grade P, Class 25, Uses T, M and A; single or multi- component.
1. Colors as selected.
 2. Applications: Use for:
 - a. Expansion joints in floors.
- G. Type G - Concrete Paving Joint Sealant: Polyurethane, self-leveling; ASTM C920, Class 25, Uses T, M and A; single or multi- component.
1. Color as selected.
 2. Applications: Use for:
 - a. Joints in sidewalks and vehicular paving.

2.2 ACCESSORIES

- A. Primer: Non-staining type, recommended by sealant manufacturer to suit application.
- B. Joint Cleaner: Non-corrosive and non-staining type, recommended by sealant manufacturer; compatible with joint forming materials.
- C. Joint Backing: Round foam rod compatible with sealant D1667, closed cell PVC oversized 30 to 50 percent larger than joint width.
- D. Bond Breaker: Pressure sensitive tape recommended by sealant manufacturer to suit application.

3 PART 3 EXECUTION

3.1 EXAMINATION AND PREPARATION

- A. Verify that substrate surfaces and joint openings are ready to receive work.
- B. Verify that joint backing and release tapes are compatible with sealant.
- C. Remove loose materials and foreign matter which might impair adhesion of sealant.
- D. Clean and prime joints in accordance with manufacturer's instructions.
- E. Perform preparation in accordance with manufacturer's instructions and ASTM C1193.

3.2 INSTALLATION

- A. Perform work in accordance with sealant manufacturer's requirements for preparation of surfaces and material installation instructions.
- B. Perform installation in accordance with ASTM C1193.
- C. Perform acoustical sealant application work in accordance with ASTM C919.
- D. Measure joint dimensions and size joint backers to achieve width-to-depth ratio, neck dimension, and surface bond area as recommended by manufacturer, except where specific dimensions are indicated.
- E. Install bond breaker where joint backing is not used.
- F. Install sealant free of air pockets, foreign embedded matter, ridges, and sags.
- G. Apply sealant within recommended application temperature ranges. Consult manufacturer when sealant cannot be applied within these temperature ranges.
- H. Tool joints concave.

...END OF SECTION