
SECTION 10005**MISCELLANEOUS SPECIALTIES****1 PART 1 GENERAL****1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of Contract including General and Supplementary Conditions and Division 1 specification sections apply to Work of this section.

1.2 SECTION INCLUDES

- A. Fire extinguishers.
- B. Fire extinguisher cabinets.
- C. Knox Boxes

1.3 SUBMITTALS

- A. Product Data: Provide data on Product, and accessories.
- B. Operating and Maintenance Instructions: Include relevant instructions. Include maintenance information.

1.4 QUALITY ASSURANCE

- A. Fire Extinguishers: Conform to NFPA 10.

2 PART 2 PRODUCTS**2.1 FIRE EXTINGUISHERS**

- A. Manufacturers:
 - 1. Allenco.
 - 2. Amerex.
 - 3. Ansul Fire Protection
 - 4. Bobrick Washroom Equipment.
 - 5. JL Industries.
 - 6. Larsen's Manufacturing Co.
 - 7. Potter-Roemer/Div. Smith Industries Inc.
 - 8. Walter Kidde/Div. Kidde Inc.
- B. Multi-Purpose Dry Chemical Type: Enameled steel tank, with pressure gage, 2A:10BC rating.
- C. Cabinets: Semi-recessed type, steel cabinet, full glass door with baked enamel finish.

1. Provide fire rated cabinet when installing in fire rated wall partition equal to rating of wall partition.

D. Brackets: Manufacturer's standard surface mounted bracket for extinguishers not indicated to have a cabinet.

2.2 KNOX BOXES

A. Manufacturers: Knox Co. #3200 Series Rapid Entry System with Recessed Mounting Kit.

3 PART 3 EXECUTION

3.1 EXAMINATION AND PREPARATION

A. Verify that surfaces and internal wall blocking are ready to receive work and opening dimensions are as instructed by the manufacturer.

3.2 INSTALLATION - FIRE EXTINGUISHERS

A. Install extinguishers in accordance with manufacturer's instructions.

B. Mount units to conform to ADA requirements, with top less than 48" above floor.

C. Install units level and plumb in wall openings.

3.3 INSTALLATION – KNOX BOXES

A. Install knox boxes in accordance with manufacturer's instructions.

B. Install units level and plumb.

C. Install knox box at location indicated on drawings and as confirmed by local fire official.

...END OF SECTION