## **GENERAL NOTES** 1. TILE INSTALLER SHALL COORDINATE WITH GENERAL CONTRACTOR AND PROVIDE LAYOUT OF ALL WALL TILE PRIOR TO INSTALLATION. GENERAL CONTRACTOR SHALL PREPARE WALLS AS TO NOT HAVE ANY CUT TILES IN EITHER DIRECTION (HORIZONTALLY OR VERTICALLY) ON ANY WALLS. LAYOUT SHALL BE APPROVED BY CHIPOTLE CM PRIOR TO INSTALLATION. CONTRACTOR SHALL CONTACT ARCHITECT OF ANY DISCREPANCIES IN DIMENSIONS FOR DIRECTION PRIOR TO INSTALLATION. FAILURE TO ADHERE TO THESE REQUIREMENTS RESULTING IN ANY REMEDIATION REQUIRED TO MEET DESIGN INTENT WILL BE 2. IF REQUIRED TO CUT TILES, CONTRACTOR TO MEASURE OVERALL WALL WIDTH AND DETERMINE WHICH SOLUTION WILL ALLOW FOR THE GREATER THAN 50% TILE WIDTH AT WALL TERMINATIONS. 3. UNLESS OTHERWISE NOTED, ALL WALL TILES SHOULD BE CENTERED ON THE WIDTH OF THE WALL PER DETAIL 1A OR 1B. 4. THERE SHOULD NEVER BE ANY CUT TILES VERTICALLY BETWEEN THE BASE AND THE CEILING. REFER TO A120 AND A140. SUBSTRATE VARIES REFER TO A115 FINISH VARIES REFER TO A120 CEMENT BOARD METAL STUDS CERAMIC TILE COUNTERSUNK **CERAMIC TILE** S.S. SCREWS WALL SUBSTRATE, RE:A115 **EQUALLY SPACED** CERAMIC TILE DEVICE WALL SUBSTRATE, RE: A115 3/4" PLYWOOD, WALL SUBSTRATE, RE: A115 FULL HEIGHT METAL STUDS FULL HEIGHT METAL STUDS PAINT ENDS WHITE RAKE OUT GROUT AND 1/8" REVEAL WITH SCHLUTER-QUADEC Q100EB PROVIDE CAULK PER BACKER ROD AND STAINLESS STEEL CORNER SPECIFICATIONS -CAULKING, EACH SIDE FULL HEIGHT METAL STUDS GUARD, 27/64" X 27/64" (ENTIRE HEIGHT OF SCHLUTER-QUADEC Q100EB CERAMIC TILE) STAINLESS STEEL CORNER GUARD, 27/64" X 27/64" (ENTIRE HEIGHT OF 1/4" THICK ALUMINUM SEALANT PLATE TO UNDERSIDE CERAMIC TILE) OF SOFFIT ABOVE FRP EDGE TRIM MOULDING JUNCTION BOXES FOR ALL OUTLETS, FRP PANEL F.A. DEVICES, HAND DRYERS, ETC. TO BE CUT IN TILE AS INDICATED TILE TO TILE INSIDE CORNER TILE DETAIL @ DEVICE LOCATIONS TILE TO TILE OUTSIDE CORNER **ALUMINUM PLATE @ JAMB/HEAD/SILL** TILE TO FRP OUTSIDE CORNER GYP BOARD, PAINT WHITE REFER TO MECH. DRAWINGS FOR NEW DUCT WORK METAL STUDS, REFER TO A115 GYP BOARD, PAINT WHITE B.O. LIGHT COVE VARIES AFF FLUORESCENT FIXTURE, REFER TO WIRE HANGERS HUNG AT 48" O.C. MIN. FASTEN TO WIRE HANGERS HUNG AT STRUCTURE ABOVE 48" O.C. MIN. FASTEN TO B.O. GYP. BD. CEILING VARIES AFF STRUCTURE ABOVE 1' - 0" SUSPENDED CEILING ACOUSTICAL CEILING JOINTS TO ALIGN WITH BOTTOM OF GYP. BD. CEILING 2 1/8" X 8 1/2" CERAMIC 5/8" GYP BOARD CEILING ACOUSTICAL TILE CEILING TILE, HORIZONTAL STACK BOND (TYP.) CHANNEL MOLDING HEMMED ANGLE MOLDING CEMENT BOARD PROVIDE 1/8" SPACER AT TOP PROVIDE 1/8" SPACER AT TOP FOR CAULK JOINT AT CEILING FOR CAULK JOINT AT CEILING METAL STUDS, REFER TO A115 CERAMIC TILE FINISH, FULL TILE CERAMIC TILE FINISH, FULL TILE SOUND BATT INSULATION, REFER TO A115 REFER TO A115 FOR REFER TO A115 FOR WALL CONSTRUCTION WALL CONSTRUCTION TILE DETAIL @ GYP BD CEILING TILE DETAIL @ SUSPENDED CEILING RESTROOM/KITCHEN COVE DETAIL **NOT USED** NOTE: REFER TO SHEET A230 FOR FURTHER INFORMATION \*NOTE: ±9'-0" BOTTOM OF GYP. BD. CEILING IS TO BE TAKEN FROM THE VARIES, SEE PLAN HIGHEST POINT OF CONCRETE SLAB. B.O. GYP. BD. CEILING ± 9'-0"" AFF \ A126 T.O. COVE ± 8'-7 1/4" AFF VARIES. SEE PLAN GYP. BD. CEILING VARIES. SEE PLAN PROVIDE 1/8" SPACER FOR CAULK JOINT AT CEILING B.O. CEILING ± 7'-7 1/4" AFF PROVIDE 1/8" SPACER FOR CAULK JOINT AT CEILING **EDGE TILES TO BE** EDGE TILES TO BE **GREATER THAN GREATER THAN** 2 1/8" X 8 1/2" CERAMIC PROVIDE 1/8"SPACER 50% OF THE WALL TILE HORIZONTAL 50% OF THE FOR CAULK JOINT WIDTH STACK BOND (TYP.) WIDTH - 2 1/8" X 8 1/2" 1/4" THICK MILL FINISH 2 1/8" X 8 1/2" EDGE TILES TO BE ALUMINUM JAMB PLATE. CERAMIC WALL CERAMIC WALL **GREATER THAN 50% OF RUN FROM TOP OF** TILE. HORIZONTAL TILE. HORIZONTAL THE TILE WIDTH; SEE POLYCRETE BASE (JOLLY) STACK BOND (TYP.) STACK BOND (TYP.) **DETAILS 1A & 1B/A126** TO UNDERSIDE OF CEILING REFER TO 9/A126 2 1/8" X 8 1/2" HORIZONTAL STACK SCHLUTER ' JOLLY' EDGE CERAMIC TILE -PROTECTION STRIP, SEE DETAIL 9A/A125 SCHLUTER 'JOLLY' EDGE PROTECTION STRIP, SEE ± 5" POLY-CRETE BASE DETAIL 9A/A125 -BASE AS BASE AS SCHEDULED SCHEDULED ± 4" POLY-CRETE BASE ← WALL WIDTH € WALL WIDTH € WALL WIDTH **TILE CENTERED LAYOUT** JOINT CENTERED LAYOUT **NOT USED RESTROOM SIDE WALL TILE LAYOUT** KITCHEN WALL ENDCAP TILE LAYOUT

Co

r e

9 (

architecture + planning

855 GRANDVIEW AVENUE SUITE 295

COLUMBUS, OHIO 43215
PHONE: 614.487.8770
FAX: 614.487.8777



COPYRIGHT 2015
THIS DRAWING IS AN INSTRUMENT OF SERVICE AND AS SUCH
REMAINS THE PROPERTY OF CHIPOTLE MEXICAN GRILL, INC..
PERMISSION FOR USE OF THIS DOCUMENT IS LIMITED AND
CAN BE EXTENDED ONLY BY WRITTEN AGREEMENT WITH
CHIPOTLE MEXICAN GRILL, INC..



CHIPOTLE MEXICAN GRILL, INC.
1401 WYNKOOP STREET, SUITE 500
DENVER, COLORADO 80202
TELEPHONE: (303) 595-4000
FAX: (303) 595-4014
INTERNET: WWW.CHIPOTLE.COM

STORE NO.: 2603
PORTLAND MARGINAL WAY
195 KENNEBEC ST
PORTLAND, ME 04101

09/15/15	PERMIT/LANDLORD REVIEW
Revisions:	

Drawn: Checked:
TC, BP, DP KH,TC

Project No.
CMG507

tents:

Tile Details

A126

Date of Last Print: 09/15/15