



December 28, 2009

Ms. Shukria Wiar, Planner
Planning and Urban Development Department
City of Portland, Maine
389 Congress Street
Fourth Floor
Portland, ME 04101

**Re: Bowl Portland
58 Alder Street**

Dear Shukria,

Per comments from David Margolis-Pineo, Portland Public Services, the plans in the vault of Public Services indicate that the floor drains of 58 Alder Street are connected to the stormwater system in Alder Street. A dye test is requested to confirm this: the floor drains and roof drains should be redirected to the stormwater system.

According to drawing R.4, Outline Specifications, division 15.A.c the "General Contractor is responsible for separating the storm drains from the sewer line, currently the lines are connected to the sewer line." A note will be added to include the floor drains.

As you can see, we have provisions in the contract to perform this work. We request that once a contractor has been chosen for this project with a team of subcontractors who will be performing the work, a dye test be performed to confirm existing conditions. The dye test results will be forwarded to David Margolis-Pineo at Public Services.

Please feel free to contact me if you have any questions.

Sincerely,

A handwritten signature in black ink, appearing to be 'DM', with a long horizontal line extending to the right from the end of the signature.

David Matero, AIA, LEED AP
DayMatero studio
207.671.6820

Cc: Justin Alford
Charlie Mitchell
Dale Akeley, Project Resources
Eric Dube, Casco Bay Engineering