FOODSERVICE EQUIPMENT SCHEDULE

MK.	QTY	DESCRIPTION	ELECTRICAL							WATER		WASTE		GAS		STEAM				VENTILATION				REMARKS
																				EXHAUST		MAKE–UP AIR		
			FLAMPS	KW	HP	VOLTS	PHASE	DIRECT	PLUG	COLD	HOT	DIRECT	INDIRECT	SIZE	MBTUH	LBS/HR	PSIG	INLET	RETURN	SIZE	CFM	SIZE	CFM	
1	2	HAND SINK (EXISTING)								1/2"	1/2"	1-1/2"												
2	1	SLANT RACK SHELF																						
3	1	DISHTABLE, SOILED								1/2"	1/2"	1-1/2"												
4	1	CONDENSATE HOOD	SEE EXHAUST HOOD DRAWINGS FOR ALL UTILITY, EXHAUST AND MAKE–UP AIR REQUIREMENTS																					
5	1	DISHWASHER WITH BOOSTER	46.3			208	3	X			3/4"	1-1/2"												
6	1	DISHTABLE, CLEAN W/POT SINKS								1/2"	1/2"	3@2"												
7	–	– SPARE NUMBER –																						
8	3	FRYER (2–EXISTING, 1–NEW)												3/4"	110									
9	–	– SPARE NUMBER –																						
10	1	CHARBROILER												3/4	144									
11	1	RANGE, 6–BURNER, 24–INCH–GRIDDLE												3/4"	336									
12	1	SALAMANDER BROILER												3/4"	40									
13	–	– SPARE NUMBER –																						
14	–	– SPARE NUMBER –																						
15	1	EXHAUST HOOD SYSTEM	SEE EXHAUST HOOD DRAWINGS FOR ALL UTILITY, EXHAUST AND MAKE–UP AIR REQUIREMENTS																					
16	–	– SPARE NUMBER –																						
17	–	– SPARE NUMBER –																						
18	1	REFRIG. SANDWICH UNIT (EXISTING)	8.8		1/3	120	1		X															
19	1	WORK TABLE WITH SINK								1/2"	1/2"		2"											
20	1	SLICER	3.9		1/3	120	1		X															
21	1	CHEF'S COUNTER (MILLWORK)																						
22	2	HEAT LAMP	9.2	1.1		120	1	X																
23	1	FREEZER, UNDERCOUNTER	7.4		1/3	120	1		X															
24	1	MICROWAVE OVEN	15.8	1.8		120	1		X															
25	1	HOT FOOD UNIT, DROP–IN	12.3	2.6		208	1	X					3/4"											
26	–	– SPARE NUMBER –																						
27	1	FREEZER, 2–SECTION	9.8		1/2	120	1		X															
28	1	REFRIGERATOR, 2–SECTION	9.1		1/3	120	1		X															
29	1	BEVERAGE COUNTER (MILLWORK)																						
30	2	WALL SHELF																						
31	1	ICED TEA BREWER (BY VENDOR)	14.8	1.8		120	1		X	1/4"														
32	1	COFFEE BREWER (BY VENDOR)		4.6		120/208	1	X		1/4"														
33	1	HAND SINK, DROP–IN								1/2"	1/2"		1-1/2"											
34	1	MOP SINK								1/2"	1/2"	2"												
35	1	ICE CREAM CABINET	5.7		1/4	120	1		X															
36	–	– SPARE NUMBER –																						
37	–	– SPARE NUMBER –																						
38	–	– SPARE NUMBER –																						
39	–	– SPARE NUMBER –																						
40	3	UNDERBAR, DRAINBOARD											1"											
41	–	– SPARE NUMBER –																						
42	–	– SPARE NUMBER –																						
43	3	UNDERBAR, SINK, 1–COMP								1/2"	1/2"	1"												
44	–	– SPARE NUMBER –																						
45	3	UNDERBAR, STORAGE CABINET											1"											
46	3	UNDERBAR, ICE BIN W/COLD PLATE											1/2"											
47	–	– SPARE NUMBER –																						
48	2	DISHWASHER, UNDERCOUNTER	36.4	6.0	3/4	208	1	X			3/4"	1-1/2"												
49	2	UNDERBAR, HAND SINK								1/2"	1/2"	1-1/2"												
50	1	UNDERBAR, 3–COMP. SINK								1/2"	1/2"	3@1"												
51	3	SPEEDRAIL, DOUBLE																						
52	–	– SPARE NUMBER –																						
53	1	SPEEDRAIL, SINGLE																						
54	3	BACK BAR COOLER	7.5		1/3	120	1		X															
55	–	– SPARE NUMBER –																						
56	–	– SPARE NUMBER –																						
57	–	– SPARE NUMBER –																						
58	1	BAG–IN–BOX RACK	15.0			120	1		X	1/2"														
59	1	ICE MACHINE WITH BIN	8.3		1	208	1	X		3/8"			2@3/4"											
60	13	DRY STORAGE SHELVING																						
61	1	WALK–IN COOLER	4.0			120	1	X																
62	1	EVAPORATOR COIL, COOLER	1.4			208	1	X					3/4"											
63	1	COMPRESSOR, COOLER	7.3		3/4	208	1	X																
64	1	WALK–IN FREEZER	4.0			120	1	X																
65	1	EVAPORATOR COIL, FREEZER	4.2	0.5		120	1		X				3/4"											
			5.8			208	1	X																
66	1	COMPRESSOR, FREEZER	8.4		2	208	3	X																
67	1	WALK–IN COOLER	4.0			120	1	X																
68	1	EVAPORATOR COIL, COOLER	1.4			208	1	X					3/4"											
69	1	COMPRESSOR, COOLER	5.8		1	208	3	X																
70	–	– SPARE NUMBER –																						
71	11	COOLER/FREEZER SHELVING																						
72	2	KEG STACKER, SHELVING																						

DayMatero studio

Architecture • Lighting Design

100 Front Street
Top Floor
Bath Maine US 04530
207.671.6819
info@daymatero.com

Plan N

Consultants

Casco Bay Engineering
Structural Engineer

Casco Bay Engineering
Civil Engineer

TJM Consulting
Food Service

Urban Dwellings
Interior Design

Revisions

.

Bowl Portland

58 Alder Street Portland, Maine

Job Number: 09.017
Date: 23.Nov.09

Drawing Title:

FOODSERVICE EQUIPMENT MECHANICAL SCHEDULE

FS-2

Copyright 2009, DayMatero studio LLC