


PLUMBING CONNECTION SCHEDULE

- P-1 1/2" COLD WATER, STUB OUT WALL AT 24"-AFF AND CONNECT AT ITEM 1, HAND SINK.
- P-1b 1/2" HOT WATER, STUB OUT WALL AT 24"-AFF AND CONNECT AT ITEM 1, HAND SINK .
- P-1c 1-1/2" DIRECT WASTE HUB, STUB OUT WALL AT 24"-AFF, CONNECT AT ITEM 1, HAND SINK.
- P-3 1/2" HOT WATER, STUB OUT WALL AT 14"-AFF AND CONNECT AT ITEM 3, DISHTABLE, SOILED .
- P-3b 1/2" COLD WATER, STUB OUT WALL AT 14"-AFF AND CONNECT AT ITEM 3, DISHTABLE, SOILED.
- P-3c 1-1/2" DIRECT WASTE HUB, STUB OUT WALL AT 14"-AFF, CONNECT AT ITEM 3, DISHTABLE, SOILED.
- P-5 1-1/2" DIRECT WASTE HUB, STUB OUT WALL AT 6"-AFF, CONNECT AT ITEM 5, DISHWASHER WITH BOOSTER.
- P-5b 3/4" HOT WATER, STUB OUT WALL AT 60"-AFF AND CONNECT AT ITEM 5, DISHWASHER WITH BOOSTER .
- P-6 1/2" HOT WATER, STUB OUT WALL AT 14"-AFF AND CONNECT AT ITEM 6, DISHTABLE, CLEAN.
- P-6b 1/2" COLD WATER, STUB OUT WALL AT 14"-AFF AND CONNECT AT ITEM 6, DISHTABLE, CLEAN.
- P-6c 2" DIRECT WASTE HUB, STUB OUT WALL AT 10"-AFF, CONNECT AT ITEM 6, DISHTABLE, CLEAN W/POT SINKS.
- P-8 1/2" GAS SUPPLY, 110-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 8, FRYER, DEEP FAT.
- P-10 3/4" GAS SUPPLY, 144-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 10, CHAR-BROILER.
- P-11 1" GAS SUPPLY, 368-MBTUH, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 11, RANGE, 6-BURNER, 24-INCH-GRIDDLE; LOOP SERVICE; ALSO SERVES CONNECT AT ITEM 12.
- P-19 FLOOR SINK, HALF-GRATE, 2" INDIRECT WASTE FROM ITEM 19, WORK TABLE WITH SINK.
- P-19b 1/2" HOT WATER, STUB OUT WALL AT 14"-AFF AND CONNECT AT ITEM 19, WORK TABLE WITH SINK .
- P-19c 1/2" COLD WATER, STUB OUT WALL AT 14"-AFF AND CONNECT AT ITEM 19, WORK TABLE WITH SINK.
- P-25 FLOOR SINK, THREE-QUARTER GRATE, 3/4" INDIRECT WASTE FROM ITEM 25, HOT FOOD UNIT, DROP-IN.
- P-31 1/4" COLD WATER, STUB OUT WALL AT 54"-AFF AND CONNECT AT ITEM 31, ICED TEA BREWER.
- P-32 1/4" COLD WATER, STUB OUT WALL AT 54"-AFF AND CONNECT AT ITEM 32, COFFEE BREWER.
- P-33 FLOOR SINK, HALF-GRATE, 1-1/2" INDIRECT WASTE FROM ITEM 33, HAND SINK, DROP-IN.
- P-33b 1/2" COLD WATER, STUB OUT WALL AT 14"-AFF AND CONNECT AT ITEM 33, HAND SINK, DROP-IN.
- P-33c 1/2" HOT WATER, STUB OUT WALL AT 14"-AFF AND CONNECT AT ITEM 33, HAND SINK, DROP-IN .
- P-34 1/2" HOT WATER, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 34, MOP SINK .
- P-34b 1/2" COLD WATER, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 34, MOP SINK.
- P-34c 3" HUB DRAIN, STUB UP 4"-AFF, 2" WASTE OUTLET, CONNECT AT ITEM 34, MOP SINK.
- P-40 FLOOR SINK, HALF-GRATE, 1" INDIRECT WASTE FROM ITEM 40, UNDERBAR, BRAINBOARD; ALSO SERVES ITEMS 43 & 46.
- P-43 1/2" HOT WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 43, UNDERBAR, SINK, 1-COMP .
- P-43b 1/2" COLD WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 43, UNDERBAR, SINK, 1-COMP.
- P-48 3/4" HOT WATER, STUB OUT WALL AT 8"-AFF AND CONNECT AT ITEM 48, DISHWASHER, UNDERCOUNTER .
- P-48b 1-1/2" DIRECT WASTE HUB, STUB OUT WALL AT 8"-AFF, CONNECT AT ITEM 48, DISHWASHER, UNDERCOUNTER.
- P-49 1-1/2" DIRECT WASTE HUB, STUB OUT WALL AT 12"-AFF, CONNECT AT ITEM 49, UNDERBAR, HAND SINK.
- P-49b 1/2" HOT WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 49, UNDERBAR, HAND SINK .
- P-49c 1/2" COLD WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 49, UNDERBAR, HAND SINK.
- P-50 1" DIRECT WASTE HUB, STUB OUT WALL AT 12"-AFF, CONNECT AT ITEM 50, UNDERBAR, 3-COMP. SINK.
- P-50b 1/2" HOT WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 50, UNDERBAR, 3-COMP. SINK .
- P-50c 1/2" COLD WATER, STUB OUT WALL AT 12"-AFF AND CONNECT AT ITEM 50, UNDERBAR, 3-COMP. SINK.
- P-58 1/2" COLD WATER, STUB OUT WALL AT 36"-AFF AND CONNECT AT ITEM 58, BAG-IN-BOX RACK.
- P-59 FLOOR SINK, HALF-GRATE, 3/4" INDIRECT WASTE FROM ITEM 59, ICE MACHINE WITH BIN.
- P-59b 3/8" COLD WATER, STUB OUT WALL AT 60"-AFF AND CONNECT AT ITEM 59, ICE MACHINE WITH BIN.
- P-62 FUNNEL TYPE FLOOR DRAIN, 3/4" INDIRECT WASTE FROM ITEM 62, EVAPORATOR COIL, COOLER; ALSO SERVES ITEMS 65.
- P-68 FUNNEL TYPE FLOOR DRAIN, 3/4" INDIRECT WASTE FROM ITEM 68, EVAPORATOR COIL, COOLER.



Consultants

Casco Bay Engineering
Structural Engineer

Casco Bay Engineering
Civil Engineer

TJM Consulting
Food Service

Urban Dwellings
Interior Design

Revisions

Bowl Portland
58 Alder Street Portland, Maine

Job Number: 09.017

Date: 23.Nov.09

1/4"=1'-0"

Drawing Title:

**FOODSERVICE
EQUIPMENT
PLUMBING
ROUGH-IN PLAN**

FS-4A