

ROOF/FLR TYPE	ROOF AND FLOOR ASSEMBLY TYPES	
	GENERAL WALL DESCRIPTION	GENERAL PICTORIAL

GENERAL FIRE RATINGS NOTES:

1. FIRE SAFING & FIRE STOPPING:
  - 1.1. PROVIDE FIRE SAFING SYSTEM/MATERIAL AT ALL PENETRATIONS THRU FIRE RATED ASSEMBLIES. COORDINATE PROPOSED SYSTEMS & MATERIALS FOR APPROPRIATENESS & COMPATIBILITY W/OTHER BLDG. SYSTEMS, TYPE OF SYSTEM PENETRATED, & APPLICATION.
  - 1.2. PROVIDE 2x SOLID BLOCKING AT CEILING LEVEL OR ALTERNATIVE METHOD APPROVED BY IBC 2003 IN UNIT COMMON WALLS.
  - 1.3. ALL PARTITIONING EXTENDING TO UNDERSIDE OF DECK OR CEILING SHALL BE INSTALLED UTILIZING A SLIP TRACK ALLOWING FOR 3/4" OF STRUCTURAL DEFLECTION. PROVIDE FIRE SAFING SYSTEM/MATERIAL AT TOP OF FIRE RATE PARTITIONS AS REQUIRED TO MAINTAIN THE FIRE RATED CLOSURE OF FIRE RATED PARTITION.
2. FIRE DAMPERS: PROVIDE APPROPRIATELY RATED FIRE DAMPERS AT ALL LOCATIONS WHERE MECHANICAL VENTILATION DUCTS PENETRATE RATED ASSEMBLIES.

PARTITION SCHEDULE NOTES

1. PROVIDE MOISTURE RESISTANT TYPE "MRX" GWB AT ALL WALL & CEILING SURFACES WITHIN ALL BATHROOMS, UTILITY ROOM & JANITOR'S CLOSETS. PROVIDE TYPE "MRX" GWB TO 4'-0" A.F.F. BEHIND ALL SINK LOCATIONS, TYPICAL. PROVIDE CEILING SUPPORT CHANNELS @ 16" O.C. AT ALL LOCATIONS WHERE MRX BOARD IS USED ON CEILINGS PER ASTM STANDARDS.
2. PROVIDE 5/8" GWB BEHIND ALL TUB & SHOWER @ FIRE RATED ASSEMBLIES & EXTERIOR WALLS. PROVIDE ADDITIONAL LAYER 5/8" GWB TO COVER TUB & SHOWER FLANGE. COORDINATE DOOR THROAT DEPTH ACCORDINGLY.
3. PROVIDE MIN. 1/2" CLEARANCE BETWEEN CONC. SLAB AND GWB. AND SEAL WITH ACOUSTIC SEALANT.
  - 3.1. PROVIDE SILL SEALER INSULATION FOR BOTH TOP & BOTTOM PLATES OF PARTITION FOR UNIT SEPARATION WALLS AND UNIT/CORRIDOR SEPARATION WALLS. TYPICAL.
4. BRACE WALL ASSEMBLIES TO STRUCTURE ABOVE AT ALL DOORS AND ELSEWHERE AS REQUIRED.
5. PROVIDE SOLID BLOCKING AS INDICATED ON DRAWINGS AND AS REQUIRED BY MANUFACTURER'S EQUIPMENT (KITCHEN CASE WORK, TOILET & BATH ACCESSORIES, CLOSET RODS & SHELVING & H.C. GRAB BARS.)
6. PROVIDE CONTINUOUS ACOUSTICAL SEALANT ALONG ALL PERIMETER BUILDING EDGES, UNIT SEPARATION WALLS & UNIT/CORRIDOR WALLS BETWEEN GWB AND THE SURROUNDING FLOOR, WALL & CEILING ELEMENTS.
7. PROVIDE CONTINUOUS ACOUSTICAL SEALANT AT ALL PENETRATIONS (I.E. ELECTRICAL BOXES, DUCTS, SPRINKLER HEADS, ETC.) IN WALLS, FLOORS, & CEILINGS. PROVIDE FIRE RATED SEALANT AT FIRE RATED WALL ASSEMBLIES, HILTI OR EQUAL.
  - 7.1. WHEN WALL DEVICES (I.E. ELECTRICAL OUTLETS, PIPES TELEPHONE JACKS, ETC.) OCCUR IN UNIT SEPARATION WALL, PROVIDE CONTINUOUS ACOUSTICAL SEALANT ALONG ALL PERIMETER EDGES AND BACKS OF DEVICES
  - 7.2. WHEN WALL PENETRATIONS (I.E. ELECTRICAL OUTLETS, PIPES TELEPHONE JACKS, ETC.) OCCUR ON OPPOSITE SIDES OF UNIT SEPARATION WALL, OFFSET PENETRATION BY AT LEAST ONE STUD CAVITY.
8. SEAL ALL PENETRATIONS IN VAPOR BARRIER, (EXTERIOR WALLS, ATTIC & CONCRETE SLAB-ON-GRADE) AS REQUIRED WITH APPROVED SEALERS, INSULATIONS AND TAPES.
9. REFERENCE FLOOR PLAN FOR SPECIFIC PARTITION NOTING AND DETAIL REFERENCING. REFERENCE SPECIFICATIONS FOR ADDITIONAL INFORMATION.



**CWS Architects**

**Architecture**  
 **Space Planning**  
 **Value Design**

434 Cumberland Avenue  
 Portland, ME 04101  
 Phone: (207)774-4441  
 Fax: (207)774-4016

[www.CWSarch.com](http://www.CWSarch.com)

Owner:  
**SOUTHERN MAINE STUDENT HOUSING LLC**  
 247 COMMERCIAL STREET  
 ROCKPORT, MAINE 04856  
 TEL: (207) 236-4067

Contractor:  
**PIZZAGALLI CONSTRUCTION**  
 100 FODEN RD WEST, SUITE 300  
 SOUTH PORTLAND, ME 04106  
 TEL: (207) 874-2323  
 FAX: (207) 874-2727

**BAYSIDE VILLAGE - A STUDENT HOUSING COMPLEX**

120 MARGINAL WAY  
 PORTLAND, MAINE

Project No: 2006-425BSV

Drawing Title:  
**PARTITION SCHEDULE FOR WALLS, CEILING & ROOF ASSEMBLIES**

Scale: NTS

Date: Progress 06/15/2007

Revisions:

- △
- △
- △
- △
- △
- △

Drawing Number:

**A0.01**