



**GENERAL NOTES**

UNDERSLAB CONDUITS SHALL BE LIMITED TO WHAT IS SHOWN ON UNDERSLAB & T101 PLAN.

ALL UNDERSLAB CONDUIT TO BE 1" PVC UNLESS NOTED OTHERWISE AND TO LOCATION INDICATED ON PLAN. EC SHALL LEAVE EXTRA PULL STRING IN CONDUIT TO GONDOLAS. SEE GONDOLA WIRING DETAIL THIS SHEET OR ELECTRICAL DETAILS PLAN.

EC TO MAINTAIN A MIN ELECTRICAL STUB UP DISTANCE OF 12" FROM REFRIGERATION PIT STUB UPS.

ALL NEW OR RELOCATED STUB UPS SHALL BE CORE DRILLED.

----- UNDERSLAB CONDUIT SHALL BE 1" PVC UNLESS NOTED OTHERWISE

----- GAS UNDERSLAB CONDUIT SHALL BE 1" U.N.D. (EC SHALL CONTINUE GAS CONDUIT FROM EACH CASE OR EACH CASE LINE-UP TO VENT 1/2" MODULE ON 1/2" GROUPING SCHEDULE AND INSTALL GAS CONDUIT W/PULL STRING). ALSO SEE REFRIGERATION PLAN & REFRIGERATION WIRING DETAILS FOR MORE INFORMATION

No.	Date	Revision
1	11/19/11	ISSUED FOR CONSTRUCTION
0	11/07/11	ISSUED FOR HANNAFORD 100K REVIEW

Project Title:

**REMODEL HANNAFORD SUPERMARKET & PHARMACY**  
**STORE #8351 - 295 FOREST AVENUE**  
**PORTLAND, MAINE 04101**

Hannaford Bros. Co.

Prepared By:

**JACOBS**  
 JACOBS ENGINEERING GROUP, INC. 04-001808  
 5700 Major Boulevard, Suite 400  
 Portland, ME 04103-2001  
 Phone: 407-903-5000 Fax: 407-903-5195

Seal:

ELECTRICAL ENGINEER OF RECORD  
 NAME: JOSEPH HARRILL, P.E.  
 MAINE REGISTERED PEI: 17107

DESIGNED BY: J. HARRILL  
 DRAWN BY: J. HARRILL  
 CHECKED BY: L. PEREZ

**UNDERSLAB PLAN**

Scale: 3/32" = 1'-0"  
 Date: 10/21/11

Drawing No. **E105**

Project No. **FRYR0300**

IBC - PORTLAND, ME

