


DIVERSIFIED
TESTING LABORATORIES, INC.
 330 WEST FRONT STREET
 PO BOX 4004
 BURLINGTON, NORTH CAROLINA 27210
 Phone (336) 227-7710 • Fax (336) 227-1178

January 9, 2003

Ms. Catherine HERRILLON
 FERRARI SA
 BP 54
 38553 LA TOUR DU PIN Cedex
 La Hure, France

Reference: Laboratory Test Report
 Lab Identification No. 5349
 Invoice No. A270 (Attached)


Dear Ms. HERRILLON:

One (1) fabric sample, identified as FRACONTRADIST 702, was received and tested in accordance with the National Fire Prevention Association No. 701, "Flame Propagation of Textiles and Films, 1999 Edition (Test 2, Large Scale)". The results are as follows:

Specimen Number	Aftersize (seconds)	Residual Flame (seconds)	Char Length (inches)
Single 1	0.0	0.0	10.0
Flat 2	0.0	0.0	11.0
Specimen 3	0.0	0.0	11.0
4	0.0	0.0	10.0
5	0.0	0.0	10.0
6	0.0	0.0	10.0
7	0.0	0.0	10.0
8	0.0	0.0	7.0
9	0.0	0.0	10.0
10	0.0	0.0	8.0

The sample submitted meets the minimum requirements of the above standard. The length of char on the individual single flat specimens shall not exceed 17.3 inches. Additionally, no specimen shall continue flaming for more than two (2) seconds after the test flame is removed and no residual shall fall to the floor of the test chamber and continue flaming for more than two (2) seconds at any time during the test.

If there are any questions or when we can be of further assistance, please let us know.

Sincerely,

 Karen S. Watkins

CSM/mr
 Attachment

OUR LETTERS AND REPORTS ARE FOR THE EXCLUSIVE USE OF THE CLIENT TO WHOM THEY ARE ADDRESSED. ANY COMMUNICATIONS BY OTHERS OR THE USE OF OUR COMPANY NAME MUST RECEIVE PRIOR APPROVAL. OUR TEST RESULTS APPLY ONLY TO THE SAMPLES TESTED AND ARE NOT NECESSARILY INDICATIVE OF THE QUALITIES OF ANY OTHERS. MATERIALS OR METHODS PROVIDED, SAMPLES NOT OBTAINED IN TESTING ARE RETURNED A MAXIMUM OF THREE DAYS. THE LETTERS REPORTS OR NAME OF DIVERSIFIED TESTING LABORATORIES, INC. MAY NOT BE USED BY ADVERTISERS TO THE GENERAL PUBLIC.

