



DIVERSIFIED

TESTING LABORATORIES, INC.

836 WEST FRONT STREET
PO BOX 4004
BURLINGTON, NORTH CAROLINA 27213
Phone (336) 227-7710 • Fax (336) 227-1176

"We Test Per Your Request"

January 9, 2003

Ms. Catherine MAILLON
FERRARI SA
BP 54
38391 La Tour Du Pin Cedex
La Mure, France

Reference: Substrate Test Report
Lab Identification No. 5349
Invoice No. R270 (Attached)

Dear Ms. MAILLON:

One (1) fabric sample, identified as **SECOCOMPROTECT 707**, was received and tested in accordance with the National Fire Protection Association No. 701, Flame Propagation of Textiles and Films, 1999 Edition (Text 2, Large Scale). The results are as follows:

Specimen Number	Absorbance (seconds)	Residual Flame (seconds)	Char Length (inches)
Single 1	0.0	0.0	10.0
Flat 2	0.0	0.0	11.0
Specimen 3	0.0	0.0	11.0
4	0.0	0.0	10.0
5	0.0	0.0	10.0
6	0.0	0.0	10.0
7	0.0	0.0	12.0
8	0.0	0.0	7.0
9	0.0	0.0	10.0
10	0.0	0.0	8.0

The sample submitted meets the minimum requirements of the above standard. The length of char on the individual single flat specimens shall not exceed 17.1 inches. Additionally, no specimen shall continue flaming for more than two (2) seconds after the test flame is removed and no particles shall fall to the floor of the test chamber and continue flaming for more than two (2) seconds at any time during the test.

If there are any questions or when we can be of further assistance, please let us know.

Sincerely,

Karen S. Watkins
Karen S. Watkins

KSK/mr
Attachment

OUR LETTERS AND REPORTS ARE FOR THE EXCLUSIVE USE OF THE CLIENT TO WHOM THEY ARE ADDRESSED. ANY COMMUNICATIONS TO OTHERS OR THE USE OF OUR REPORTS FOR ANY PURPOSES OTHER THAN THAT FOR WHICH THEY WERE TESTED ARE NOT WARRANTED. INDEMNITY BY THE CLIENT IS REQUIRED. RESULTS OF SERVICES PROVIDED, INCLUDING BUT NOT LIMITED TO TESTING AND SERVICES A MAJOR PORTION OF WHICH ARE PROVIDED BY THE CLIENT, ARE NOT TO BE USED IN ANY MANNER THAT MIGHT BE CONSIDERED AS ADVERTISING TO THE GENERAL PUBLIC.